

To access the Agenda and Backup Materials electronically, go to www.gjcity.org



**CITY COUNCIL AGENDA
WEDNESDAY, OCTOBER 2, 2019
250 NORTH 5TH STREET
5:15 PM – PRE-MEETING – ADMINISTRATION CONFERENCE ROOM
6:00 PM – REGULAR MEETING – CITY HALL AUDITORIUM**

To become the most livable community west of the Rockies by 2025

Call to Order, Pledge of Allegiance, Moment of Silence

Proclamations

Proclaiming October 6 - 12, 2019 as Fire Prevention Week in the City of Grand Junction

Proclaiming October 2019 as Arts and Humanities Month in the City of Grand Junction

Certificates of Appointment

To the Ridges Architectural Control Committee

To One Riverfront

Presentations

Letter of Appreciation Presented by Grand Junction Police Department

2018 Auditor's Report to City Council - Ty Holman, Haynie & Company

Citizen Comments

Individuals may comment regarding items scheduled on the Consent Agenda and items not specifically scheduled on the agenda. This time may be used to address City Council about items that were discussed at a previous City Council Workshop.

City Manager Report

Council Reports

CONSENT AGENDA

The Consent Agenda includes items that are considered routine and will be approved by a single motion. Items on the Consent Agenda will not be discussed by City Council, unless an item is removed for individual consideration.

1. Approval of Minutes

- a. Summary of the September 16, 2019 Workshop
- b. Minutes of the September 18, 2019 Regular Meeting
- c. Minutes of the September 18, 2019 Special Session

2. Set Public Hearings

All ordinances require two readings. The first reading is the introduction of an ordinance and generally not discussed by City Council. Those are listed in Section 2 of the agenda. The second reading of the ordinance is a Public Hearing where public comment is taken. Those are listed below.

- a. Legislative
 - i. Consider a Group of Actions Including 1) Introduce an Ordinance to Amend Multiple Sections of the Zoning and Development Code to Update the Transportation Capacity Payment and the Parks and Recreation Impact Fee and to Adopt New Impact Fees for Police, Fire and Municipal Facilities; and 2) Introduce an Ordinance Amending Ordinance No. 3641 Regarding the Growth and Development Related Streets Policy and Set Public Hearings for October 16, 2019

3. Contracts

- a. Change Order for 2019 Monument Road Bicycle Path (Lunch Loop Connector) Trail
- b. 2019 Community Development Block Grant Subrecipient Agreements between the Western Slope Center for Children and HomewardBound of the Grand Valley and the City of Grand Junction

4. Resolutions

- a. Resolution Adopting the Strategic Plan
- b. Resolution Authorizing the City Manager to Submit a Grant Request to Great Outdoors Colorado (GOCO) for a Local Park and Outdoor Recreation Grant for Land Acquisition of Approximately 21 Acres along Monument Road on Behalf of the Mesa County Land Conservancy, Inc. with the Trade Name of Colorado West Land Trust
- c. A Resolution Assigning City Councilmembers to Various Boards, Commissions, and Authorities

REGULAR AGENDA

If any item is removed from the Consent Agenda by City Council, it will be considered here.

5. Public Hearings

- a. Quasi-judicial
 - i. An Ordinance to Vacate a Portion of the East-West Alley Right-of-Way on the South Side of the Property Located at 845 Orchard Avenue

6. Non-Scheduled Citizens & Visitors

This is the opportunity for individuals to speak to City Council about items on tonight's agenda and time may be used to address City Council about items that were discussed at a previous City Council Workshop.

7. Other Business

8. Adjournment



City of Grand Junction, State of Colorado

Proclamation

- Whereas,** the City of Grand Junction is committed to ensuring the safety and security of all those living in and visiting Grand Junction; and
- Whereas,** fire is a serious public safety concern both locally and nationally, and homes are the locations where people are at greatest risk from fire; and
- Whereas,** home fires killed 2,630 people in the United States in 2017, and fire departments in the United States responded to 357,000 home fires; and
- Whereas,** the majority of U.S. fire deaths (4 out of 5) occur at home each year; and
- Whereas,** Grand Junction residents who have planned and practiced a home fire escape plan are more prepared and will therefore be more likely to survive a fire; and
- Whereas,** Grand Junction residents should practice using different ways out; and in a real emergency should get low and go under the smoke to get out quickly, and stay out, never going back inside the home for people, pets, or things; and
- Whereas,** the 2019 Fire Prevention Week theme, "Not Every Hero Wears a Cape. Plan and Practice Your Escape!" effectively serves to remind us that we need to take personal steps to increase our safety from fire.

NOW, THEREFORE, I, Rick Taggart, by the power vested in me as Mayor of the City of Grand Junction, do hereby proclaim October 6 - 12, 2019 as


"Fire Prevention Week"

in the City of Grand Junction and urge all citizens to find out how they can support "Fire Prevention Week" and develop a home fire escape plan at FPW.org.

IN WITNESS WHEREOF, I have hereunto set my hand and caused to be affixed the official Seal of the City of Grand Junction this 2nd day of October, 2019.



Mayor



City of Grand Junction, State of Colorado

Proclamation

- Whereas,** the nation's 95,000 nonprofit and 4,500 arts organizations, the arts and humanities councils in 50 states and six U.S. jurisdictions, the National Endowment for the Arts, and the National Endowment for the Humanities have regularly issued official proclamations designating October as National Arts and Humanities Month; and
- Whereas,** the arts and humanities embody much of the accumulated wisdom, intellect, and imagination of humankind while enhancing and enriching American lives by playing a unique role to our families, communities and country; and
- Whereas,** cities and states — through their local and state arts agencies and representing thousands of cultural organizations — have celebrated the value and importance of culture in the lives of Americans and the health of thriving communities during National Arts and Humanities Month for several years; and
- Whereas,** the humanities help diverse communities across the United States explore their history and culture with the support and partnership of the National Endowment for the Humanities, the 55 state and territorial humanities councils, and local educational and cultural institutions; and
- Whereas,** the arts and culture industry annually generates \$166.3 billion in total economic activity, \$26 billion in government revenue, and supports 5 million full-time jobs; and
- Whereas,** the creative economy drives tourism and commerce, supports American workers, and makes up 4.3% of the annual GDP, proposed federal legislation titled The CREATE Act (S. 650 and H.R. 1519) would support economic development of the creative economy.

NOW, THEREFORE, I, Rick Taggart, by the power vested in me as Mayor of the City of Grand Junction, do hereby proclaim October 2019 as

"National Arts and Humanities Month"

in the City of Grand Junction and call upon our citizens to celebrate and promote arts and culture and encourage greater participation for the arts and humanities in Grand Junction.



IN WITNESS WHEREOF, I have hereunto set my hand and caused to be affixed the official Seal of the City of Grand Junction this 2nd day of October, 2019.

Mayor



Grand Junction City Council

Regular Session

Item #

Meeting Date: October 2, 2019

Presented By: Wanda Winkelmann, City Clerk

Department: City Clerk

Submitted By: Wanda Winkelmann

Information

SUBJECT:

To the Ridges Architectural Control Committee

RECOMMENDATION:

Present the new volunteer with their Certificate of Appointment.

EXECUTIVE SUMMARY:

There is one new member to the Ridges Architectural Control Committee.

BACKGROUND OR DETAILED INFORMATION:

Robert M. Stubbs was appointed by City Council at their September 18, 2019 Regular Meeting.

FISCAL IMPACT:

N/A

SUGGESTED MOTION:

N/A

Attachments

None



Grand Junction City Council

Regular Session

Item #

Meeting Date: October 2, 2019

Presented By: Wanda Winkelmann, City Clerk

Department: City Clerk

Submitted By: Wanda Winkelmann

Information

SUBJECT:

To One Riverfront

RECOMMENDATION:

Present the newly appointed members with their Certificates of Appointment.

EXECUTIVE SUMMARY:

There are two reappointed members and two new members to One Riverfront.

BACKGROUND OR DETAILED INFORMATION:

Elaine Heath and Catherine Ventling were reappointed, and Dave Bastian was appointed by City Council at their August 7, 2019 Regular meeting. Lewis Patterson was appointed by City Council at their September 3, 2019 Regular Meeting.

FISCAL IMPACT:

N/A

SUGGESTED MOTION:

N/A

Attachments

None



Grand Junction City Council

Regular Session

Item #

Meeting Date: October 2, 2019

Presented By: Doug Shoemaker, Chief of Police

Department: Police

Submitted By: Doug Shoemaker

Information

SUBJECT:

Letter of Appreciation Presented by Grand Junction Police Department

RECOMMENDATION:

Presentation of letter.

EXECUTIVE SUMMARY:

The Grand Junction Police Department will present a "Letter of Appreciation" to civilian Marcus Alexander.

BACKGROUND OR DETAILED INFORMATION:

On July 2, while on his way to work, citizen Marcus Alexander stopped and helped a juvenile in distress. Because of the positive interaction between the two, the juvenile climbed down from the top of a bridge onto a walkway and joined Mr. Alexander. Mr. Alexander very well may have saved her life and the Grand Junction Police Department would like to formally recognize Mr. Alexander's actions and willingness to assist.

FISCAL IMPACT:

N/A

SUGGESTED MOTION:

No motion is required for this item.

Attachments

1. Letter of Appreciation



October 2, 2019

Mr. Marcus Alexander
529 Colorado Avenue
Grand Junction, CO 81501

On July 2, 2019 at approximately 4:17 p.m., officers with the Grand Junction Police Department requested the Mesa County Sheriff's Office Co-Responder Unit to respond to the area of the Riverside Parkway pedestrian bridge. This request was made in regard to a possible suicidal subject who was standing on top of the bridge structure.

Upon arrival in the area, officers could not immediately locate anyone on or below the pedestrian bridge. After searching the area under the Hwy 340 bridge an officer located a subject sitting on top of the pedestrian bridge directly over Crosby Avenue. The subject had climbed onto the bridge and it was obvious that the subject was in emotional distress.

As officers continued to assess the situation, they noticed a person riding his bicycle southbound on Crosby Avenue. This person stopped and left his bicycle near the pedestrian bridge, ascended the stairs and was in verbal communication with the juvenile subject on the bridge. The juvenile's emotional demeanor did not appear to be exacerbated by the presence of the bystander. Because of the positive interaction between the two, officers decided to monitor the contact. After approximately 12 minutes, the juvenile climbed down onto the walkway and joined the bystander.

Once the situation had been resolved and the juvenile was cared for, officers determined that you, Marcus Alexander, were the person who chose to stop and help someone who, that prior to that day, didn't even know. You recognized the juvenile was in distress, and although on your way to work, you stopped and made a difference. Whatever you said to this person on the afternoon of July 2nd may have very well saved her life.

In recognition of your support and courage, I am honored to present you with this Letter of Appreciation. I commend you for your quick action and willingness to assist. Your efforts to keep our community safe speaks volumes about your character and were critical to the successful outcome of this situation.

Sincerely,

A handwritten signature in black ink, appearing to read "Doug Shoemaker", with a long horizontal flourish extending to the right.

Doug Shoemaker
Chief of Police



Grand Junction City Council

Regular Session

Item #

Meeting Date: October 2, 2019

Presented By: Greg Caton, City Manager

Department: Finance

Submitted By: Jodi Romero, Finance Director

Information

SUBJECT:

2018 Auditor's Report to City Council - Ty Holman, Haynie & Company

RECOMMENDATION:

This is a presentation to City Council.

EXECUTIVE SUMMARY:

Haynie & Company is the City Council's independent auditor. Each year the City's financial statements are audited in connection with the issuance of the Comprehensive Annual Financial Report.

The auditor works directly for the City Council. Ty Holman, Partner at Haynie & Company conducts the City's audit and he will report the audit results to the City Council. This report will include that the City again received a "clean" opinion which means the financial statements present fairly, in all material respects, the financial position of the City.

BACKGROUND OR DETAILED INFORMATION:

The City of Grand Junction 2018 CAFR is available on-line.

FISCAL IMPACT:

N/A

SUGGESTED MOTION:

I move to (accept/not accept) the Auditors Report and Financial Statements for the City

of Grand Junction, Colorado for the year ended December 31, 2018.

Attachments

None

GRAND JUNCTION CITY COUNCIL WORKSHOP SUMMARY

September 16, 2019

Meeting Convened: 5:30 p.m. in the City Hall Auditorium

Meeting Adjourned: 6:54 p.m.

City Councilmembers present: Councilmembers Kraig Andrews, Chuck McDaniel, Phyllis Norris, Phil Pe'a, Duke Wortmann, and Mayor Rick Taggart.

Staff present: City Manager Greg Caton, City Attorney John Shaver, Finance Director Jodi Romero, Public Works Director Trent Prall, Sr. Assistant to the City Manager Greg LeBlanc, and City Clerk Wanda Winkelmann.

Agenda Topic 1. Discussion Topics

a. Xcel Energy Update

Mr. Caton introduced Kelly Flenniken, Area Manager with Xcel Energy. Ms. Flenniken provided updates on:

1. Colorado Energy Plan
2. December 2018 Carbon Announcement
3. 2019 Electric Rate Cast
4. Electric Vehicles

Ms. Flenniken shared Xcel's *Community Report*, which describes carbon emissions, street light conversions to LEDs, and the energy supply. Street light outages are generally fixed within five days.

As a way to give back to the community, Xcel Energy participates in Day of Service, United Way, and Corporate Giving. Xcel also helped relocate a transmission line in the Dos Rios development.

Discussion ensued about the number of crews working on the 7th Street project; the demand for linemen service; residential installs occurring only weekly; the perception of Xcel's mission; and possible LED conversion of ball park lights. Ms. Flenniken was complimentary of the Public Works department.

b. Broadband Update

Mr. Caton introduced the topic.

Mr. John Lee with Charter Communications reviewed the current status of the offering of Broadband providers. Over \$32 billion was invested nationwide for the Broadband infrastructure; \$456 million in 2018 in Colorado in infrastructure upgrades. Upgrades were done with minimal disruption to infrastructure.

Steve Fullerton with Unite Private Networks noted they started with upgrades for District 51 and it is now a 10-gig network. Additionally they have added 30 new cell sites and 9000 miles of fiber in the valley and serve 7000 customers. Unite continues to work with existing companies to upgrade their services.

Rock Johansen with Emery Telcom stated a large partner is putting in new fiber between Salt Lake City and Denver along Interstate 70 with a completion date May 2021.

Discussion ensued about service in Montrose as a rural area; the State Broadband map; Federal policy to provide incentives to rural areas; and other municipalities who provide Broadband to their citizens.

Diane Swenke, Chamber of Commerce Executive Director, said the business community is being served very well in this area and the available Broadband is not a barrier for business expansion.

Agenda Topic 2. Next Workshop Topics

Mr. Caton reported the September 30 workshop (which starts at 4:00 p.m.) is a presentation of the City Manager's recommended budget.

3. Other Business

Discussion ensued about future revenues and growth and the impact on the 2020 budget. Mr. Caton stated that the budget Council will be presented is modest.

Mayor Taggart reviewed a recent concern expressed by a citizen about possible mill tailings at the high school. A radon test of the property will be conducted and, if any concerns are found, the soils will be removed and the property remediated accordingly.

Adjournment

The workshop adjourned at 6:54 p.m.

GRAND JUNCTION CITY COUNCIL MINUTES OF THE REGULAR MEETING

September 18, 2019

Call to Order, Pledge of Allegiance, Moment of Silence

The City Council of the City of Grand Junction convened into regular session on the 18th day of September, 2019 at 6:00 p.m. Those present were Councilmembers Kraig Andrews, Chuck McDaniel, Phyllis Norris, Phillip Pe'a, Anna Stout, Duke Wortmann and Council President Rick Taggart.

Also present were City Manager Greg Caton, City Attorney John Shaver, City Clerk Wanda Winkelmann and Deputy City Clerk Janet Harrell.

Council President Taggart called the meeting to order. Councilmember Andrews led the Pledge of Allegiance which was followed by a moment of silence.

Council President Taggart announced Direct Support Professional Week and R.E.D. Friday Hero Day.

Appointments

To the Ridges Architectural Control Committee

Councilmember Wortmann moved to appoint Robert Stubbs to the Ridges Architectural Control Committee. Councilmember Norris seconded the motion. Motion carried by unanimous voice vote.

Citizen Comments

Richard Swingle spoke about broadband.

City Manager Report

City Manager Caton said Forensic Science Week is September 15 - 21, 2019 and recognized those in the Grand Junction Police Department who perform these roles. He also announced the Las Colonias River Park Ground Breaking Ceremony will be held on September 24, 2019.

Council Reports

Councilmember Stout spoke against the vandalism at the Islamic Center of Grand Junction - Two Rivers Mosque.

Councilmember McDaniel said the Grand Junction Regional Airport Authority Board authorized the Administration building to be razed, which was the most cost effective option.

Councilmember Wortmann attended the Community Hospital Gala and received encouraging feedback from new City residents.

Council President Taggart attended the Community Hospital Gala, the Hispanic Heritage Month Kick-Off Celebration and a fundraiser for the Colorado National Monument Amphitheater.

CONSENT AGENDA

Councilmember Andrews moved to adopt Consent Agenda items #1 - #3. Councilmember Wortmann seconded the motion. Motion carried by unanimous voice vote.

1. Approval of Minutes

- a. Minutes of the September 4, 2019 Regular Meeting

2. Set Public Hearings

- a. Legislative
 - i. Introducing an Ordinance Amending Industrial Pretreatment Regulations Title 13 of the Grand Junction Municipal Code Section 13.04.370 Regarding Limits for Metals in Industrial Wastewater Discharge and Set a Public Hearing for November 6, 2019
- b. Quasi-judicial
 - i. A Resolution Referring a Petition to the City Council for the Annexation of Lands to the City of Grand Junction, Colorado, Setting a Hearing on Such Annexation, Exercising Land Use Control, and Introducing Proposed Annexation Ordinance for the Adams II Annexation of 1.999-Acres, Located at 216 27 ½ Road and Set a Public Hearing for November 6, 2019
 - ii. Introduction of an Ordinance to Vacate a Portion of the East-West Alley Right-of-Way on the South Side of the Property Located at 845 Orchard Avenue and Set a Public Hearing for October 2, 2019
 - iii. A Resolution Referring a Petition to the City Council for the Annexation of Lands to the City of Grand Junction, Colorado, Setting a Hearing on Such Annexation, Exercising Land Use Control, and Introducing Proposed Annexation Ordinance for Zona's Annexation of 2.0 Acres, Located at 408 29 Road and Set a Public Hearing for November 6, 2019

3. Contracts

- a. 2019 CDBG Subrecipient Agreements between the Counseling and Education Center, Riverside Educational Center, Mesa Youth Services dba Mesa County Partners, Marillac Clinic, and STRiVE and the City of Grand Junction

REGULAR AGENDA

A Resolution Supporting District 51 Board of Education Ballot Issue 4A

The purpose of this item is to declare support for District 51 Board of Education ballot issue 4A.

The citizen comment period opened at 6:17 p.m.

Scott Beilfuss and Rick Peterson spoke in favor of the issue.

The citizen comment period closed at 6:20 p.m.

Council discussion included school safety, the transparency and accountability of the District's current Administration and Board, the District's capital needs, the economic development potential of a well-educated and skilled work force and that any mill tailing issues would be addressed.

Councilmember Wortmann moved to adopt Resolution No. 61-19, a resolution supporting District 51 Board of Education Ballot Issue 4A. Councilmember Norris seconded the motion. Motion carried by unanimous roll call vote.

An Ordinance to Rezone the Community Pod 5 from Mixed Use to Planned Development and Approve an Outline Development Plan for Approximately 39.25 Acres at 2372 G Road

The applicant Club Deal 127 Merk Grand Junction, LP requested approval of a rezone of 39.25 acres located at 2372 G Road to Planned Development (PD) with a default zone of Business Park and approval of an Outline Development Plan to be known as The Community Pod 5. The property is currently zoned Mixed Use.

This rezone request to PD is complementary to the "The Community", a Mixed Use Planned Development that received Council approval for four development pods on May 15, 2019. Pod 5 is proposed to allow single-family, multi-family, business and commercial land uses in a mixed use development.

Principal Planner Dave Thornton presented this item.

The public hearing opened at 6:42 p.m.

Joseph Coleman, represented owners of Pods 1 - 4, spoke in favor of this item.

The public hearing closed at 6:43 p.m.

Discussion included the definition of accessory dwellings and the type of allowed units for properties with a proposed width of 20 feet.

Councilmember Andrews moved to adopt Ordinance No. 4875, an ordinance zoning the Club Deal 127 Merk Grand Junction, LP Development to a PD (Planned Development) Zone, by approving an Outline Development Plan for POD 5, with a default zone of BP (Business Park Mixed Use), located at 2372 G Road on final passage and ordered final publication in pamphlet form. Councilmember Wortmann seconded the motion. Motion carried by unanimous roll call vote.

An Ordinance Amending Ordinance No. 4861 to Change the Name of the Grand Junction Dos Rios General Improvement District to the City of Grand Junction Dos Rios General Improvement District

The purpose of this item is to amend Ordinance No. 4861 regarding the name of the Dos Rios General Improvement District.

City Attorney John Shaver presented this item.

The public hearing opened at 6:47 p.m.

There were no public comments.

The public hearing closed at 6:48 p.m.

Councilmember Wortmann moved to adopt Ordinance No. 4876, an ordinance of the City of Grand Junction, Colorado, amending a portion of Ordinance No. 4861 to change the name of the Grand Junction Dos Rios General Improvement District to the City of Grand Junction Dos Rios General Improvement District on final passage and ordered final publication in pamphlet form. Councilmember Norris seconded the motion. Motion carried by unanimous roll call vote.

Non-Scheduled Citizens & Visitors

There were none.

Other Business

There was none.

Adjournment

The meeting adjourned at 6:49 p.m.

Wanda Winkelmann, MMC
City Clerk

GRAND JUNCTION CITY COUNCIL

SPECIAL SESSION MINUTES

September 18, 2019

The City Council of the City of Grand Junction, Colorado met in Special Session on Wednesday, September 18, 2019 at 5:00 p.m. in the Administration Conference Room, 2nd Floor, City Hall, 250 North 5th Street. Those present were Councilmembers Kraig Andrews, Chuck McDaniel, Phyllis Norris, Phillip Pe'a, Anna Stout, Duke Wortmann (arrived at 5:06 p.m.), and Mayor Rick Taggart.

Staff present for the Executive Session were City Manager Greg Caton and City Attorney John Shaver.

Councilmember McDaniel moved to go into Executive Session:

TO DISCUSS UNDER C.R.S. 24-4-402(4)(b) OF THE COLORADO OPEN MEETINGS LAW TO CONFER WITH AND RECEIVE LEGAL ADVICE FROM THE CITY ATTORNEY REGARDING THE CITY'S POSITION AND STRATEGY(IES) RELATIVE TO THE AUGUST 29, 2019 NOTICE OF CLAIM FROM BRUNO, COLIN & LOWE REGARDING RETIREE HEALTH INSURANCE

Councilmember Norris seconded the motion. Motion carried unanimously.

The City Council convened into Executive Session at 5:04 p.m.

Councilmember Stout moved to adjourn. Councilmember Andrews seconded. Motion carried unanimously.

The meeting adjourned at 5:37 p.m.

Wanda Winkelmann
City Clerk



Grand Junction City Council

Regular Session

Item #2.a.i.

Meeting Date: October 2, 2019

Presented By: Greg Caton, City Manager, Trent Prall, Public Works Director, Tamra Allen, Community Development Director

Department: Community Development

Submitted By: Tamra Allen, Community Development Department Director

Information

SUBJECT:

Consider a Group of Actions Including 1) Introduce an Ordinance to Amend Multiple Sections of the Zoning and Development Code to Update the Transportation Capacity Payment and the Parks and Recreation Impact Fee and to Adopt New Impact Fees for Police, Fire and Municipal Facilities; and 2) Introduce an Ordinance Amending Ordinance No. 3641 Regarding the Growth and Development Related Streets Policy and Set Public Hearings for October 16, 2019

RECOMMENDATION:

The Planning Commission heard this at their September 24, 2019 meeting and recommended to not approve the full staff recommendation. However, many Planning Commissioners expressed support for the full implementation of impact fees for transportation and parks and recreation.

EXECUTIVE SUMMARY:

In July 2018, City Council provided direction to staff to conduct a study for the impact fees related to a variety of city capital facilities. In the Fall of 2018, the City contracted with TischlerBise a consultancy that conducts impact fee studies across the country. TischlerBise has provided a study for the maximum fee potential new impact fees related to police, fire and municipal facilities. Included in their study is an update for Parks Impact Fees, fees that have not been updated for more than 35 years.

Prior to the work with TischlerBise, the Grand Valley Metropolitan Planning Organization (GVMPO) had contracted with Duncan Associates to update the Transportation Impact Fees within the Grand Valley, including Mesa County, the City of

Grand Junction, the City of Fruita and the Town of Palisade. An impact fee study was last conducted for transportation in 2002 and were, at that time, adopted at 52 percent of the recommended rate.

BACKGROUND OR DETAILED INFORMATION:

PURPOSE OF IMPACT FEES

Impact fees are one-time payments for new development's proportionate share of the capital cost of infrastructure. TischlerBise, on behalf of the City, has drafted an impact fee study for fire, police, municipal facilities and parks and recreation pursuant to the State enabling legislation and consistent with Colorado Revised Statutes regarding the purpose and methodology related to calculation of impact fees. The study specifically addresses the City of Grand Junction's Municipal Facilities, Fire, Police, and Parks and Recreation facilities.

Impact fees have limitations and should not be regarded as the total solution for infrastructure funding. Rather, they are one component of a comprehensive funding strategy to ensure provision of adequate public facilities. Impact fees may only be used for capital improvements or debt service for growth-related infrastructure. They may not be used for operations, maintenance, replacement of infrastructure, or correcting existing deficiencies.

IMPACT FEE STUDIES

The regional Grand Valley Metropolitan Planning Organization (GVMPO) completed an update to their 2002 Transportation Impact Fee study in Fall of 2018. The report was authored by Duncan Associates and recommended a significant increase in transportation impact fees, known as Transportation Capacity Payments (TCP).

In July 2018, the City Council directed staff to engage a separate consultant to conduct a nexus study for development impact fees for Fire, Police, Municipal Facilities and Parks. The City engaged the consultant TischlerBise in this effort and a report was completed in April 2019. The report found that a substantial fee could be assigned to growth's share of maintaining capacity at today's level of service in the capital facilities related to Fire, Police and Municipal Facilities. The report also recommended a significant increase in the Parks and Recreation Impact Fee.

Originally, the TCP was proposed to be adopted first, followed by discussion regarding the other impact fees, however concern was expressed during the Planning Commission's March 26, 2019 hearing that all the fees (TCP, Fire, Police, Municipal Facilities and Parks) be heard together. As a result, the TCP fees were withdrawn from hearing at the City Council's May 1, 2019 meeting.

OUTREACH

Since May 2018, staff has been working with a variety of stakeholders including

representatives from the Chamber of Commerce, Western Colorado Contractor's Association, Homebuilders of Western Colorado (HBA), Associated Members of Growth and Development (AMGD), and Grand Junction Area Realtors Association (GJARA) to identify an implementation program for the fees that would be mutually agreeable between all stakeholders. The group has met five times since May to discuss this topic.

Staff met with stakeholders multiple times between May and the end of July to discuss and negotiate the fee structure, keeping in mind that any fee would need to be defensible and its methodology aligned with a fee study. Based on these discussions and work sessions, negotiations resulted in several deviations from the original fee studies, based on the direct input from stakeholders. These changes were founded on additional work and analysis provided by either TischlerBise or Duncan Associates to ensure the methodology for the fee was legally defensible. The changes included:

§ Creating a fee for single-family that was stratified by size. This resulted in a decreased fee for smaller units to address issues expressed about affordability/attainability of homes based on price.

§ Reducing the Multi-family TCP to be consistent with the smallest single-family residential category to ensure parity between use types.

§ Compressing TCP fees for commercial into six categories. This resulted in a significant decrease in the collection of commercial TCP for specific uses such as medical offices.

§ Also, as a result of the passage of 2B, costs for vehicles for police were removed from the capital needs calculation.

The discussions with the industry stakeholders and workshop input resulted in the recommendations herein proposed by staff regarding fees and implementation schedule.

In advance of the August 5 workshop, the industry stakeholder group submitted a letter acknowledging that fees need to be updated but requesting fees for transportation and parks and recreation be updated at a rate of 50% of the proposed increase. They also requested that no fees be adopted for Fire, Police and Municipal Facilities.

The updated TCP study was presented to City Council and Planning Commission at a December 3, 2018 workshop and at a work with both City Council and Planning Commission held on March 4, 2019. Subsequent workshops have been held on impact fees in June, August and September, 2019.

EXISTING TRANSPORTATION CAPACITY PROGRAM

In 2004, the City adopted Ordinance No. 3641 that provided the approach for calculation and collection of the City's Transportation Capacity Payment (TCP) fee. The TCP was modeled so that the City would pay for improvements to the street system that either provided capacity to the system or added safety improvements. The streets identified for the use of the TCP funds were only those streets shown on the adopted Grand Valley Circulation Plan functional classification map and that were considered part of the City's Major Street System. Though the Streets Policy required the City to pay for safety improvements (such as turn lanes or traffic signals) those costs were not included in the calculation of the TCP fee. The TCP fees and methodology were based on a fee study conducted by Duncan and Associates in 2002. The fees were originally adopted at a rate of 52% of what was recommended by the study. The fee was to be adopted annually by resolution of the Council and be adjusted annually for inflation in the Consumer Price Index. This has not happened regularly. Since adoption in 2004, the City adjusted the fee for residential development (based on the CPI) from \$1,500 to \$1,589 between 2004 and 2007 then to its current fee of \$2,554 in 2008 but which have not been adjusted since. The TCP fee for Commercial development was originally adopted at a rate of \$2,461 per 1,000 square feet (e.g. Shopping Center) and was adjusted upwards in 2008 to \$2,607 and then in 2013, 2014 and 2015 to a rate of \$4,189 per 1,000 square feet (e.g. Shopping Center) that is being collected today.

REDEVELOPMENT AREA INCENTIVE (TCP)

In 2013 the City Council adopted Resolution 15-13, which provided for infill and redevelopment incentives. Within the defined redevelopment area TCP fees were reduced. The boundary included Downtown, the river district area as well as the North Avenue corridor between State Highway 6 & 50 and I-70 Business Loop. It was intended to encourage development of infill parcels and redevelopment of underutilized land within certain areas of the City. The Redevelopment Area provides for significant incentive for redeveloping these area, especially if building more than one story. For example, a four-story hotel of 96 rooms outside of the redevelopment area today would pay a fee of \$231,072, while if it is constructed inside of the redevelopment area the fee would equate to \$28,884 (the formula = # of rooms x \$2,407 / 2 divided by # of stories). Staff is recommending maintaining the Redevelopment Area incentive as currently adopted.

GROWTH AND DEVELOPMENT RELATED STREETS POLICY

At the same time the City adopted updated TCP fees in 2004, the City adopted a Growth and Development Related Streets Policy. At that time the City determined that there were three key components to a meaningful growth and development related street/traffic policy. These included: 1. Collection of a realistic TCP fees for all new development projects, 2. A clear articulation of what minimum requirements (in addition to TCP fees) each development must construct; and, 3. City funding and/or other means of participation in construction of street improvements. The 2004 policy replaced

the previous policy that required developers to pay for the improvement of the half of the street(s) that was directly abutting their project ("half street improvements") and eliminated the need for the developer to build any safety improvements (e.g., turn lanes into their development) as well as eliminated any need for the developer to pay for any off-site improvements (e.g., intersection improvements and traffic signals). As the Policy and Fees are today, there are significant implications for how the City funds street capacity and safety improvements. Those include:

- 1) The City pays for all safety improvements, even those related to a specific development and benefiting only a specific development(s).
- 2) The obligation to improve that street (Collector designation or higher) is carried in full by the City – even if the improvements are necessary for access to a specific development. Only if the street is considered a "local or unclassified" street is the developer required to construct it.

The net effect has been two-fold, whereas:

- 1) The City carries the full cost of improving/constructing all streets (classified higher than local) and
- 2) The City finds itself moving capital dollars towards certain street projects to serve specific development, but that may not be of the greatest overall community benefit or need.

In a survey of other jurisdictions, staff found that cities almost always require the developer to pay for the adjacent street to be developed to a local street standard (or that are adequate to serve the development) including curb, gutter and sidewalk and then the city pays the portion of the cost required to "upscale" the street to a higher classification (e.g., collector or arterial, etc.). In addition, other cities require all safety improvements such as acceleration and deceleration lanes to be constructed as part of a development. Both on-site safety improvements (eg. Turn lanes to/from development) and off-site safety improvements (eg. signalized intersection a few blocks away) are generally required. Staff is recommending repealing the previous Growth and Development Related Streets Policy and modifying the language within the Zoning and Development Code to require developments to construct safety improvements related to the specific development. As discussed with industry stakeholder's this requirement would be implemented beginning January 1, 2021 to allow for the industry to prepare for this change.

EXISTING PARKS IMPACT FEE

The City currently has a Parks impact fee of \$225 that is collected per residential unit. This fee has been in place for more than 35 years and has not been updated since

initial adoption. The TischlerBise study found that a significant increase in this fee is warranted in order for park and recreation capital improvements to maintain the existing level of service for the City related to parks and recreation. Since residents utilize parks, a Parks and Recreation fee is only charged to residential uses. Staff is recommending implementation of the full Parks and Recreation fee over three years in equal annual increases starting January 1, 2020.

NEW IMPACT FEES (FIRE, POLICE, MUNICIPAL FACILITIES)

As directed by City Council in July 2018, an impact fee study included an analysis for the capital needs of Police, Fire and Municipal Facilities related to the impacts of growth on capital needs of these facilities. The study found that fees could be charged to growth to maintain the existing level of service for these facilities. Staff is recommending implementation of the full Fire, Police and Municipal Facilities fees over three years in equal annual increases starting January 1, 2020.

STAFF RECOMMENDATIONS

Staff recommends adopting the fee schedules as attached as well as the following implementation schedule:

Transportation Capacity Payments (TCP)

- a. Fee increases for TCP will begin January 1, 2020
- b. The City will implement the full fees over 3 years in equal biannual increases.
- c. After full implementation the fee will increase by a 10-year rolling average of CDOT's Construction Cost Index.
- d. For Single-Family (detached and attached) dwelling units, full fees will be collected at time of Planning Clearance.
- e. For Multi-Family dwelling units, excluding those intended to be separate fee simple ownership (eg. Duplex, Townhomes, Condominiums), implement the full fee. The fee would be established at time of complete application submittal and would be valid so long the project commenced construction within two years from the date of application submittal.
- g. Payment of fees will no longer be considered for deferral. Parks is currently the only City impact fee that cannot be deferred.
- h. The City will retain its Redevelopment Area boundary that provides for significant reductions in TCP fees for development in this area where street infrastructure is in place.

Fire, Police, Municipal Facilities, and Parks

- a. Fee increases for Parks and Recreation and new fees for Fire, Police, Municipal Facilities will begin January 1, 2020
- b. The City will implement the full fees over 3 years in equal increases.
- c. After full fee implementation, the fee will increase annually by the Construction Cost Index published by Engineering News Record.
- d. For Single-Family (detached and attached) dwelling units, full fees will be collected at time of Planning Clearance.
- e. For Multi-Family dwelling units, excluding those intended to be separate fee simple ownership (eg. Duplex, Townhomes, Condominiums), implement the full fee. The fee would be established at time of complete application submittal and would be valid so long the project commenced construction within two years from the date of application submittal.
- g. Payment of fees will no longer be considered for deferral. Parks is currently the only City impact fee that cannot be deferred.

Safety Improvements

- a. Commencing January 1, 2021, development such as a subdivision in which traffic warrants safety improvements (eg. Turn lane and deceleration lanes) for a development (as determined by a traffic study or similar methodology) will be required to make necessary safety improvements.
- b. Should the improvements benefit future adjacent development, a cost reimbursement agreement may be executed on behalf of the developer for a period up to 10 years.

NOTIFICATION REQUIREMENTS

Notice was completed as required by Section 21.02.080(g). Notice of the public hearing was published on September 14, 2019, in the Grand Junction Daily Sentinel.

ANALYSIS

In accordance with Section 21.02.140(c), a proposed text amendment shall address in writing the reasons for the proposed amendment. There are no criteria for review because a code amendment is a legislative act within the discretion of the City Council. Reasons for the proposed amendments are provided in the Background section of this report.

STAFF RECOMMENDATION AND FINDINGS OF FACT

In accordance with Section 21.02.140(c) of the Zoning and Development Code, the reasons for the amendment have been adequately addressed and include but are not limited to the amendments being necessary for growth to pay a proportionate share of the cost of capital facilities to maintain adequate level of service for Fire, Police, Municipal Facilities, Parks and Recreation and Transportation and to provide mechanisms which will allow for the construction of safety improvements concurrent with development. Staff therefore recommends approval of the proposed amendments to the Zoning and Development Code.

FISCAL IMPACT:

The fiscal impact of impact fees is driven by growth which results in needed improvements and expansion of facilities. The needs and the related impact fee revenue are only generated if growth occurs. Following is a comparison of the revenue and costs generated from growth. In each case the revenues from impact fees only pay a portion of the cost.

Currently the City receives on average \$1.5 million per year in Transportation Impact Fees (aka Transportation Capacity Payments). At full implementation, the anticipated revenue is estimated at approximately \$3.5 million per year. With a three-year implementation schedule, \$2 million in TCP revenues will be lost. Over a 10-year period based on growth assumptions, the revenue generated from impact fees will cover approximately one-third of the cost of expansion improvements as a result of growth.

The City currently collects an average of \$350,000 per year in Parks impact fees. At full implementation, the anticipated revenue is estimated at approximately \$569,000 per year. With a three-year implementation schedule, \$487,000 in Parks and Recreation impact fee revenues will be lost. Over a 10-year period based on growth assumptions, the revenue generated from impact fees will cover approximately 50% of the cost of a park development which will be needed as a result of growth.

The City does not currently collect Police impact fees. At full implementation, the anticipated revenue is estimated at approximately \$129,000 per year. With a three-year implementation schedule, \$129,000 in Police impact fee revenues will be lost. Over a 10-year period based on growth assumptions, the revenue generated from impact fees will cover approximately 40% of the cost of a police facility expansion which will be needed as a result of growth.

The City does not currently collect Fire impact fees. At full implementation, the anticipated revenue is estimated at approximately \$302,000 per year. With a three-year implementation schedule, \$302,000 in Fire impact fee revenues will be lost. Over a 10-

year period based on growth assumptions, the revenue generated from impact fees will cover approximately one-half of the cost of an additional fire station (fire station #9) needed as a result of growth.

The City does not currently collect Municipal Facilities impact fees. At full implementation, the anticipated revenue is estimated at approximately \$362,000 per year. With a three-year implementation schedule, \$362,000 in Municipal Facilities impact fee revenues will be lost. Over a 10-year period based on growth assumptions, the revenue generated from impact fees will cover approximately two-thirds of municipal facilities (such as fleet maintenance building expansion) which will be needed as a result of growth.

SUGGESTED MOTION:


I move to adopt,

1) Ordinance ____, amending Section 21.06 of the Grand Junction Zoning and Development Code Concerning the updating of and adoption of new Development Impact Fees; and

2) Ordinance _____, amending Ordinance No. 3641 concerning growth and development related Street Policy.

Attachments

1. Grand Junction CO Dev Transportation Impact Fee Study 2019_FINAL
2. Grand Junction CO Dev Fire Police Facilities Parks Impact Fee Study 4.10.19
3. City Council Presentation for 8-19-19 Workshop - Tischler Bise
4. Police Fire MF Parks Implementation Schedule
5. TIF Implementation Schedule
6. Comparison Table Industry to Staff Proposed
7. Stakeholder Position letter on impact fees
8. Fee Comparison GJARA_MetroStudy
9. Fee Comparison - TischlerBise
10. Annual Sales Tax Increase per Annual Housing Unit Increase
11. Draft Ordinance Amending Ordinance No 3641
12. Ordinance No. 3641 - 2004
13. Ordinance Impact Fees Draft v2



Transportation Impact Fee Study for Mesa County, Colorado

prepared by

Duncan Associates

November 2018

with minor revisions February 2019

Table of Contents

EXECUTIVE SUMMARY.....	1
Update Overview.....	2
Updated Fees	3
Comparative Jurisdictions	4
SERVICE AREAS	6
MAJOR ROADWAY SYSTEM	7
TRAVEL DEMAND	8
Trip Generation.....	8
New Trip Factor.....	8
Average Trip Length.....	8
Travel Demand Summary	10
COST PER SERVICE UNIT	14
Average Cost per Lane-Mile	14
Cost per Service Unit Summary	15
NET COST PER SERVICE UNIT	17
NET COST SCHEDULE	19
APPENDIX A: MAJOR ROAD INVENTORY	20
APPENDIX B: LAND USE DEFINITIONS	27
APPENDIX C: LEGAL FRAMEWORK.....	31
Dual Rational Nexus Test	31
The Need Test.....	31
The Benefit Test	31
Colorado Statutes	32
Level of Service.....	33
Proportionality	33
Developer Credits	33
Revenue Credits.....	34
APPENDIX D: METHODOLOGY	36
Service Unit.....	36
Consumption-Based Model	36
APPENDIX E: TRIP RATES BY UNIT SIZE.....	39

prepared by Duncan Associates
Clancy Mullen, Principal/Project Manager
17409 Rush Pea Circle, Austin, Texas 78738
(512) 423-0480, clancy@duncanassociates.com

List of Tables

Table 1. Current Transportation Impact Fees.....	1
Table 2. Comparison of Current and Updated Transportation Impact Fees	4
Table 3. Transportation Impact Fees in Colorado	5
Table 4. Existing Average Daily Trips.....	9
Table 5. Average Trip Length.....	9
Table 6. Average Trip Lengths by Trip Purpose.....	10
Table 7. Travel Demand Schedule	12
Table 8. Travel Demand Comparison	13
Table 9. Urban Average Cost per Lane-Mile.....	14
Table 10. Rural Average Cost per Lane-Mile.....	15
Table 11. Weighted Average Cost per Lane-Mile	15
Table 12. Transportation Cost per Service Unit	16
Table 13. Average Annual State/Federal Road Capacity Funding, FY 2019-2022.....	17
Table 14. Average Annual Local Road Capacity Expenditures	18
Table 15. Transportation Funding Credit	18
Table 16. Transportation Net Cost per Service Unit	18
Table 17. Updated Transportation Impact Fees	19
Table 18. Existing Major Roadway Inventory	20
Table 19. Existing Major Roadway Level of Service	37
Table 20. Unit Size by Number of Bedrooms, Single-Family.....	39
Table 21. Persons per Unit by Bedrooms, Single-Family	39
Table 22. Trip Rates by Household Size	40
Table 23. Daily Trip Ends by Unit Size, Single-Family.....	41

EXECUTIVE SUMMARY


This is a slightly revised version of the November 28, 2018 study, which adds some alternative residential land use categories. Specifically, it (1) adds the option of single-family detached fees for four unit size categories, (2) breaks down the multi-family category into three potential subcategories (multi-family low-rise, multi-family mid-rise, and townhome), and (3) adds two senior adult housing categories (detached and attached). The changes modify Tables 7 and 17, and add a new Appendix E. In all other respects, the study is unchanged.

The purpose of this project is to assist Mesa County and participating municipalities (Grand Junction, Palisade and Fruita) by updating the county-wide transportation impact fees study. The previous study was prepared in 2002. The fees calculated in that study and the fees currently being charged by the participating jurisdictions are summarized in Table 1, and are illustrated in Figure 1 on the following page for five major land use categories. All jurisdictions originally adopted the fees at a lower rate than calculated in the 2002 study, and some have adjusted the fees periodically for inflation. Except for Fruita's residential fees, the current fees being charged are lower than the fees calculated 16 years ago.

Table 1. Current Transportation Impact Fees

Land Use	Unit	2002 Study	Mesa County	Grand Junction	Palisade	Fruita
Single-Family Detached	Dwelling	\$2,854	\$1,902	\$2,554	\$2,554	\$3,200
Multi-Family	Dwelling	\$1,979	\$1,317	\$1,769	\$1,769	\$2,208
Mobile Home/RV Park	Pad	\$1,435	\$958	\$1,284	\$1,284	\$795
Hotel/Motel	Room	\$2,687	\$1,795	\$2,407	\$2,407	\$1,494
Shopping Center (0 to <100k sf)	1,000 sf	\$4,646	\$3,124	\$4,189	\$4,190	\$2,606
Shopping Center (100k to <249k sf)	1,000 sf	\$4,393	\$2,935	\$3,933	\$3,935	\$2,447
Shopping Center (250k to <500k sf)	1,000 sf	\$4,267	\$2,843	\$3,805	\$3,815	\$2,368
Shopping Center (500k sf or more)	1,000 sf	\$3,942	\$2,627	\$3,525	\$3,521	\$2,193
Auto Sales/Service	1,000 sf	\$4,232	\$2,824	\$3,780	\$3,785	\$2,352
Bank	1,000 sf	\$7,117	\$4,744	\$6,359	\$6,365	\$3,957
Convenience Store w/Gas Sales	1,000 sf	\$10,191	\$6,818	\$9,143	\$9,149	\$5,689
Golf Course	Hole	\$6,578	\$4,439	\$5,951	\$5,954	\$3,702
Health Club	1,000 sf	\$3,813	\$2,542	\$3,422	\$3,410	\$2,129
Movie Theater	1,000 sf	\$11,834	\$7,889	\$10,574	\$10,584	\$6,578
Restaurant, Sit Down	1,000 sf	\$5,757	\$3,838	\$5,159	\$5,150	\$3,210
Restaurant, Fast Food	1,000 sf	\$12,846	\$8,596	\$11,544	\$11,532	\$7,182
Office, General (0 to <99k sf)	1,000 sf	\$3,494	\$2,342	\$3,141	\$3,142	\$1,954
Office, General (100 sf or more)	1,000 sf	\$2,973	\$1,997	\$2,682	\$2,675	\$1,668
Office, Medical	1,000 sf	\$9,807	\$6,607	\$8,862	\$8,865	\$5,514
Hospital	1,000 sf	\$4,554	\$3,069	\$4,112	\$4,117	\$2,558
Nursing Home	1,000 sf	\$1,276	\$860	\$1,149	\$1,153	\$715
Church	1,000 sf	\$2,184	\$1,462	\$1,967	\$1,961	\$1,224
Day Care Center	1,000 sf	\$4,553	\$3,052	\$4,086	\$4,094	\$2,542
Elementary/Secondary School	1,000 sf	\$713	\$478	\$639	\$641	\$397
Industrial Park	1,000 sf	\$2,073	\$1,385	\$1,864	\$1,857	\$1,160
Warehouse	1,000 sf	\$1,477	\$987	\$1,328	\$1,324	\$826
Mini-Warehouse	1,000 sf	\$512	\$344	\$460	\$463	\$286

Source: 2002 study fees from Duncan Associates, *Transportation Impact Fee Study for Mesa County, Colorado*, September 2002; Mesa County fees from resolution adjusting the fees for inflation adopted January 8, 2018; Palisade fees from Town of Palisade, February 5, 2018; Fruita fees from 2018 fee schedule from City of Fruita, February 5, 2018.

Figure 1. Existing Transportation Impact Fees, Mesa County

Note: Shopping center and office fees based on 100,000 sq. ft. building

Update Overview

This study retains the general methodology used in the 2002 study (see discussion of methodology in Appendix D). The original study calculated regional and non-regional fees, under the expectation that the participating jurisdictions would pool the regional fees and use them to improve regional roadways. Instead, the jurisdictions are spending the fees they collect to improve roads within their jurisdiction, regardless of the regional/non-regional road distinction. This update does not calculate separate fees for the two categories.

Participating jurisdictions can adopt the updated fees at any level up to 100% of the amounts calculated in this study. The adoption percentage should be the same for all land uses to retain the proportionality of the fees to the impact on the major roadway system. If disproportionate reductions are made in fees assessed on selected types of development, the shortfall should be made up with general fund revenue, and a revenue credit should be calculated to avoid non-favored development paying more than its fair share (see Proportionality section in Appendix C).

This study calculates fees that exclude right-of-way (ROW) costs, both to keep the fees from increasing so much and to give jurisdictions the option not to provide developer credits for ROW exactions. However, if a jurisdiction opts to not give developers credit against the fees for required ROW dedications, that jurisdiction should consider restricting the funds collected from being spent on ROW (see Developer Credit section of Appendix C).


The inputs into the fee calculations are updated in this study based on the most current available data. Trip rates have been updated based on the September 2017 edition of the Institute of Transportation Engineers (ITE) *Trip Generation Manual*. Updated average trip lengths are from the U.S. Department of Transportation's 2017 *National Household Travel Survey*. An updated inventory of the county-wide major roadway system is used to calibrate the travel demand factors and ensure that they are consistent with existing travel on the major roadway system in Mesa County.

Several modifications to the fee schedule land use categories are made in this update to better reflect current available data and/or simplify the process of fee determination and collection. A discussion of the reasons for individual changes can be found in the summary section of the Travel Demand chapter. Recommended definitions for the land use categories are provided in Appendix B.

Updated Fees

The updated fees are compared with the fees calculated in the 2002 study in Table 2 on the following page. Not surprisingly, the fees are considerably higher than those calculated 16 years ago for most land uses. Construction costs have increased considerably over this time. The Colorado Department of Transportation's Construction Cost Index is 2.46 times what it was in 2002. Compared to inflation-adjusted 2002 study fees, the updated fees are lower for the majority of land uses, including the major categories of single-family, multi-family, retail/commercial, general office, and industrial/warehouse uses, as illustrated in Figure 2.

Figure 2. Comparison of Current and Updated Transportation Impact Fees



The wide variation in percentage changes between land use categories reflects changes in travel demand factors, including trip generation rates (1997 versus 2017 ITE manual), percent new trips (also from ITE manual), and average trip lengths (1995 versus 2017 national travel survey).

Table 2. Comparison of Current and Updated Transportation Impact Fees

Land Use Type	Unit	2002 Study		Updated Fees	% Change from	
		Original	Inflated		Original	Inflated
Single-Family Detached	Dwelling	\$2,854	\$7,021	\$6,763	137%	-4%
Multi-Family	Dwelling	\$1,979	\$4,868	\$4,570	131%	-6%
Mobile Home/RV Park	Pad	\$1,435	\$3,530	\$3,583	150%	1%
Hotel/Motel	Room	\$2,687	\$6,610	\$4,183	56%	-37%
Shopping Center/Commercial	1,000 sf	\$4,393	\$10,807	\$8,240	88%	-24%
Auto Sales/Service	1,000 sf	\$4,267	\$10,497	\$9,258	117%	-12%
Bank, Drive-In	1,000 sf	\$7,117	\$17,508	\$18,365	158%	5%
Convenience Store w/Gas Sales	1,000 sf	\$10,191	\$25,070	\$26,395	159%	5%
Golf Course	Hole	\$6,578	\$16,182	\$12,850	95%	-21%
Movie Theater	1,000 sf	\$11,834	\$29,112	\$33,028	179%	13%
Restaurant, Standard	1,000 sf	\$5,757	\$14,162	\$14,975	160%	6%
Restaurant, Drive-Through	1,000 sf	\$12,846	\$31,601	\$33,203	158%	5%
Office, General	1,000 sf	\$2,973	\$7,314	\$6,685	125%	-9%
Office, Medical	1,000 sf	\$9,807	\$24,125	\$25,665	162%	6%
Animal Hospital/Vet Clinic	1,000 sf	n/a	n/a	\$15,858	n/a	n/a
Hospital	1,000 sf	\$4,554	\$11,203	\$7,905	74%	-29%
Nursing Home	1,000 sf	\$1,276	\$3,139	\$3,120	145%	-1%
Place of Worship	1,000 sf	\$2,184	\$5,373	\$2,725	25%	-49%
Day Care Center	1,000 sf	\$4,553	\$11,200	\$4,485	-1%	-60%
Elementary/Secondary School	1,000 sf	\$713	\$1,754	\$1,688	137%	-4%
Public/Institutional	1,000 sf	n/a	n/a	\$3,813	n/a	n/a
Industrial	1,000 sf	\$2,073	\$5,100	\$2,078	0%	-59%
Warehouse	1,000 sf	\$1,477	\$3,633	\$1,248	-16%	-66%
Mini-Warehouse	1,000 sf	\$512	\$1,260	\$1,075	110%	-15%

Source: Original 2002 study fees from Duncan Associates, *Transportation Impact Fee Study for Mesa County, Colorado*, September 2002 (sum of regional road fees without major structure costs and nonregional road fees); inflated 2002 fees are 2.46 times the original fee, based on the increase in the Colorado Department of Transportation *Construction Cost Index* from 2nd quarter 2012 to 2nd quarter 2018; updated fees from Table 17.

Comparative Jurisdictions

Communities in the process of updating impact fees are naturally interested in knowing what other nearby or comparable jurisdictions are charging. However, concerns about “competitiveness” with other jurisdictions are not necessarily well-founded. Studies have found that reducing or eliminating fees did not have any perceptible effect on the rate of development that subsequently occurred. This is not surprising, given the myriad other market and regulatory factors that differ between jurisdictions besides transportation impact fees.

The fees from the 2002 study and this update are compared to transportation impact fees currently charged by 12 other Colorado jurisdictions in Table 3. Note that while only transportation fees are compared, two-thirds of the comparison jurisdictions also charge other types of impact fees.


Table 3. Transportation Impact Fees in Colorado

Jurisdiction	Study/ Adoption Year	Single- Family (per unit)	Multi- Family (per unit)	Retail (per 1,000 sq. ft.)	Office (per 1,000 sq. ft.)	Industrial (per 1,000 sq. ft.)
Boulder (1)	2017	\$3,734	\$2,702	\$3,020	\$2,700	\$2,620
Durango	n/a	\$2,169	\$1,298	\$3,810	\$2,823	\$1,963
El Paso County	2017	\$3,532	\$2,220	\$4,572	\$2,933	\$3,366
Fort Collins	2017	\$5,150	\$3,392	\$6,721	\$4,951	\$1,598
Garfield County (2)	2017	\$1,992	\$1,230	\$3,145	\$1,361	\$472
Greeley	2015	\$3,973	\$2,565	\$5,428	\$4,650	\$1,609
Jefferson County (3)	n/a	\$2,911	\$2,051	\$5,360	\$3,590	\$1,550
Larimer County	2018	\$4,168	\$2,955	\$5,461	\$3,213	\$1,296
Loveland	n/a	\$2,578	\$1,801	\$7,910	\$3,550	\$1,890
Mesa Co (2002)	2002	\$2,854	\$1,979	\$4,393	\$2,973	\$2,073
Mesa Co (updated)	2018	\$6,763	\$4,570	\$8,240	\$6,685	\$2,078
Montrose County	2007	\$3,480	\$2,440	\$7,790	\$4,000	\$2,530
Weld County	2011	\$2,488	\$1,630	\$3,450	\$2,275	\$2,251
Windsor	2017	\$3,838	\$2,436	\$5,076	\$4,674	\$2,016

Notes: (1) includes transportation excise tax; (2) average of two areas; (3) single-family fee is average of fees for up-to-two-car garages and three-or-more-car garages

Source: Duncan Associates internet survey, October 5, 2018 (where fees vary by size, assumes 2,000 sq. ft. single-family unit, 1,000 sq. ft. multi-family unit, and 1 million square foot retail center or office building).

Single-family and retail transportation fees charged by Mesa County and the other 12 Colorado jurisdictions are illustrated in the two charts below. The 2002 study fees for Mesa County are well below the median of the other jurisdictions for both single-family and retail. The updated fees are at the high end of what the other 12 jurisdictions currently charge. Multi-family and office fee comparisons are not shown, but are similar. Industrial fees are not going up much in this update.

Figure 3. Comparative Transportation Fees, Colorado Jurisdictions


SERVICE AREAS

There are two kinds of geographic areas in impact fee systems: service areas and benefit districts. A service area is an assessment area that is served by a defined group of capital facilities and subject to a uniform impact fee schedule. A benefit district is an area within which fees collected are earmarked to be spent.

Generally, transportation impact fees tend to have a single service area and a uniform fee schedule, whether at the municipal level or the regional, county-wide level. That is because the arterial road system is designed to move traffic from one part of a community to another, and improvements to this system are generally of community-wide benefit. In some communities, major collectors may function as part of the arterial system as well.

The transportation impact fees apply only in the most rapidly developing area of the County. The boundaries of the Grand Valley Airshed as defined by the Colorado Department of Health for the purposes of monitoring air pollution is used as the transportation impact fee service area. Based on the 6,000-foot elevation line on the valley walls, the Airshed defines the developing area in and around the municipalities of Grand Junction, Palisade and Fruita. This transportation impact fee service area is about one-quarter of the area of the entire county, including roughly twice as much privately-owned land area as the area used in regional transportation planning. This area continues to be appropriate as the boundary of the service area for the transportation impact fees (see Figure 4).


Figure 4. Transportation Impact Fee Service Area



MAJOR ROADWAY SYSTEM

A transportation impact fee system should include a clear definition of the major roadway system that is to be funded with the impact fees. The major roadway system consists of all state and federal highways (excluding I-70), principal arterials (e.g., 24 Road, Patterson Road), minor arterials, and major collector roads within the transportation impact fee service area (illustrated in Figure 5). Other roads will not be funded with transportation impact fees, nor will developer improvements to roads not included in the major roadway system be eligible for credits against the transportation impact fees. A detailed listing of the current road segments included in the major roadway system is provided in Table 18 in Appendix A.

Figure 5. Major Roadway System



TRAVEL DEMAND

The travel demand generated by specific land use types in Mesa County is a product of three factors: 1) trip generation, 2) percent new trips, and 3) average trip length. The first two factors are well documented in the professional literature – the average trip generation characteristics identified in studies of communities around the nation should be reasonably representative of trip generation characteristics in Mesa County. In contrast, trip lengths are much more likely to vary between communities, depending on the geographic size and shape of the community and its major roadway system.

Trip Generation

Trip generation rates are based on information published in the most recent edition of the Institute of Transportation Engineers' (ITE) Trip Generation manual. Trip generation rates represent trip ends, or driveway crossings at the site of a land use. Thus, a single trip from home to work counts as one trip end for the residence and one trip end for the work place, for a total of two trip ends. To avoid over counting, all trip rates are divided by two. This allocates travel equally between the origin and destination of the trip and avoids double charging. This update utilizes the most current edition of the ITE manual (the 10th edition published in 2017).

New Trip Factor

Trip rates must also be adjusted by a “new trip factor” to exclude pass by and diverted-linked trips. This adjustment is intended to reduce the possibility of over-counting by only including primary trips generated by the development. Pass by trips are those trips that are already on a particular route for a different purpose and simply stop at a development on that route. For example, a stop at a convenience store on the way home from the office is a pass by trip for the convenience store. A pass by trip does not create an additional burden on the street system and therefore should not be counted in the assessment of impact fees. A diverted-linked trip is similar to a pass by trip, but a diversion is made from the regular route to make an interim stop. The reduction for pass by and diverted-linked trips is drawn from ITE manual and other published information.

Average Trip Length

In the context of a transportation impact fee based on a consumption-based methodology, it is important to determine the average length of a trip on the major roadway system within Mesa County. The average trip length can be determined by dividing the total vehicle-miles of travel (VMT) on the major roadway system by the total number of trips generated by existing development in the service area. Total VMT on the major roadway system is estimated by multiplying the length of each road segment by the current traffic volume on that segment and summing for the entire system. Total trips can be estimated by multiplying existing land uses by the appropriate trip generation rates (adjusted for new trip factors and divided by two) and summing for all existing development in the service area.

Existing land use information was compiled for all jurisdictions within the transportation impact fee service area to determine an average trip length. Existing land uses in each of the general categories are multiplied by average daily trip generation rates and summed to determine a reasonable estimate of total daily trips within the service area. As shown in Table 4, existing land uses within the transportation impact fee service area generate approximately 428,000 average daily trips.

Table 4. Existing Average Daily Trips

Land Use Type	ITE Code	Unit	Existing Units	Trips/Unit	Daily Trips
Single-Family Detached	210	Dwelling	44,535	4.72	210,205
Multi-Family	220/221	Dwelling	11,383	3.19	36,312
Subtotal, Residential			55,918		246,517
Hotel/Motel	310/320	Rooms	3,806	2.92	11,114
Commercial	820	1,000 Sq. Ft.	13,754	8.30	114,158
Office	710	1,000 Sq. Ft.	3,028	4.87	14,746
Industrial	130	1,000 Sq. Ft.	3,655	1.68	6,140
Warehousing	150	1,000 Sq. Ft.	6,130	0.87	5,333
Public/Institutional	620	1,000 Sq. Ft.	8,999	3.32	29,877
Subtotal, Nonresidential			35,566		181,368
Total					427,885

Source: Existing development in service area from Mesa County GIS, March 12, 2018; trips per unit from Table 7.

A reasonable estimate of Mesa County's average trip length can be derived by dividing total daily VMT on the major roadway system by the total number of daily trips generated by existing development within the service area. This calculation, presented in Table 5, indicates that the average trip length on the major roadway system is about 5.5 miles.

Table 5. Average Trip Length

Daily VMT on Major Roads	2,347,636
÷ Daily Trips in Service Area	427,885
Average Trip Length (miles)	5.49

Source: VMT from Table 18; trips from Table 4.

Average trip lengths by trip purpose for the western region are available from the U.S. Department of Transportation's 2017 *National Household Travel Survey*. In addition, a residential trip length is determined, using a weighting of 20 percent work trips and 80 percent average trips. The average trip length on the major roadway system is 62.6% of the regional average trip length. Using this ratio, reasonable trip lengths were derived for specific trip purposes, including home-to-work trips, shopping, school/church and other personal trips, as shown in Table 6.

Table 6. Average Trip Lengths by Trip Purpose

Trip Purpose	Regional Trip Length (miles)	Local Ratio	Local Trip Length (miles)
To or from work	10.77	0.626	6.74
Residential	9.16	0.626	5.73
Doctor/Dentist	9.42	0.626	5.90
School/Church	5.01	0.626	3.14
Family/Personal	6.00	0.626	3.76
Shopping	6.34	0.626	3.97
Average of All Trip Purposes*	8.76	0.626	5.49

* weighted (not simple average of trip purposes shown)

Source: Regional average trip lengths for the western Census region from US Department of Transportation, *National Household Travel Survey*, 2017; regional residential trip length estimated based on weighting of 20% work trips and 80% average trips (20% work trip factor based on 2016 5-year U.S. Census sample data for Mesa County showing the average dwelling unit has 0.91 workers, and 0.91 work trips per unit is 20% of average trips per unit, derived from Table 4); average local trip length from Table 5; ratio is average local to regional trip length; local trip length by purpose is product of regional trip length and local ratio.

Travel Demand Summary

The result of combining trip generation rates, new trip factors, average trip lengths and the local adjustment factor is the travel demand schedule. The travel demand schedule establishes the average daily vehicle-miles of travel (VMT) generated by various land use types per unit of development in the service area. The updated demand schedule reflects updated trip generation rates from the Institute of Transportation Engineers (ITE), *Trip Generation Manual*, 10th edition, 2017. Average trip lengths are updated with the 2017 *National Household Travel Survey*. The adjustment factor ensures that the VMT generated by existing land uses does not exceed current observed VMT on the major roadway system. The updated travel demand schedule is presented in Table 7. For each land use, daily VMT is a factor of trip rate, trip length, new trip factor, and the local adjustment factor.

Some modifications to the land use categories are made in this update to better reflect available data and to simplify the process of fee determination and collection. Recommended definitions of all the categories are provided in Appendix B.

- The current four shopping center size categories are combined into a single retail/commercial category. It is based on average trip characteristics for shopping centers, which tend to include a relatively broad mix of commercial uses. While trip generation rates are available for shopping centers by size, data on new trip factors and average trip lengths by size are harder to come by. Trip generation rates tend to go down by shopping center size, but this is counterbalanced by fewer pass by trips and longer trip lengths. The average shopping center rate is the appropriate default for a wide range of retail and commercial uses not specifically identified in the fee schedule. Health club is merged into the new “Shopping Center/Commercial” category because the ITE manual does not have a daily trip generation rate, and the PM peak hour rate is similar to shopping center.

- The current two office categories by building size are combined into a single general office category, for the same reasons of data availability and counterbalancing applicable to shopping centers.
- Two new categories have been added: animal hospital/vet clinic and public/institutional. The new ITE manual now has an average daily trip rate for animal hospital. The public/institutional category, based on trip data for junior/community college, is intended to provide a default category for other public/institutional uses not specifically listed in the fee schedule.
- The sit-down and fast food restaurant categories have been renamed “standard” and “drive-through,” and are defined by whether they have drive-through/drive-in facilities. This provides an administratively simple way to distinguish between them and is consistent with the ITE category from which the fast food trip rate is derived.
- Church has been renamed “Place of Worship” to better reflect its nondenominational character. Industrial park has been renamed “Industrial” to reflect its broader applicability.
- Finally, several additional residential subcategories are provided as alternatives to adopting the broader single-family detached and multi-family categories. In addition, two categories are added for senior adult housing.

The updated travel demand schedule is presented in Table 7 on the following page.

Table 7. Travel Demand Schedule

Land Use Type	ITE Code	Unit	Trips	% New	Miles	VTM
Single-Family Detached	210	Dwelling	4.72	100%	5.73	27.05
<1,250 sq. ft. of living area	210	Dwelling	2.27	100%	5.73	13.01
1,250 - 1,649 sq. ft. of living area	210	Dwelling	3.79	100%	5.73	21.72
1,650 - 2,299 sq. ft. of living area	210	Dwelling	4.41	100%	5.73	25.27
2,300 or more sq. ft. of living area	210	Dwelling	5.96	100%	5.73	34.15
Multi-Family (including townhome)	220/221	Dwelling	3.19	100%	5.73	18.28
Multi-Family, Low-Rise (1-2 stories)	220	Dwelling	3.66	100%	5.73	20.97
Multi-Family, Mid-Rise (3-10 stories)	221	Dwelling	2.72	100%	5.73	15.59
Townhouse	230	Dwelling	2.90	100%	5.73	16.62
Senior Adult Housing - Detached	251	Dwelling	2.13	100%	5.73	12.20
Senior Adult Housing - Attached	252	Dwelling	1.85	100%	5.73	10.60
Mobile Home/RV Park	240	Pad	2.50	100%	5.73	14.33
Hotel/Motel	310/320	Room	2.92	100%	5.73	16.73
Shopping Center/Commercial	820	1,000 sf	18.87	44%	3.97	32.96
Auto Sales/Service	840	1,000 sf	13.92	67%	3.97	37.03
Bank, Drive-In	912	1,000 sf	50.01	37%	3.97	73.46
Convenience Store w/Gas Sales	853	1,000 sf	312.10	17%	1.99	105.58
Golf Course	430	Hole	15.19	90%	3.76	51.40
Movie Theater	444	1,000 sf	39.04	90%	3.76	132.11
Restaurant, Standard	931	1,000 sf	41.92	38%	3.76	59.90
Restaurant, Drive-Through	934	1,000 sf	235.47	30%	1.88	132.81
Office, General	710	1,000 sf	4.87	100%	5.49	26.74
Office, Medical	720	1,000 sf	17.40	100%	5.90	102.66
Animal Hospital/Vet Clinic	650	1,000 sf	10.75	100%	5.90	63.43
Hospital	610	1,000 sf	5.36	100%	5.90	31.62
Nursing Home	620	1,000 sf	3.32	100%	3.76	12.48
Place of Worship	560	1,000 sf	3.47	100%	3.14	10.90
Day Care Center	565	1,000 sf	23.81	24%	3.14	17.94
Elementary/Secondary School	520/522/530	1,000 sf	8.96	24%	3.14	6.75
Public/Institutional	540	1,000 sf	10.12	48%	3.14	15.25
Industrial	130	1,000 sf	1.45	100%	5.73	8.31
Warehouse	150	1,000 sf	0.87	100%	5.73	4.99
Mini-Warehouse	151	1,000 sf	0.75	100%	5.73	4.30

Source: 1-way trips are ½ of trip ends from Institute of Transportation Engineers (ITE), *Trip Generation Manual*, 10th Edition, 2017 (single-family by unit size from Table 23 in Appendix E); new trip percentages for retail/commercial uses from ITE, *Trip Generation Handbook*, 3rd Edition, 2017; new trip percentage for day care and schools based on Preston Hitchens, "Trip Generation of Day Care Centers," 1990 ITE Compendium; average trip lengths from Table 6 (convenience store is one half retail, drive-through restaurant is one-half standard restaurant); VMT is product of trip rate, percent new trips, and trip length.

Comparisons of existing and updated travel demand factors are shown in Table 8. Travel demand per unit of development by land use type is lower for most land uses in this update. The change in travel demand per unit by land use exhibits considerable variation, ranging from a decline of 68% for warehouse to an increase of 7% for movie theater.

Table 8. Travel Demand Comparison

Land Use Type	Unit	VMT per Unit		Percent Change
		2002	Updated	
Single-Family Detached	Dwelling	29.70	27.05	-9%
Multi-Family	Dwelling	20.59	18.28	-11%
Mobile Home/RV Park	Pad	14.94	14.33	-4%
Hotel/Motel	Room	27.96	16.73	-40%
Shopping Center/Commercial	1,000 sf	44.91	32.96	-27%
Auto Sales/Service	1,000 sf	43.97	37.03	-16%
Bank, Drive-In	1,000 sf	73.94	73.46	-1%
Convenience Store w/Gas Sales	1,000 sf	106.28	105.58	-1%
Golf Course	Hole	69.15	51.40	-26%
Movie Theater	1,000 sf	122.94	132.11	7%
Restaurant, Standard	1,000 sf	59.82	59.90	0%
Restaurant, Drive-Through	1,000 sf	133.96	132.81	-1%
Office, General	1,000 sf	33.80	26.74	-21%
Office, Medical	1,000 sf	103.00	102.66	0%
Hospital	1,000 sf	47.83	31.62	-34%
Nursing Home	1,000 sf	13.40	12.48	-7%
Place of Worship	1,000 sf	22.80	10.90	-52%
Day Care Center	1,000 sf	47.55	17.94	-62%
Elementary/Secondary School	1,000 sf	7.45	6.75	-9%
Industrial	1,000 sf	21.57	8.31	-61%
Warehouse	1,000 sf	15.37	4.99	-68%
Mini-Warehouse	1,000 sf	5.38	4.30	-20%

Source: 2002 VMT from Duncan Associates, *Transportation Impact Fee Study*, September 2002; updated VMT from Table 7.

COST PER SERVICE UNIT

There are two components to determining the average cost to add a unit of capacity to the major roadway system: the cost of a set of improvements, and the capacity added by those improvements. This section describes both components used to calculate the average cost per service unit.

This update excludes right-of-way (ROW) costs from the fee calculation. The exclusion of ROW eliminates the most variable component of project costs, keeps the fees lower, and allows jurisdictions the option of not providing developer credit for ROW dedication.

Average Cost per Lane-Mile

The first step is to determine the cost to add an additional lane-mile of roadway. While transportation impact fees can be used to pay for a variety of types of improvements that expand the capacity of the major roadway system without adding lanes, such as intersection improvements and signalization, it is difficult to quantify the vehicle-miles of capacity (VMC) added by these types of improvements. The cost per lane-mile can be calculated based on a representative list of historical or planned improvements. The average cost per lane-mile developed for this study uses a weighted average of urban and rural road improvements. Right-of-way costs have been excluded in this update.

Costs for improving urban road sections are drawn from cost data provided by the City of Grand Junction. The estimated costs of the City's planned improvements over the next ten years are summarized in Table 9. Mesa County engineers confirm these costs are reasonably representative of urban road capacity expansion in other parts of the county. None of the projects include major structures, such as overpasses, elevated ramps or bridges. As shown, the weighted average cost of urban road expansions is about \$3.3 million per lane-mile.

Table 9. Urban Average Cost per Lane-Mile

Road	From	To	Miles	Lanes		New Ln-Mi.	Project Cost	Cost per Lane-Mile
				Ex.	Fut.			
24 Road	Patterson	I-70	1.20	3	5	2.40	\$8,100,000	\$3,375,000
25 Road	I-70B	F 1/4	0.75	3	5	1.50	\$7,290,000	\$4,860,000
25 Road	F 1/4 Road	G Road	0.75	2	3	0.75	\$3,060,000	\$4,080,000
26 Road	Patterson	H Road	2.00	2	3	2.00	\$6,480,000	\$3,240,000
26 1/2 Road	Horizon	Summerhill	2.20	2	3	2.20	\$8,019,000	\$3,645,000
28 1/4 Road	Patterson	Hawthorne	0.38	0	2	0.76	\$390,000	\$513,158
28 3/4 Road	North Ave	Orchard Ave	0.50	2	3	0.50	\$4,500,000	\$9,000,000
29 Rd Pkwy	F Road	I-70	1.00	2	5	3.00	\$9,000,000	\$3,000,000
Crosby Ave	25 1/2 Rd	Main St	0.63	2	3	0.63	\$4,025,700	\$6,390,000
D 1/2 Road	29 Road	30 Road	1.00	2	3	1.00	\$4,500,000	\$4,500,000
F 1/2 Pkwy	I-70B	F 1/4 Rd	1.70	0	3	5.10	\$9,720,000	\$1,905,882
G Road	24 Road	27 Road	3.00	2	3	3.00	\$10,700,000	\$3,566,667
Total			15.11			22.84	\$75,784,700	\$3,318,069

Source: Planned projects descriptions and costs in 2018 dollars from Trent Prall, Public Works Director, City of Grand Junction, September 19, 2018; cost per lane-mile is project cost divided by new lane-miles.

The cost of recent County rural road projects constructed or estimated in engineering studies are summarized in Table 10. All these projects or studies are from about three years ago and have been adjusted to current dollars. The costs do not include any bridge work, which the County often does as part of such projects. The list does not include any urban projects, or projects in the high country, which tend to cost quite a bit more. Many of these projects do not actually add new travel lanes, but rather the equivalent amount of pavement provided by new shoulders. The resulting average rural road cost is about \$1.68 million per lane-mile in current dollars.

Table 10. Rural Average Cost per Lane-Mile

Road	From	To	Project Description	Miles	Lanes		New Ln-Mi.	Project Cost	Cost/ Lane-Mile
					Ex.	Fut.			
22 Road	Ranchman's Ditch	H Road	Added 3rd lane w/shldrs	0.27	2	3	0.27	\$948,300	\$3,512,222
22 Road	H Road	H 1/2 Road	Added 3rd lane w/shldrs	0.41	2	3	0.41	\$1,046,400	\$2,552,195
22 Road	H 1/2 Road	I Road	Added 6' shoulders	0.59	2	3	0.59	\$997,350	\$1,690,424
22 Road	I Road	GVIC Canal	Added 6' shoulders	0.66	2	3	0.66	\$1,008,250	\$1,527,652
22 Road	GVIC Canal	J 1/2 Road	Added 6' shoulders	0.70	2	3	0.70	\$1,057,300	\$1,510,429
22 Road	J 1/2 Road	K Road	Added 6' shoulders	0.58	2	3	0.58	\$784,800	\$1,353,103
K Road	19 Road	19 1/2 Road	Added 6' shoulders	0.61	2	3	0.61	\$833,850	\$1,366,967
K Road	19 1/2 Road	20.2 Road	Added 6' shoulders	0.70	2	3	0.70	\$1,286,200	\$1,837,429
K Road	Adobe	20.8 Road	Added 6' shoulders	0.63	2	3	0.63	\$693,240	\$1,100,381
Total				5.15			5.15	\$8,655,690	\$1,680,717

Source: Mesa County Engineering, October 5, 2018; original costs inflated by the change in the CDOT Construction Cost Index over the last three years; cost per lane-mile is project cost divided by new lane-miles.

Average urban and rural costs per lane-mile identified above are converted to a weighted average cost per lane-mile in Table 11 based on the distribution of existing lane-miles. The weighted average is about \$2.8 million per lane-mile.

Table 11. Weighted Average Cost per Lane-Mile

	Urban	Rural	Total
Average Cost per Lane-Mile	\$3,318,069	\$1,680,717	n/a
x Percent of Lane-Miles	66.2%	33.8%	100.0%
Weighted Average Cost per Lane-Mile	\$2,196,562	\$568,082	\$2,764,644

Source: Average cost per lane-mile from Table 9 (urban) and Table 10; distribution of urban and rural major roadway lane-miles within the service area from Mesa County GIS, September 28, 2018.

Cost per Service Unit Summary

Dividing the weighted average cost per lane-mile by the average daily capacity per lane yields an average cost of per vehicle-mile of capacity or VMC. Under the modified consumption-based methodology, the cost per VMC needs to be multiplied by the VMC/VMT ratio (see discussion in Appendix D: Methodology) to determine the cost per vehicle-mile of travel or VMT. As shown in Table 12, the cost per service unit to accommodate the traffic generated by new development is \$353 per VMT. Note that this updated cost per service unit excludes ROW costs.

Table 12. Transportation Cost per Service Unit

Weighted Average Cost per Lane-Mile	\$2,764,644
÷ Average Daily Capacity per Lane	7,827
Average Cost per Vehicle-Mile of Capacity (VMC)	\$353
x VMC/VMT Ratio	1.00
Cost per Vehicle-Mile of Travel (VMT)	\$353

Source: Weighted average cost per lane-mile from Table 11; average capacity per lane derived from Table 18 (total VMC ÷ total lane-miles); VMC/VMT ratio is recommended ratio from Table 19.

NET COST PER SERVICE UNIT

As discussed in Appendix C: Legal Framework, revenue credits may be warranted for existing deficiencies, outstanding debt, the availability of State/Federal funding, and the historical use of local funding for major roadway expansion. There are no existing deficiencies from the perspective of the transportation impact fees because the fees are based on a level of service that is lower than what is currently provided to existing development.

The City of Grand Junction is the only one of the four jurisdictions that has any outstanding debt on existing major roadways. The City has about \$25 million in outstanding debt for the Riverside Parkway widening. However, Riverside Parkway accounts for only about 4% of the total excess capacity in the major roadway system that is available for new development. The fees that Grand Junction collects could be used to retire this debt, although that is not the City's current practice. Consequently, no revenue credit is required for the outstanding debt.

While not necessarily required, as discussed in the Revenue Credits section of Appendix C, revenue credits will be calculated for direct state and federal funding for road improvements, and for local government's historical use of funding for capacity-expanding improvements.

Direct funding of road improvements with State and Federal funds is programmed through the *Transportation Improvement Program (TIP)* prepared by the Grand Valley Metropolitan Planning Organization. The current TIP includes \$2.7 million in annual funding over next four years for improvements that are capacity-expanding. These improvements are summarized in Table 13.

Table 13. Average Annual State/Federal Road Capacity Funding, FY 2019-2022

Facility	Location	Description	Amount
I-70B	24 Rd-15th St	Widening	\$2,000,000
US 6	Clifton-Palisade	Preliminary Engineering	\$7,200,000
US 6	Fruita-I-70B	Highway & Intersection Improvements	\$1,650,000
Total State/Federal Funding			\$10,850,000
÷ Number of Years			4
Average Annual Funding			\$2,712,500

Source: Grand Valley Metropolitan Planning Organization, *Transportation Improvement Program, State FY 2019 to 2022*, amended October 22, 2018.

In addition to direct state and federal funding for road improvements, other state highway revenues, primarily highway user taxes and motor vehicle registration fees, are allocated to local jurisdictions and earmarked for transportation-related expenditures. Other major local sources of revenue for road expenditures include Mesa County's sales tax and Grand Junction's general fund. The consultant analyzed the four jurisdictions' annual reports for the last five years to determine how much is spent on right-of-way, new roads, and roadway capacity improvements. As can be seen from Table 14, local governments in Mesa County are spending about \$10 million annually on capacity improvements.

Table 14. Average Annual Local Road Capacity Expenditures

Jurisdiction	5-Yr. Avg.
Mesa County	\$7,184,091
City of Grand Junction	\$2,431,028
City of Fruita	\$441,301
Town of Palisade	\$0
Total	\$10,056,420

Source: Local Highway Finance Reports, 2012-2016 for Mesa County and Grand Junction, 2013-2017 for Fruita and Palisade.

The amount of the revenue credit is determined by first dividing the total annual funding available for road capacity improvements by total VMT on the major roadway system, then multiplying by a present value factor. This results in a credit per service unit that is the current equivalent of the future 30-year stream of funding that will be available to help defray the growth-related costs of improving the major roadway system.

Table 15. Transportation Funding Credit

Annual State/Federal Capital Funding	\$2,712,500
Annual Local Capital Expenditures	\$10,056,420
Total Annual Capital Funding	\$12,768,920
÷ Daily VMT on Major Road System	2,347,636
Annual Funding per Daily VMT	\$5.44
x Present Value Factor (30 Years)	18.86
Funding Credit per Daily VMT	\$103

Source: State/Federal funding from Table 13; local expenditures from Table 14; existing VMT from Table 18; present value factor is based on a discount rate of 3.30%, which is the national average yield on AAA 30-year municipal bonds from fmsbonds.com on November 27, 2018.

The net cost per service unit is the cost per VMT less the revenue credit for non-impact fee funding. As shown in Table 16, the net cost per service unit is \$250 per VMT.

Table 16. Transportation Net Cost per Service Unit

Cost per Vehicle-Mile of Travel	\$353
– Credit per Vehicle-Mile of Travel	-\$103
Net Cost per Vehicle-Mile of Travel	\$250

Source: Cost per VMT from Table 12; credit from Table 15.

NET COST SCHEDULE

The updated transportation impact fees for the various land use categories are shown in Table 17. Fees shown exclude ROW costs. The impact fee calculation for each land use category is the product of daily VMT per development unit on the major roadway system and the net cost per VMT, which takes into account the average cost to add roadway capacity as well as future revenue that will be generated by new development to help offset those costs. The comparison of the updated fees with current fees is presented in the Executive Summary.

Table 17. Updated Transportation Impact Fees

Land Use Type	Unit	VMT/ Unit	Net Cost/ VMT	Net Cost/ Unit
Single-Family Detached	Dwelling	27.05	\$250	\$6,763
<1,250 sq. ft. of living area	Dwelling	13.01	\$250	\$3,253
1,250 - 1,649 sq. ft. of living area	Dwelling	21.72	\$250	\$5,430
1,650 - 2,299 sq. ft. of living area	Dwelling	25.27	\$250	\$6,318
2,300 or more sq. ft. of living area	Dwelling	34.15	\$250	\$8,538
Multi-Family (including townhome)	Dwelling	18.28	\$250	\$4,570
Multi-Family, Low-Rise (1-2 stories)	Dwelling	20.97	\$250	\$5,243
Multi-Family, Mid-Rise (3-10 stories)	Dwelling	15.59	\$250	\$3,898
Townhouse	Dwelling	16.62	\$250	\$4,155
Senior Adult Housing - Detached	Dwelling	12.20	\$250	\$3,050
Senior Adult Housing - Attached	Dwelling	10.60	\$250	\$2,650
Mobile Home/RV Park	Pad	14.33	\$250	\$3,583
Hotel/Motel	Room	16.73	\$250	\$4,183
Shopping Center/Commercial	1,000 sf	32.96	\$250	\$8,240
Auto Sales/Service	1,000 sf	37.03	\$250	\$9,258
Bank, Drive-In	1,000 sf	73.46	\$250	\$18,365
Convenience Store w/Gas Sales	1,000 sf	105.58	\$250	\$26,395
Golf Course	Hole	51.40	\$250	\$12,850
Movie Theater	1,000 sf	132.11	\$250	\$33,028
Restaurant, Standard	1,000 sf	59.90	\$250	\$14,975
Restaurant, Drive-Through	1,000 sf	132.81	\$250	\$33,203
Office, General	1,000 sf	26.74	\$250	\$6,685
Office, Medical	1,000 sf	102.66	\$250	\$25,665
Animal Hospital/Vet Clinic	1,000 sf	63.43	\$250	\$15,858
Hospital	1,000 sf	31.62	\$250	\$7,905
Nursing Home	1,000 sf	12.48	\$250	\$3,120
Place of Worship	1,000 sf	10.90	\$250	\$2,725
Day Care Center	1,000 sf	17.94	\$250	\$4,485
Elementary/Secondary School	1,000 sf	6.75	\$250	\$1,688
Public/Institutional	1,000 sf	15.25	\$250	\$3,813
Industrial	1,000 sf	8.31	\$250	\$2,078
Warehouse	1,000 sf	4.99	\$250	\$1,248
Mini-Warehouse	1,000 sf	4.30	\$250	\$1,075

Source: VMT per unit from Table 17; net cost per VMT from Table 16.

APPENDIX A: MAJOR ROAD INVENTORY

Table 18. Existing Major Roadway Inventory

Street	From	To	Type	Miles	Lns	Capacity	ADT	VMC	VMT
1 9/10 Rd	Highline Canal Rd	I-70	COL	0.588	2	12,000	97	7,056	57
4th Ave	S of S 7th St	S 9th 9th St	COL	0.558	2	12,000	228	6,696	127
14 Rd	Hwy 6 & 50	Node	COL	0.340	2	12,000	193	4,080	66
15 Rd	Hwy 6 & 50	L Rd	COL	0.114	2	12,000	151	1,368	17
15th St	North Ave	Patterson Rd	COL	0.998	2	12,000	838	11,976	836
16 Rd	Hwy 6 nd 50	Q Rd	COL	5.770	2	12,000	638	69,240	3,681
17 1/2 Rd	Applewood Dr	N 3/10 Rd	COL	2.827	2	12,000	1,502	33,924	4,246
17 Rd	K Rd	O Rd	COL	3.996	2	12,000	562	47,952	2,246
18 1/2 Rd	K Rd	N 3/10 Rd	COL	3.669	2	12,000	2,382	44,028	8,740
18 Rd	K 6/10 Rd	Node	COL	3.142	2	12,000	75	37,704	236
19 Rd	Hwy 6 and 50	Node	COL	6.690	2	12,000	3,349	80,280	22,405
20 1/2 Rd	Spoon Ct	E 3/4 Rd	COL	0.849	2	12,000	286	10,188	243
20 Rd	E 3/4 Rd	N Rd	COL	5.663	2	12,000	1,612	67,956	9,129
21 1/2 Rd	Hwy 6 & 50	I Rd	COL	0.979	2	12,000	536	11,748	525
21 Rd	Node	Node	COL	8.129	2	12,000	1,423	97,548	11,568
22 Rd	Hwy 6 & 50	Node	COL	5.128	2	12,000	146	61,536	749
23 Rd	Hwy 6 & 50	Orchard Ave	COL	5.600	2	12,000	2,928	67,200	16,397
24 1/2 Rd	Hwy 6 & 50	Patterson Rd	MA	0.301	4	40,000	11,141	12,040	3,353
24 1/2 Rd	Patterson Rd	F 3/8 Rd	COL	0.368	2	18,000	9,238	6,624	3,400
24 1/2 Rd	F 3/8 Rd	H Rd	COL	1.629	2	12,000	4,691	19,548	7,642
24 Rd	Node	Node	PA	0.466	2	18,000	5,041	8,388	2,349
24 Rd	Patterson Rd	I-70 Ramp	PA	1.290	2	26,000	14,869	33,540	19,181
24 Rd	I-70 Ramp	I-70 Ramp	COL	0.079	4	24,000	8,730	1,896	690
24 Rd	I-70 Ramp	K Rd	COL	3.438	2	12,000	6,335	41,256	21,780
25 1/2 Rd	Independent Ave	Patterson Rd	COL	0.753	2	18,000	4,696	13,554	3,536
25 1/2 Rd	Patterson Rd	Fall Valley Ave	COL	0.267	2	12,000	2,672	3,204	713
25 1/2 Rd	Fall Valley Ave	Moonridge Dr	COL	0.544	2	18,000	1,795	9,792	976
25 1/2 Rd	Moonridge Dr	G Rd	COL	0.201	2	12,000	1,309	2,412	263
25 Rd	Hwy 6 And 50	Riverside Pkwy	PA	0.332	4	44,000	17,671	14,608	5,867
25 Rd	Hwy 6 & 50	Patterson Rd	MA	0.610	2	24,000	18,733	14,640	11,427
25 Rd	Patterson Rd	Foresight Cir	MA	0.169	2	16,000	9,182	2,704	1,552
25 Rd	Foresight Cir	F 1/2 Rd	PA	0.326	2	18,000	9,066	5,868	2,956
25 Rd	F 1/2 Rd	Hayes Dr	MA	0.248	2	16,000	8,493	3,968	2,106
25 Rd	Hayes Dr	G Rd	MA	0.254	2	24,000	7,228	6,096	1,836
25 Rd	G Rd	Node	COL	4.344	2	12,000	2,728	52,128	11,850
26 1/2 Rd	Horizon Dr	H Rd	MA	1.740	2	16,000	254	27,840	442
26 1/2 Rd	H Rd	I Rd	COL	0.998	2	12,000	254	11,976	253
26 Rd	Patterson Rd	G 1/2 Rd	MA	1.453	2	16,000	6,526	23,248	9,482
26 Rd	G 1/2 Rd	Node	MA	0.110	2	24,000	4,332	2,640	477
26 Rd	Node	H Rd	MA	0.435	2	16,000	4,332	6,960	1,884
26 Rd	H Rd	I Rd	COL	0.999	2	12,000	1,113	11,988	1,112
27 1/2 Rd	Patterson Rd	Horizon Dr	COL	1.020	2	18,000	9,077	18,360	9,259
27 1/4 Rd	H Rd	Node	COL	0.926	2	12,000	52	11,112	48
27 Rd	B Rd	C Rd	COL	0.902	2	12,000	2,829	10,824	2,552
27 Rd	G Rd	H Rd	MA	0.999	2	16,000	3,138	15,984	3,135
28 1/2 Rd	Hwy 50	Orchard Ave	COL	1.944	2	12,000	6,159	23,328	11,973
28 1/4 Rd	North Ave	Orchard Ave	COL	0.504	2	18,000	2,666	9,072	1,344

continued on next page

Table 18. Existing Major Roadway Inventory (continued)

Street	From	To	Type	Miles	Lns	Capacity	ADT	VMC	VMT
28 1/4 Rd	Orchard Ave	Patterson Rd	MA	0.498	4	32,000	7,803	15,936	3,886
28 1/4 Rd	Patterson Rd	Park Dr	COL	0.210	2	18,000	2,666	3,780	560
28 Rd	B 1/2 Rd	UnawEEP Ave	COL	0.504	2	12,000	382	6,048	193
28 Rd	I-70 B	Node	MA	0.282	2	16,000	5,494	4,512	1,549
28 Rd	Node	Orchard Ave	MA	0.788	2	24,000	5,494	18,912	4,329
28 Rd	Patterson Rd	Ridge Dr	COL	0.498	2	18,000	3,302	8,964	1,644
28 Rd	Ridge Dr	Cortland Ave	COL	0.252	2	12,000	1,912	3,024	482
29 1/2 Rd	Hwy 50	F 1/2 Rd	COL	2.006	2	12,000	481	24,072	965
29 3/4 Rd	Old WW Rd	Hwy 50	COL	0.724	2	12,000	21	8,688	15
29 Rd	Hwy 50	UnawEEP Ave	COL	0.987	2	18,000	3,125	17,766	3,084
29 Rd	UnawEEP Ave	D Rd	PA	1.276	2	26,000	14,078	33,176	17,964
29 Rd	D Rd	D 1/2 Rd	PA	0.413	4	44,000	15,766	18,172	6,511
29 Rd	D 1/2 Rd	North Ave	PA	0.590	4	36,000	22,096	21,240	13,037
29 Rd	North Ave	Patterson Rd	MA	0.998	2	24,000	10,566	23,952	10,545
29 Rd	Patterson Rd	29 Rd	PA	0.876	2	18,000	5,850	15,768	5,125
29 Rd	G Rd	N I-70 Frontg Rd	COL	0.424	2	12,000	5	5,088	2
2nd St	Front St	F Rd	COL	0.276	2	12,000	1,410	3,312	389
30 Rd	Hwy 50	B 1/2 Rd	COL	1.231	2	12,000	766	14,772	943
30 Rd	D Rd	E Rd	MA	0.878	2	24,000	7,489	21,072	6,575
30 Rd	E Rd	Patterson Rd	MA	1.120	4	40,000	17,250	44,800	19,320
30 Rd	Patterson Rd	F 1/2 Rd	COL	0.497	2	12,000	6,188	5,964	3,075
31 1/2 Rd	E Rd	F 1/2 Rd	COL	1.456	2	12,000	3,895	17,472	5,671
31 Rd	Hwy 50	F 1/2 Rd	COL	4.399	2	12,000	1,440	52,788	6,335
32 Rd	I-70 B	Frontage Rd	MA	0.023	4	32,000	3,440	736	79
32 Rd	E 1/2 Rd	32 Rd	MA	0.217	4	40,000	5,896	8,680	1,279
32 Rd	32 Rd	F Rd	MA	0.246	2	16,000	6,713	3,936	1,651
32 Rd	F Rd	E 1/2 Rd	COL	0.500	2	12,000	2,518	6,000	1,259
32 1/2 Rd	E Rd	F Rd	COL	0.836	2	12,000	2,209	10,032	1,847
33 Rd	D 1/2 Rd	D 3/4 Rd	COL	0.249	2	12,000	1,877	2,988	467
33 Rd	D 3/4 Rd	E Rd	COL	0.751	2	18,000	369	13,518	277
33 Rd	E 1/2 Rd	Node	COL	1.672	2	12,000	91	20,064	152
34 1/2 Rd	C 1/2 Rd	D Rd	COL	0.504	2	12,000	1,319	6,048	665
34 Rd	E 1/4 Rd	G Rd	COL	1.757	2	12,000	48	21,084	84
35 1/2 Rd	E Rd	E 1/2 Rd	COL	0.497	2	12,000	454	5,964	226
35 Rd	34 1/2 Rd	E Rd	COL	1.435	2	12,000	1,319	17,220	1,893
36 Rd	E 1/2 Rd	F Rd	COL	0.496	2	12,000	454	5,952	225
37 1/4 Rd	F Rd	F 1/4 Rd	COL	0.243	2	12,000	1,079	2,916	262
37 3/10 Rd	G Rd	I-70	COL	0.777	2	12,000	2,168	9,324	1,685
38 Rd	Horse Mntn Rd	G Rd	COL	0.921	2	12,000	1,947	11,052	1,793
A 1/2 Rd	30 Rd	31 Rd	COL	0.999	2	12,000	182	11,988	182
American Way	Base Rock St	Maldonado St	COL	0.236	2	12,000	3867	2,832	913
B 1/2 Rd	Hwy 50	27 1/2 Rd	MA	0.208	2	24,000	4,382	4,992	911
B 1/2 Rd	27 1/2 Rd	32 Rd	MA	4.520	2	16,000	4382	72,320	19,807
B Rd	27 Rd	30 Rd	COL	3.055	2	12,000	2269	36,660	6,932
Base Rock	Node	Node	COL	0.556	2	18,000	4,509	10,008	2,507
Belford Ave	N 4th St	N 5th St	MA	0.092	4	16,000	1,447	1,472	133
Belford Ave	N 24th St	28 Rd	COL	0.199	2	12,000	3,642	2,388	725
Bookcliff Ave	26 1/2 Rd	N 12th St	COL	0.467	2	12,000	2,623	5,604	1,225
C 1/2 Rd	32 Rd	34 1/2 Rd	COL	2.549	2	12,000	1,656	30,588	4,221
C Rd	31 Rd	32 Rd	COL	0.998	2	12,000	128	11,976	128

continued on next page

Table 18. Existing Major Roadway Inventory (continued)

Street	From	To	Type	Miles	Lns	Capacity	ADT	VMC	VMT
Canon St	Node	Hwy 50	COL	0.221	2	12,000	2,839	2,652	627
Coffman Rd	Hwy 141	Broadway	COL	3.662	2	12,000	10	43,944	37
Colorado Ave	S 3rd St	S 7th St	COL	0.365	2	12,000	7,799	4,380	2,847
Cortland Ave	27 1/2 Rd	28 Rd	COL	0.500	2	12,000	2,735	6,000	1,368
Crosby Ave	American Way	Broadway	COL	0.465	2	12,000	2,367	5,580	1,101
Crossroads Blvd	27 Rd	Horizon Dr	MA	1.088	2	16,000	6,177	17,408	6,721
D 1/2 Rd	29 Rd	D 1/2 Ct	COL	0.245	2	18,000	7,050	4,410	1,727
D 1/2 Rd	D 1/2 Ct	30 1/4 Rd	COL	1.044	2	12,000	7,050	12,528	7,360
D 1/2 Rd	30 1/4 Rd	Node	COL	0.077	2	18,000	9,619	1,386	741
D 1/2 Rd	Node	33 Rd	COL	2.669	2	12,000	7,669	32,028	20,469
D Rd	Monument Rd	Rosevale Rd	COL	0.306	2	12,000	2,191	3,672	670
D Rd	Node	Node	MA	0.373	4	32,000	4,849	11,936	1,809
D Rd	Node	Node	MA	0.300	2	16,000	4,983	4,800	1,495
D Rd	Node	Riverside Pkwy	MA	0.044	4	32,000	4,983	1,408	219
D Rd	D Rd	Node	PA	0.054	2	26,000	12,164	1,404	657
D Rd	29 Rd	32nd Rd	MA	2.993	2	16,000	15,986	47,888	47,846
Desert Rd	Hwy 50	Hwy 141	COL	4.787	2	12,000	11	57,444	53
DS Rd	17 3/10 Rd	Rim Rock Dr	COL	4.883	2	12,000	979	58,596	4,780
E 1/2 Rd	30 Rd	36 Rd	MA	1.497	2	16,000	5,706	23,952	8,542
E 1/2 Rd	32 Rd	Aaron Ct	COL	1.606	2	12,000	3,642	19,272	5,849
E 1/4 Rd	33 Rd	34 Rd	COL	1.009	2	12,000	833	12,108	840
E 3/4 Rd	20 1/2 Rd	20 3/4 Rd	COL	0.247	2	12,000	996	2,964	246
E Aspen Ave	N Mesa St	N Peach St	COL	1.212	2	12,000	4,328	14,544	5,246
E Grand Ave	Hwy 6 And 50	S PINE St	COL	0.485	2	12,000	612	5,820	297
E Ottley Ave	N Mesa St	Node	COL	0.447	2	12,000	4,369	5,364	1,953
E Pabor Ave	N Mesa St	N Maple St	COL	0.249	2	12,000	846	2,988	211
E Rd	30 Rd	35 1/2 Rd	COL	3.539	2	12,000	10,048	42,468	35,560
Elm Ave	N 7th St	Houston Ave	COL	1.848	2	12,000	2,868	22,176	5,300
F Rd	I-70 B	33 Rd	PA	0.675	2	26,000	17,935	17,550	12,106
F Rd	33 Rd	33 1/2 Rd	PA	0.512	2	18,000	8,076	9,216	4,135
F Rd	31 Rd	33 1/2 Rd	PA	1.320	4	44,000	19,165	58,080	25,298
F Rd	33 1/2 Rd	37 1/4 Rd	COL	1.721	2	12,000	1,323	20,652	2,277
F 1/4 Rd	37 1/4 Rd	Horse Mntain Rd	COL	0.809	2	12,000	1,485	9,708	1,201
F 1/2 Rd	25 Rd	32 Rd	COL	4.041	2	12,000	2,078	48,492	8,397
Frontage Rd	Timber Falls Dr	Hwy 6 and 50	COL	0.777	2	12,000	2,992	9,324	2,325
Frontage Rd	31 1/2 Rd	32 Rd	MA	0.487	2	16,000	3,860	7,792	1,880
G Rd	Power Rd	Hwy 6 & 50	COL	0.048	2	12,000	3,338	576	160
G Rd	Hwy 6 & 50	Horizon Dr	MA	4.944	2	16,000	1,727	79,104	8,538
G Rd	33 Rd	Front St	COL	3.710	2	12,000	1,398	44,520	5,187
Grand Ave	N 1ST St	N 7th St	MA	0.532	4	40,000	19,966	21,280	10,622
Grand Ave	N 7th St	N 12th St	MA	0.466	2	24,000	8,449	11,184	3,937
Grand Ave	N 12th St	28 Rd	COL	1.009	2	12,000	6,344	12,108	6,401
Gunnison Ave	N 1st St	N 9th St	COL	0.706	2	12,000	6,335	8,472	4,473
Gunnison Ave	N 9th St	N 12th St	COL	0.290	2	18,000	7,753	5,220	2,248
Gunnison Ave	N 12th St	Mantlo Cir	COL	0.809	2	12,000	3,912	9,708	3,165
H Rd	21 Rd	26 1/2 Rd	COL	4.495	2	12,000	1,074	53,940	4,828
H Rd	26 1/2 Rd	Jamaica Dr	COL	0.204	2	18,000	4,329	3,672	883
H Rd	Jamaica Dr	North Crest Dr	COL	1.131	2	12,000	3,117	13,572	3,525
H Rd	North Crest Dr	Horizon Dr	COL	0.455	2	18,000	1,659	8,190	755
Horizon Dr	26 1/2 Rd	N 2th St	MA	0.670	2	16,000	7,489	10,720	5,018

continued on next page

Table 18. Existing Major Roadway Inventory (continued)

Street	From	To	Type	Miles	Lns	Capacity	ADT	VMC	VMT
O Rd	16 Rd	19 Rd	COL	1.999	2	12,000	185	23,988	370
Old 6 and 50	Node	2 8/10 Rd	MA	11.956	2	16,000	64	191,296	765
Orchard Ave	1st St	26 Rd	COL	2.016	2	12,000	4,826	24,192	9,729
Orchard Ave	28 Rd	30 Rd	MA	0.591	2	24,000	9,842	14,184	5,817
Orchard Ave	Normandy Dr	29 Rd	MA	0.397	2	16,000	8,059	6,352	3,199
Orchard Ave	29 Rd	29 1/2 Rd	MA	0.503	2	24,000	7,877	12,072	3,962
Orchard Ave	29 1/2 Rd	30 Rd	MA	0.500	2	16,000	5,282	8,000	2,641
Ottley Ave	Node	N Pine St	COL	0.300	2	12,000	2,779	3,600	834
Patterson Rd	Hwy 6 & 50	26 Rd	PA	2.417	4	44,000	8,723	106,348	21,083
Patterson Rd	26 Rd	Mira Vista Rd	PA	0.297	4	36,000	30,773	10,692	9,140
Patterson Rd	Mira Vista Rd	View Point Dr	PA	0.385	4	44,000	30,640	16,940	11,796
Patterson Rd	View Point Dr	Node	PA	0.209	4	36,000	28,741	7,524	6,007
Patterson Rd	Node	31 Rd	PA	4.108	4	44,000	26,667	180,752	109,548
Pkwy Ramp	Node	Riverside Pkwy	RMP	0.380	2	12,000	1,651	4,560	627
Pkwy Ramp	Node	Node	PA	0.027	1	9,000	186	243	5
Pkwy Ramp	Node	Node	RMP	0.542	2	6,000	2,915	3,252	1,580
Pitkin Ave	Ute Ave	2nd St	PA	0.114	4	18,000	13,144	2,052	1,498
Pitkin Ave	S 2nd St	S 12th St	PA	0.921	6	27,000	13,144	24,867	12,106
Pitkin Ave	S 12th St	Node	PA	0.440	4	18,000	12,263	7,920	5,396
Rabbit Valley Rd	Node	Node	RMP	0.170	2	12,000	9	2,040	2
Redlands Pkwy	S Broadway	Broadway	COL	0.440	2	12,000	7,715	5,280	3,395
Redlands Pkwy	Colorado River	Pkwy Ramp	PA	0.809	4	36,000	17,688	29,124	14,310
Redlands Pkwy	S Camp Rd	S Broadway	COL	0.262	2	12,000	7,715	3,144	2,021
Redlands Pkwy	Broadway	Colorado River	PA	0.827	2	18,000	12,843	14,886	10,621
Redlands Pkwy	Node	Node	PA	0.022	4	36,000	17,435	792	384
Redlands Pkwy	Node	Node	PA	0.336	2	18,000	8,540	6,048	2,869
Redlands-Riverside	Node	Node	RMP	0.095	2	6,000	608	570	58
Reeder Mesa Rd	Hwy 50	Goodfellow Ct	COL	2.567	2	12,000	381	30,804	978
Ridges Blvd	Ridgeway Ct	Broadway	COL	0.753	2	12,000	7,717	9,036	5,811
Rimrock Dr	N 16 1/2 Rd	S Camp Rd	COL	23.005	2	12,000	288	276,060	6,625
River Rd	Frontage Rd	Pkwy Ramp	COL	4.607	2	12,000	3,886	55,284	17,903
Riverside Pkwy	Pkwy Ramp	Overpass	COL	1.389	2	18,000	2,722	25,002	3,781
Riverside Pkwy	Node	Node	COL	0.161	2	12,000	1,980	1,932	319
Riverside Pkwy	Node	Node	COL	0.039	4	24,000	444	936	17
Riverside Pkwy	Node	29 Rd	MA	1.556	2	24,000	12,885	37,344	20,049
Riverside Pkwy	Node	Node	PA	0.306	2	9,000	1,215	2,754	372
Riverside Pkwy	Node	Node	PA	0.115	4	44,000	17,227	5,060	1,981
Riverside Pkwy	Node	Node	PA	0.132	2	9,000	1,536	1,188	203
Riverside Pkwy	Node	Node	PA	1.713	4	44,000	17,670	75,372	30,269
Riverside Pkwy	Hwy 50 Exit	Hwy 50 on-ramp	PA	0.230	4	44,000	12,420	10,120	2,857
Riverside Pkwy	Node	S 9th St	PA	0.330	4	44,000	12,276	14,520	4,051
Riverside Pkwy	S 9th St	D Rd	PA	1.011	2	26,000	10,253	26,286	10,366
Riverside Pkwy	Node	Node	RMP	0.252	2	6,000	10,313	1,512	2,599
Riverside Pkwy	Node	Node	RMP	0.255	1	6,000	177	1,530	45
Riverside Pkwy	Node	Node	RMP	0.264	2	6,000	9,264	1,584	2,446
Rood Ave	N 1st St	N 7th St	COL	0.529	2	12,000	3,134	6,348	1,658
Rosevale Rd	S Redlands Rd	D Rd	COL	0.820	2	12,000	1,570	9,840	1,287
S 1st St	Ute Ave	Main St	PA	0.116	4	36,000	25,971	4,176	3,013
S 5th St	Hwy 50	Pitkin Ave	EXP	1.143	4	24,000	14,590	27,432	16,676
S 5th St	Pitkin Ave	Ute Ave	MA	0.068	4	32,000	15,318	2,176	1,042

continued on next page

Table 18. Existing Major Roadway Inventory (continued)

Street	From	To	Type	Miles	Lns	Capacity	ADT	VMC	VMT
S 4th St	Pitkin Ave	Main St	MA	0.205	4	16,000	4,410	3,280	904
S 5th St	Ute Ave	Main St	MA	0.131	6	24,000	7,584	3,144	994
S 7th St	Riverside Pkwy	Pitkin Ave	COL	0.539	2	18,000	1,203	9,702	648
S 7th St	Pitkin Ave	Main St	MA	0.202	4	40,000	8,117	8,080	1,640
S 9th St	Riverside Pkwy	4th Ave	COL	0.230	2	12,000	848	2,760	195
S 9th St	4th Ave	Ute Ave	MA	0.416	2	16,000	1,526	6,656	635
S 12th St	Pitkin Ave	Colorado Ave	PA	0.133	2	18,000	3,127	2,394	416
S 12th St	Colorado Ave	Main St	PA	0.070	2	26,000	3,127	1,820	219
S Broadway	Mnmnt Canyon Dr	S Camp Rd	COL	3.462	2	12,000	5,224	41,544	18,085
SB Pkwy on-ramp	Broadway	Riverside Pkwy	RMP	0.224	2	6,000	3,872	1,344	867
S Camp Rd	Monument Rd	Rimrock Rd	COL	0.626	2	12,000	3,335	7,512	2,088
S Camp Rd	Rimrock Rd	Buffalo Dr	COL	0.873	2	12,000	3,166	10,476	2,764
S Camp Rd	Buffalo Dr	Mckinley Dr	COL	0.858	2	18,000	2,419	15,444	2,076
S Camp Rd	Mckinley Dr	S Broadway	COL	0.295	2	12,000	3,605	3,540	1,063
S Coulson St	Hwy 6 & 50	W Aspen Ave	COL	0.051	2	12,000	3,664	612	187
S Maple St	Hwy 6 & 50	E Aspen Ave	COL	0.358	2	12,000	1,864	4,296	667
S Mesa St	Hwy 6 & 50	W Aspen Ave	COL	0.184	2	12,000	2,109	2,208	388
S Pine St	Hwy 6 & 50	J 2/10 Rd	COL	0.339	2	18,000	8,893	6,102	3,015
S Pine St	J 2/10 Rd	E Aspen Ave	COL	0.371	2	12,000	7,461	4,452	2,768
S Redlands Rd	Mount Sopris Dr	Monument Rd	COL	0.402	2	12,000	3,057	4,824	1,229
Teller Ave	I-70 B	29 Rd	RMP	0.189	4	24,000	3,973	4,536	751
Unaweep Ave	Hwy 50	29 Rd	COL	2.847	2	18,000	9,028	51,246	25,703
Ute Ave	S 1st St	N 5th St	PA	0.355	4	18,000	10,652	6,390	3,781
Ute Ave	S 5th St	S 12th St	PA	0.646	6	27,000	11,357	17,442	7,337
Ute Ave	S 12th St	I-70 B	PA	0.424	4	18,000	10,777	7,632	4,569
Warrior Way	I-70 B	E 1/2 Rd	COL	0.112	2	18,000	7,513	2,016	841
West Ave	Broadway	Riverside Pkwy	COL	0.170	2	12,000	8,172	2,040	1,389
W Aspen Ave	N Coulson St	N Mesa St	COL	0.250	2	12,000	4,037	3,000	1,009
W Grand Ave	Mulberry St	N 1st St	PA	0.154	4	44,000	20,840	6,776	3,209
W Ottley Ave	Hwy 6 And 50	N Mesa St	COL	0.885	2	12,000	1,256	10,620	1,112
W Pabor Ave	N Cherry St	N Mesa St	COL	0.251	2	12,000	2,587	3,012	649
Whitewtr Crk Rd	Reeder Mesa Rd	Node	COL	1.633	2	12,000	111	19,596	181
Subtotal, Non-State Roads				350.168				5,325,416	1,326,921
EB Off-Ramp	Node	Node	RMP	0.224	2	6,000	9,260	1,344	2,074
EB Off-Ramp	Node	Node	RMP	0.047	2	6,000	49	282	2
EB On-Ramp	Node	Node	RMP	0.031	2	6,000	2,984	186	93
EB On-Ramp	Node	Node	RMP	0.055	2	6,000	313	330	17
EB On-Ramp	Node	Node	RMP	0.321	2	6,000	3,110	1,926	998
EB to EB Off-ramp	Node	Node	RMP	0.201	2	6,000	9,211	1,206	1,851
EB to WB Off-ramp	Node	Node	RMP	0.035	2	6,000	29	210	1
EB to WB On-ramp	Node	Node	RMP	0.061	2	6,000	80	366	5
Hwy 6	N 1st St	I-70 B	PA	3.819	4	44,000	25,380	168,036	96,926
Hwy 6	Node	Node	RMP	0.316	4	12,000	11,903	3,792	3,761
Hwy 6	Node	Node	RMP	0.477	2	6,000	10,907	2,862	5,203
Hwy 6	Node	Node	RMP	0.101	4	12,000	11,903	1,212	1,202
Hwy 6	Node	N 1st St	PA	0.101	4	44,000	22,848	4,444	2,308
Hwy 6	F Rd	G Rd	PA	3.320	2	18,000	7,854	59,760	26,075
Hwy 6	G Rd	Shiraz Dr	PA	0.284	2	26,000	8,038	7,384	2,283
Hwy 6	Shiraz Dr	37 3/10 Rd	PA	0.388	2	18,000	6,705	6,984	2,602

continued on next page

Table 18. Existing Major Roadway Inventory (continued)

Street	From	To	Type	Miles	Lns	Capacity	ADT	VMC	VMT
Hwy 6	37 3/10 Rd	Peach Ave	PA	0.382	2	26,000	5,940	9,932	2,269
Hwy 6	Peach Ave	Rapid Creek Rd	PA	2.482	2	18,000	3,985	44,676	9,891
Hwy 6	Node	Node	RMP	0.418	2	6,000	673	2,508	281
Hwy 6	Rapid Creek Rd	I-70	RMP	0.372	2	6,000	475	2,232	177
Hwy 6/50 offramp	Hwy 6 and 50	Redlands Pkwy	RMP	0.244	2	6,000	659	1,464	161
Hwy 6/50 onramp	Redlands Pkwy	Hwy 6 & 50	RMP	0.265	2	6,000	5,266	1,590	1,395
Hwy 6 and 50	Node	Old Hwy 6 & 50	EXP	0.763	2	24,000	446	18,312	340
Hwy 6 and 50	Hwy 6 & 50	past 22 Rd	EXP	13.894	2	24,000	1,082	333,456	15,033
Hwy 6 and 50	Node	Node	EXP	0.081	4	48,000	25,077	3,888	2,031
Hwy 6 and 50	Node	Node	EXP	0.430	4	24,000	11,656	10,320	5,012
Hwy 6 and 50	Node	Patterson Rd	EXP	2.003	4	48,000	29,287	96,144	58,662
Hwy 6 and 50	Node	Node	EXP	0.984	4	24,000	13,115	23,616	12,905
Hwy 6 and 50	Node	Node	EXP	0.155	6	36,000	15,170	5,580	2,351
Hwy 6 and 50	Node	Rimrock Ave	EXP	1.259	6	72,000	32,103	90,648	40,418
Hwy 6 and 50	Rimrock Ave	Node	EXP	0.794	6	24,000	19,314	19,056	15,335
Hwy 6 and 50	Node	Node	EXP	0.256	6	12,000	8,406	3,072	2,152
Hwy 6 and 50	Node	Node	EXP	0.514	6	24,000	10,339	12,336	5,314
Hwy 6 and 50	Node	Node	EXP	0.216	6	48,000	20,001	10,368	4,320
Hwy 50	Unaweeep Ave	Palisade St	EXP	0.428	4	48,000	40,563	20,544	17,361
Hwy 50	Unaweeep Ave	Unaweeep Ave	EXP	1.116	4	24,000	19,139	26,784	21,359
Hwy 50	Palisade St	27 Rd	EXP	0.409	4	48,000	27,092	19,632	11,081
Hwy 50	27 Rd	B 1/2 Rd	EXP	0.294	4	24,000	13,212	7,056	3,884
Hwy 50	27 Rd	Hwy 50 Ramp	EXP	0.358	2	24,000	13,219	8,592	4,732
Hwy 50	B 1/2 Rd	27 1/2 Rd	EXP	0.375	4	24,000	9,085	9,000	3,407
Hwy 50	27 1/2 Rd	County Line	EXP	18.666	4	48,000	18,631	895,968	347,766
Hwy 50 Ramp	Hwy 50	Node	MA	0.135	2	8,000	4,114	1,080	555
Hwy 50 Ramp	Node	B 1/2 Rd	MA	0.221	2	24,000	4,148	5,304	917
Hwy 139	Node	Co Rd 258	MA	13.643	2	16,000	1,569	218,288	21,406
Hwy 141	Node	Hwy 50	MA	0.964	2	16,000	1,914	15,424	1,845
Hwy 141	Hwy 50	D Rd	PA	3.650	2	18,000	6,192	65,700	22,601
Hwy 141	D Rd	I-70 B	PA	1.792	4	44,000	17,659	78,848	31,645
Hwy 340	Raptor Rd	Red Cliffs Dr	MA	0.603	4	40,000	5,926	24,120	3,573
Hwy 340	Red Cliffs Dr	Kings View Rd	MA	0.655	4	32,000	3,553	20,960	2,327
Hwy 340	Kings View Rd	S Broadway	MA	4.026	2	16,000	2,884	64,416	11,611
Hwy 340	S Broadway	W Scenic Dr	PA	5.073	2	18,000	3,324	91,314	16,863
Hwy 340	W Scenic Dr	Pleasant Ridge Ln	PA	0.209	2	26,000	13,630	5,434	2,849
Hwy 340	Pleasant Ridge Ln	Ridges Blvd	PA	0.351	2	18,000	14,473	6,318	5,080
Hwy 340	Ridges Blvd	Country Club Park	PA	0.472	4	36,000	19,465	16,992	9,187
Hwy 340	Country Club Park	West Ave	PA	0.840	4	44,000	19,524	36,960	16,400
Hwy 340	West Ave	Pkwy On Ramp	PA	0.024	4	36,000	23,980	864	576
Hwy 340	Pkwy On Ramp	past Crosby Ave	PA	0.297	4	44,000	20,635	13,068	6,129
Hwy 340	W Aspen Ave	I-70	MA	0.209	4	40,000	15,948	8,360	3,333
Hwy 340	Ramp	Ramp	MA	0.095	4	40,000	14,906	3,800	1,416
I-70 B Ramp	I-70 B	29 Rd	RMP	0.277	2	6,000	5,356	1,662	1,484
I-70 Access Rd	Node	Node	RMP	0.179	2	6,000	6,429	1,074	1,151
I-70 Access Rd	Node	Node	RMP	0.529	2	6,000	5,558	3,174	2,940
I-70 Access Rd	Node	Node	RMP	0.562	2	6,000	5,733	3,372	3,222
I-70 B	Node	Node	EXP	0.147	4	24,000	17,021	3,528	2,502
I-70 B	Node	I-70 Off Ramp	EXP	5.886	4	48,000	18,112	282,528	106,607
I-70 B	Node	Node	EXP	0.377	4	24,000	12,901	9,048	4,864

continued on next page

Table 18. Existing Major Roadway Inventory (continued)

Street	From	To	Type	Miles	Lns	Capacity	ADT	VMC	VMT
I-70 B	Node	Node	RMP	0.353	2	6,000	7,341	2,118	2,591
Ramp	Node	Node	RMP	0.049	2	6,000	2,799	294	137
WB Off-Ramp	Node	Node	RMP	0.015	2	6,000	3,068	90	46
WB Off-Ramp	Node	Node	RMP	0.287	2	6,000	3,224	1,722	925
WB On-Ramp	Node	Node	RMP	0.245	2	6,000	8,387	1,470	2,055
WB On-Ramp	Node	Node	RMP	0.010	2	6,000	8,331	60	83
WB-EB off-ramp	Node	Node	RMP	0.065	2	6,000	222	390	14
WB-WB off-ramp	Node	Node	RMP	0.084	2	6,000	3,280	504	276
WB-WB on-ramp	Node	Node	RMP	0.054	2	6,000	8,645	324	467
Subtotal, State Roads				99.317			2,925,706		1,020,715
Total				449.485			8,251,122		2,347,636

Notes: ADT is average daily traffic volume; VMC is vehicle-miles of capacity, VMT is vehicle-miles of travel

Source: Mesa County GIS, March 19, 2018.

APPENDIX B: LAND USE DEFINITIONS

Recommended definitions for the land uses in the updated impact fee schedule are provided below. If these are adopted by ordinance or resolution, those that differ from or overlap with zoning or general definitions should have a disclaimer that they only apply to the impact fee section.

Single-Family Detached means the use of a lot for only one dwelling unit, including a mobile home not located in a mobile home park, provided that a single-family detached use may also include an accessory dwelling unit, if allowed by zoning, which shall be assessed the rate for a multi-family unit.

Multi-Family means a building containing two or more dwelling units. It includes duplexes, apartments, residential condominiums, townhouses, and timeshares.

Mobile Home/RV Park means a parcel (or portion thereof) or abutting parcels of land designed, used or intended to be used to accommodate two or more occupied mobile homes or recreational vehicles, with necessary utilities, vehicular pathways, and concrete pads or vehicle stands.

Hotel/Motel means a building or group of buildings on the same premises and under single control, consisting of sleeping rooms kept, used, maintained or advertised as, or held out to the public to be, a place where sleeping accommodations are supplied for pay to transient guests or tenants. This land use category includes rooming houses, boardinghouses, and bed and breakfast establishments.

Shopping Center/Commercial means an integrated group of commercial establishments planned, developed, owned or managed as a unit, or a free-standing retail or commercial use not otherwise listed in the impact fee schedule. Uses located on a shopping center outparcel are considered free-standing for the purposes of this definition. A retail or commercial use shall mean the use of a building or structure primarily for the sale to the public of nonprofessional services, or goods or foods that have not been made, assembled or otherwise changed in ways generally associated with manufacturing or basic food processing in the same building or structure. This category includes but is not limited to all uses located in shopping centers and the following free-standing uses:

- Amusement park
- Auto parts store
- Auto wrecking yard
- Automobile repair
- Bank without drive-through facilities
- Bar and cocktail lounge
- Camera shop
- Car wash
- Convenience food and beverage store without gas pumps
- Department store
- Florist shop
- Food store
- Grocery
- Hardware store

Health or fitness club
Hobby, toy and game shop
Junkyard
Laundromat
Laundry or dry cleaning
Lawn and garden supply store
Massage establishment
Music store
Newsstand
Nightclub
Racetrack
Recreation facility, commercial
Rental establishment
Repair shop, other than auto repair
School, commercial
Specialty retail shop
Supermarket
Theater, indoor (excluding movie theaters)
Used merchandise store
Variety store
Vehicle and equipment dealer

Auto Sales/Service means an establishment primarily engaged in selling new or used motor vehicles, and which may also provide repair and maintenance services.

Bank, Drive-In means an establishment providing banking services to the public that includes drive-in or drive-through facilities.

Convenience Store w/Gas Sales means an establishment offering the sale of motor fuels and convenience items to motorists.

Golf Course means a golf course that is not restricted primarily for use by residents of a residential development of which it is a part, including commercial uses such as pro shop or bar that are designed primarily to serve patrons.

Movie Theater means a stand-alone establishment, not located in a shopping center, offering the viewing of motion pictures for sale to the public.

Restaurant, Standard means a stand-alone establishment, not located in a shopping center but may be located on an out-parcel, that sells meals prepared on site, and does not provide drive-through or drive-in service.

Restaurant, Drive-Through means a stand-alone establishment, not located in a shopping center but may be located on an out-parcel, that sells meals prepared on site, and provides drive-through or drive-in service.

Office, General means a building exclusively containing establishments providing executive, management, administrative, financial, or non-medical professional services, and which may include ancillary services for office workers, such as a restaurant, coffee shop, newspaper or candy stand, or child care facilities. It may be the upper floors of a multi-story office building with ground floor retail uses. Typical uses include banks without drive-in facilities, real estate, insurance, property management, investment, employment, travel, advertising, secretarial, data processing, telephone answering, telephone marketing, music, radio and television recording and broadcasting studios; professional or consulting services in the fields of law, architecture, design, engineering, accounting and similar professions; interior decorating consulting services; and business offices of private companies, utility companies, trade associations, unions and nonprofit organizations. This category does not include an administrative office that is ancillary to a principal commercial or industrial use.

Office, Medical means a building primarily used for the examination and/or treatment of patients on an outpatient basis (with no overnight stays by patients) by health professionals, and which may include ancillary services for medical office workers or a medical laboratory to the extent necessary to carry out diagnostic services for the medical office's patients.

Animal Hospital/Vet Clinic means the use of a site primarily for the provision of medical care and treatment of animals, and which may include ancillary boarding facilities.

Hospital means an establishment primarily engaged in providing medical, surgical, or skilled nursing care to persons, including overnight or longer stays by patients.

Nursing Home means an establishment primarily engaged in providing limited health care, nursing and health-related personal care but not continuous nursing services.

Place of Worship means a structure designed primarily for accommodating an assembly of people for the purpose of religious worship, including related religious instruction for 100 or fewer children during the week and other related functions.

Day Care Center means a facility or establishment that provides care, protection and supervision for six or more children unrelated to the operator and which receives a payment, fee or grant for any of the children receiving care, whether or not operated for profit. The term does not include public or nonpublic schools.

Elementary/Secondary School means a school offering an elementary through high school curriculum.

Public/Institutional means a governmental, quasi-public or institutional use, or a non-profit recreational use, not located in a shopping center or separately listed in the impact fee schedule. Typical uses include higher education institutions, city halls, courthouses, post offices, jails, libraries, museums, military bases, airports, bus stations, fraternal lodges, parks and playgrounds. It also includes bus terminals, fraternal clubs, adult day care centers, dormitories, and prisons.

Industrial means an establishment primarily engaged in the fabrication, assembly or processing of goods. Typical uses include manufacturing plants, industrial parks, research and development laboratories, welding shops, wholesale bakeries, dry cleaning plants, and bottling works.

Warehouse means an establishment primarily engaged in the display, storage and sale of goods to other firms for resale, as well as activities involving significant movement and storage of products or equipment. Typical uses include wholesale distributors, storage warehouses, trucking terminals, moving and storage firms, recycling facilities, trucking and shipping operations and major mail processing centers.

Mini-Warehouse means an enclosed storage facility containing independent, fully enclosed bays that are leased to persons for storage of their household goods or personal property.

APPENDIX C: LEGAL FRAMEWORK

Impact fees are a way for local governments to require new developments to pay a proportionate share of the infrastructure costs they impose on the community. In contrast to “negotiated” developer exactions, impact fees are charges assessed on new development using a standard formula based on objective characteristics, such as the number and type of dwelling units constructed. The fees are a one-time, up-front charge, with the payment made at the time of building permit issuance. Impact fees require that each new development project pay a pro-rata share of the cost of new capital facilities required to serve that development.

Dual Rational Nexus Test

Impact fees were pioneered in states that lacked specific enabling legislation, and they have generally been legally defended as an exercise of local government’s broad “police power” to regulate land development in order to protect the health, safety and welfare of the community. To distinguish regulatory impact fees from unauthorized taxes, state courts have developed guidelines for constitutionally-valid impact fees, based on the “rational nexus” standard. The standard essentially requires that fees must be proportional to the need for additional infrastructure created by the new development, and the fees must be spent to provide that same type of infrastructure to benefit new development. A Florida district court of appeals described the dual rational nexus test in 1983 as follows, and this language was subsequently quoted and followed by the Florida Supreme Court in its 1991 St. Johns County decision:¹

In order to satisfy these requirements, the local government must demonstrate a reasonable connection, or rational nexus, between the need for additional capital facilities and the growth in population generated by the subdivision. In addition, the government must show a reasonable connection, or rational nexus, between the expenditures of the funds collected and the benefits accruing to the subdivision. In order to satisfy this latter requirement, the ordinance must specifically earmark the funds collected for use in acquiring capital facilities to benefit the new residents.

The Need Test

To meet the first prong of the dual rational nexus test, it is necessary to demonstrate that new development creates the need for additional roadway facilities. The demand on roadways created by new developments of different types is quantified in the form of trip generation rates per housing unit and per various measures of nonresidential development. Transportation impact fees are designed to be proportional to the capacity needed to accommodate each new development.

The Benefit Test

To meet the second prong of the dual rational nexus test, it is necessary to demonstrate that new development subject to the fee will benefit from the expenditure of the impact fee funds. One requirement is that the fees actually be used to fill the need that serves as the justification for the fees under the first part of the test.

¹ St. Johns County v. Northeast Florida Builders Association, Inc., 583 So.2d 635, April 18, 1991

Colorado Statutes

Impact fees were pioneered by local governments in the absence of explicit state enabling legislation. Consequently, such fees were originally defended as an exercise of local government's broad "police power" to protect the health, safety and welfare of the community. The courts gradually developed guidelines for constitutionally valid impact fees, based on a "rational nexus" that must exist between the regulatory fee or exaction and the activity that is being regulated.

Prior to 2001, the authority of counties in Colorado to impose transportation impact fees was not entirely clear. Several counties had adopted impact fees, which they felt were authorized under counties' implied powers. This changed with the passage of SB 15 by the Legislature and its signature by the governor on November 16, 2001. Among other things, this bill created a new section 104.5: Impact Fees, in Article 20 of Title 29, Colorado Revised Statutes, which includes the following authorization and major requirements:

(1) Pursuant to the authority granted in section 29-20-104 (1) (g) and as a condition of issuance of a development permit, a local government may impose an impact fee or other similar development charge to fund expenditures by such local government ... needed to serve new development. No impact fee or other similar development charge shall be imposed except pursuant to a schedule that is:

- (a) Legislatively adopted;*
- (b) Generally applicable to a broad class of property; and*
- (c) Intended to defray the projected impacts on capital facilities caused by proposed development.*

(2) (a) A local government shall quantify the reasonable impacts of proposed development on existing capital facilities and establish the impact fee or development charge at a level no greater than necessary to defray such impacts directly related to proposed development. No impact fee or other similar development charge shall be imposed to remedy any deficiency in capital facilities that exists without regard to the proposed development.

...

(3) Any schedule of impact fees or other similar development charges adopted by a local government pursuant to this section shall include provisions to ensure that no individual landowner is required to provide any site specific dedication or improvement to meet the same need for capital facilities for which the impact fee or other similar development charge is imposed. ...

SB 15 clearly authorized counties in Colorado to assess impact fees. It also imposed requirements relating to level of service, proportionality, and developer credits. Another important legal requirement not addressed in Colorado statutes but firmly rooted in impact fee case law is the need to provide revenue credits to avoid double-charging by charging both impact fees and other taxes (rather than improvements required as a condition of development). These topics are discussed below. Other statutory provisions require accounting for fee revenues in special funds and authorize waivers of fees for affordable housing.

Level of Service

Subsection 104.5(2)(a) of the Impact Fees statute requires that the fees not exceed the cost directly related to the proposed development, and that they not be used to remedy any existing deficiency. The statute does not use the term “level of service,” but the concept is implicit in establishing the relationship of the cost of improvements to the new development, as well as in determining existing deficiencies. These provisions get to the heart of the one of the most fundamental principles established in impact fee case law, which is that impact fees should not charge new development for a higher level of service than is provided to existing development. Basing the fees on a higher level of service (LOS) than is being provided to existing development means there is a deficiency in existing facilities to provide the same LOS new development is paying for through the impact fee. Such a deficiency needs to be paid for in such a way that it does not burden new development. The methodology used in this study results in a fee that does not exceed the cost to maintain the existing LOS.

Proportionality

One of the fundamental legal principles of impact fee case law is that the fees for each individual land use type should be proportional to the impact of that use. This is reflected in subsection (2)(a), which requires that the fees be “directly related” to the impacts of new development. The language could also be read as allowing lower fees for some uses compared to others, as long as the fee for each use does not exceed the cost attributable to the development. However, if the fees are not based on the actual impact of the development, there is a risk that the courts may deem it to be an unauthorized tax rather than a fee. There may be a temptation to simply adopt fees at a lower rate for certain types of development that are seen as more desirable. A better approach would be to appropriate general fund monies to pay a portion of the fees for desired types of development. It would also be advisable to calculate a revenue credit to account for future general fund taxes that non-subsidized development will generate that will be used to subsidize fees for other classes of development.

Developer Credits

Another fundamental requirement articulated in impact fee case law is the need to avoid double-charging new development through impact fees and other requirements or taxes. Subsection 104.5(3) reflects this principle in the context of improvements required as a condition of development approval. It states that developers should not be required to make “site-specific dedications or improvements” that “meet the same need” being addressed by the impact fees while also being required to pay the fee. In general, impact fees should be reduced by the value of dedications or improvements required of developers for the same type of improvements that would be eligible to be funded with the impact fees. These reductions are referred to as developer credits.

It is reasonable to have some restrictions on the types of improvements that are eligible for credit. Granting credits is essentially spending future impact fees, and the fees should be spent for priority improvements that benefit the community at large. Developers should not be allowed to monopolize the fees for localized improvements if they choose to develop in areas that lack adequate infrastructure. For example, credit eligibility could be restricted to contributions related to projects identified in a

local or regional transportation master plan or capital improvements plan. However, developers should be eligible for credits for required improvements related to projects that are consistent with the jurisdiction's land use and capital plans.

The updated fees do not include the cost of rights-of-way (ROW). This does not mean that the fees cannot be spent to acquire ROW needed to accommodate future capacity-expanding improvements. However, if a jurisdiction decides not to give developers credit for required ROW dedications on the major roadway system related to a future capacity-expanding project, it might be appropriate to restrict the fees collected to be spent only on improvements. This issue has not been litigated, but the expenditure restriction would establish a bright line between what the fees are and are not designed to pay for, and avoid any argument that developments paying the fee are not getting the full benefit of the improvements they are paying for through the fees.

Revenue Credits

A revenue credit is a reduction from the cost per service unit designed to equalize the burden between existing and new development arising from the expenditure of future revenues that can be attributed in part to new development. While developer credits are provided on a case-by-case basis, revenue credits must be addressed in the fee calculation study.

As noted above, if there are existing deficiencies with respect to the level of service used in the fee calculation, the fees should be reduced by a credit that accounts for the contribution of new development toward remedying the existing deficiencies. A similar situation arises when the existing level of service has not been fully paid for. Outstanding debt on existing facilities that are counted in the existing level of service will be retired, in part, by revenues generated from new development. Given that new development will pay impact fees to provide the existing level of service for itself, the fact that new development may also be paying for the facilities that provide that level of service for existing development could amount to paying for more than its proportionate share. Consequently, impact fees should be reduced to account for future payments that will retire outstanding debt on existing facilities that provide the level of service on which the fees are based for existing development.

The issue is less clear-cut when it comes to other types of revenue that may be used to make capacity-expanding capital improvements of the same type being funded by impact fees. The clearest case occurs when non-impact fee general fund tax revenues are programmed for capacity-expanding improvements on an "as available" basis because impact fees are insufficient to fund all needed growth-related improvements. These capacity-adding projects that may be funded in the future with non-impact fee dollars will be paid for by both existing and new development and will increase the overall level of service, benefitting both existing development and future growth.

Similar considerations apply to dedicated funding sources, such as special taxes that can only be used for the same type of facilities as the impact fees. Like discretionary revenue, these types of dedicated revenue sources are typically not specifically dedicated only for capacity-expanding improvements, and even if they are, their use to fund capacity-related improvements improves the level of service for both existing and new development.

Outside funding or grants for capacity-expanding improvements to major roads that can reasonably be anticipated in the future could warrant a credit, but this is not clear-cut. In addition to the argument made above (i.e., the additional funding raises the level of service and benefits both new development and existing development), two additional arguments can be made against providing credits for such funding. First, new development in a community does not directly pay for State and Federal grants in the same way they pay local gasoline and property taxes. Second, future grant funding is far more uncertain than dedicated revenue streams.

While these arguments are compelling, they have not been litigated, and the law on whether revenue credits may be warranted in situations other than existing deficiencies or outstanding debt on existing facilities is currently unclear. In addition, such credits were provided in the original 2002 impact fee study. This update continues to incorporate revenue credits for both local and Federal/State non-impact fee funding anticipated to be available to help fund growth-related transportation improvements.

If fees are disproportionately reduced or waived for selected land use categories or types of development, a revenue credit should probably be provided for other land uses not subject to the reduction. Even if the targeted reductions are replaced with general funds, new development that is not eligible for the reduction will generate future general fund revenues that will be used to pay for the reduced fees for eligible development. This could arguably amount to new development that is not eligible paying more than its proportionate share of transportation improvement costs. While this issue has not been litigated, the prudent course would be either not to apply targeted fee reductions or else calculate an appropriate revenue credit for non-eligible development types.

APPENDIX D: METHODOLOGY

This appendix describes the methodology used to develop the transportation impact fees. A key concept in any transportation impact fee methodology is the definition of the “service unit,” which is described first. This description is followed by an explanation of the “consumption-based” model used in this study. Finally, the appendix concludes with a description of the formula used to calculate the transportation impact fees.

Service Unit

A service unit creates the link between supply (roadway capacity) and demand (traffic generated by new development). An appropriate service unit basis for transportation impact fees is vehicle-miles of travel (VMT). Vehicle-miles is a combination of the number of vehicles traveling during a given time period and the distance (in miles) those vehicles travel.

The two time periods most often used in traffic analysis are the 24-hour day (average daily trips or ADT) and the single hour of the day with the highest traffic volume (peak hour trips or PHT). The current transportation impact fee system is based on ADT. The regional transportation model is also based on ADT. Daily trips will continue to be used in this update.

Consumption-Based Model

The two traditional alternative methodologies for calculating transportation impact fees are the “improvements-driven” and “consumption-based” approaches. The consumption-based methodology continues to be recommended for Mesa County’s transportation impact fees.

The “improvements-driven” approach essentially divides the cost of growth-related improvements required over a fixed planning horizon by the number new service units (e.g., vehicle-mile of travel or VMT) projected to be generated by growth over the same planning horizon in order to determine a cost per service unit. The improvements-driven approach depends on accurate planning and forecasting. For example, the fees will be accurate only if the forecasted increase in traffic actually necessitates all of the improvements identified in the transportation master plan. If many of the planned improvements will provide excess capacity that will be available to serve additional development beyond the planning horizon on which the fees are based, the fees may be too high.

The “consumption-based” approach does not depend on knowing in advance what improvements will be made or what type or density of development will occur. The consumption-based model simply charges a new development the cost of replacing the capacity that it will consume on the major roadway system. That is, for every service unit of traffic generated by the development, the transportation impact fee charges the net cost to construct an additional service unit of capacity. Compiling a list of planned improvements needed to accommodate projected growth is not necessary for the development of consumption-based transportation impact fees, which can be calculated based on any representative list of road improvements, including an historical list or a list of projects needed at build-out.

In a consumption-based system, the list of road improvements is used to determine the cost per unit of capacity. Thus, doubling the total cost of the list of road improvements will not double the fee and in fact may very well not increase the fee at all. Only if the improvements added to the list were more expensive, per unit of capacity created, would their addition have the effect of increasing the impact fee.

In most rapidly growing communities, some roadways will be experiencing an unacceptable level of congestion at any given point in time. One of the principles of impact fees is that new development should not be charged, through impact fees, for a higher level of service than is provided to existing development. A consumption-based fee, unlike an improvements-driven one, is not designed to recover the full costs to maintain the desired LOS on all roadway segments. Instead, it is only designed to maintain a minimum system-wide ratio between demand and capacity. Virtually all major roadway systems have more capacity (VMC) than demand (VMT) on a system-wide basis. Consequently, under a consumption-based system, the level of service standard is the system-wide VMC/VMT ratio. If the major roadway system currently has a VMC/VMT ratio higher than the one on which the fees are based, there are no existing deficiencies.

Since travel is never evenly distributed throughout a roadway system, actual roadway systems require more than one unit of capacity for every unit of demand in order for the system to function at an acceptable level of service. Suppose, for example, that the community completes a major arterial widening project. The completed arterial is likely to have a significant amount of excess capacity for some time. If the entire system has just enough capacity to accommodate all the vehicle-miles of travel, then the excess capacity on this segment must be balanced by another segment being over-capacity. Clearly, roadway systems in the real world need more total aggregate capacity than the total aggregate demand, because the traffic does not always precisely match the available capacity. Consequently, the standard consumption-based model generally underestimates the full cost of growth.

A modified consumption-based transportation impact fee model that more accurately identifies the full growth-related cost of maintaining desired service levels uses the system-wide ratio of capacity to demand. Essentially, this approach requires that new development pay for the cost to construct more capacity than it directly consumes in order to maintain the system-wide ratio of capacity to demand. In this system, the cost per vehicle-mile of capacity (VMC) is multiplied by the system-wide ratio of VMC/VMT to determine the cost per VMT. The existing major roadway system has an overall ratio of 3.51 vehicle-miles of capacity for every vehicle-mile of travel, as shown in Table 19. However, that ratio may not be sustainable over the long term. As communities grow and become more urban, the ratio tends to fall. The 2002 study used a 1.50 VMC/VMT ratio. The 1.00 ratio implicit in the standard consumption-based methodology is recommended for this update.

Table 19. Existing Major Roadway Level of Service

	Non-State Roads	State Roads	Total System
Daily VMC on Major Roads	5,325,416	2,925,706	8,251,122
÷ Daily VMT on Major Roads	1,326,921	1,020,715	2,347,636
Existing VMC/VMT Ratio	4.01	2.87	3.51
Recommended VMC/VMT Ratio for Impact Fee Calculation			1.00

Source: VMC and VMT from Table 18 in the appendix.

The formula for the modified consumption-based methodology used in this study is summarized in Figure 6. The maximum fee calculated under this methodology is the number of service units (VMT) that will be generated by the development times the net cost per service unit. The inputs into the formula are described in more detail below.

Figure 6. Transportation Impact Fee Formula

$$\text{FEE} = \text{VMT} \times \text{NET COST/VMT}$$

Where:

$$\text{VMT} = \text{TRIPS} \times \% \text{ NEW} \times \text{LENGTH}$$

$$\text{TRIPS} = 1/2 \text{ average daily trip ends generated by the development during the work week}$$

$$\% \text{ NEW} = \text{Percent of trips that are primary trips, as opposed to passby or diverted-link trips}$$

$$\text{LENGTH} = \text{Average length of a trip on major roadway system}$$

$$\text{NET COST/VMT} = \text{COST/VMT} - \text{CREDIT/VMT}$$

$$\text{COST/VMT} = \text{COST/VMC} \times \text{VMC/VMT}$$

$$\text{COST/VMC} = \text{Average cost to create a new VMC based on historical or planned improvements}$$

$$\text{VMC/VMT} = \text{The system-wide ratio of capacity to demand in the major roadway system}$$

$$\text{CREDIT/VMT} = \text{Credit per VMT, based on revenues to be generated by new development}$$

APPENDIX E: TRIP RATES BY UNIT SIZE

The calculation of average daily trip generation rates for single-family detached units by dwelling unit size is addressed in this appendix. Information from U.S. Census for the Mesa County area, the national American Housing Survey, and the National Cooperative Highway Research Program are utilized in the calculations.

The 2017 American Housing Survey provides national data on the average size of single-family units by number of bedrooms in square feet of living area. This data is based on a national sample of over 34,000 single-family detached units containing one or more bedrooms (efficiency units have a very small sample size and are excluded from the analysis). The average sizes of single-family units by number of bedrooms are summarized in Table 20. These national average sizes should be reasonably representative of existing development in Mesa County.

Table 20. Unit Size by Number of Bedrooms, Single-Family

No. of Bedrooms	Sample Units	Weighted Square Feet	Weighted Units	Average Size
1	602	1,600,040,501	1,486,842	1,076
2	4,768	15,727,551,611	11,053,273	1,423
3	16,920	70,835,665,150	38,294,217	1,850
4 or more	12,483	70,293,266,037	25,784,587	2,726
Total	34,773	158,456,523,300	76,618,920	2,068

Source: U.S. Census Bureau, 2017 American Housing Survey, national microdata.

The Census Bureau conducts annual surveys of housing units, which include information on the number of bedrooms and the number of persons residing in the unit. These annual surveys are combined into 5-year data sets. The most recent is the 5% sample covering the years 2013-2017 and including over 3,700 units. To get a large enough sample in all bedroom categories (other than efficiencies, which were excluded) it was necessary to use data for the region that includes Mesa County and four adjoining Colorado counties. Mesa County accounts for 64% of the population of the five-county region, according to U.S. Census population estimates for 2017. These recent, localized data identify the following average number of persons per unit by number of bedrooms, which should be representative of the average occupancy in single-family detached units in Mesa County.

Table 21. Persons per Unit by Bedrooms, Single-Family

No. of Bedrooms	Sample Units	Weighted Persons	Weighted Units	Persons/Unit
1	132	2,328	2,326	1.00
2	663	20,215	12,503	1.62
3	2,050	90,447	42,253	2.14
4 or more	883	47,398	17,068	2.78
Total	3,728	160,388	74,150	2.16

Source: U.S. Census Bureau, *American Community Survey*, 2013-2017 5% sample microdata for Mesa, Montrose, Delta, San Miguel, and Ouray Counties.


The National Cooperative Highway Research Program (NCHRP) of the National Research Council has developed estimates of average daily trip generation rates by the number of persons in a household. The NCHRP data indicate that trip generation is strongly related to the number of people residing in the unit, as shown in Table 22 and illustrated in Figure 7. While the trip rates themselves are somewhat dated due to the age of the study, the relative differences are still reasonable to rely on, if adjustments are made to account for the slight overall change in the average trip generation rates over the interval.²

Table 22. Trip Rates by Household Size

Household Size	Average Daily Trip Ends
One Person	3.3
Two Persons	6.4
Three Persons	9.8
Four Persons	11.2
Five or more Persons	12.8

Source: National Cooperative Highway Research Program, National Research Council, *NCHRP Report 365: Travel Estimation Techniques for Urban Planning*, Washington, D.C., 1998, Table 9: Trip estimation variables by urban size (for urban areas with population of 200,000-499,999)

Figure 7. Trip Rates by Household Size



² The average trip generation rate for a single-family detached unit declined 1.4% from the 6th edition (1997) to the 10th edition (2017) of the ITE *Trip Generation Manual* (9.57 in 1997 to 9.44 in 2017).

Data on unit size (in square feet) and the number of persons in the unit can be brought together because both sources also collect information on a related measure of unit size – the number of bedrooms. Then the number of persons in the unit can be related to trip generation, after adjusting for the overall decline in trip generation as well as the current average persons per unit for single-family units in Mesa County. The resulting trip generation rates for single-family detached units are presented in Table 23 for four unit size categories.

Table 23. Daily Trip Ends by Unit Size, Single-Family

No. of Bedrooms	Average Sq. Feet	Unit Size Range	Persons/ Unit	Daily Trips
1	1,076	<1,250 sf	1.00	4.54
2	1,423	1,250-1,649 sf	1.62	7.57
3	1,850	1,650-2,299 sf	2.14	8.81
4+	2,726	2,300 sf+	2.78	11.92
Total	2,068		2.16	9.44

Source: Average square feet from Table 20; unit size ranges based on approximate midpoints between the four average sizes; persons per unit from Table 21; daily trip ends based on linear interpolation between household size categories in Table 22, normalized for average persons per single-family unit from Table 21 and single-family average trip generation rate from Institute of Transportation Engineers, *Trip Generation Manual*, 2017.

2019 Impact Fee Study

Prepared for:

City of Grand Junction, Colorado

August 8, 2019

Prepared by:



4701 Sangamore Road

Suite S240

Bethesda, Maryland 20816

800.424.4318

www.tischlerbise.com

[PAGE INTENTIONALLY LEFT BLANK]

IMPACT FEE STUDY

TABLE OF CONTENTS

EXECUTIVE SUMMARY	1
COLORADO IMPACT FEE ENABLING LEGISLATION.....	1
ADDITIONAL LEGAL GUIDELINES	2
PROPOSED MAXIMUM SUPPORTABLE IMPACT FEE	3
Figure 1. Summary of City of Grand Junction Impact Fees	3
MAXIMUM SUPPORTABLE IMPACT FEES	3
Figure 2. Maximum Supportable Impact Fee.....	4
GENERAL METHODS FOR IMPACT FEES	5
<i>Cost Recovery Method (past improvements)</i>	5
<i>Incremental Expansion Method (concurrent improvements)</i>	5
<i>Plan-Based Method (future improvements)</i>	5
EVALUATION OF POSSIBLE CREDITS.....	6
MUNICIPAL FACILITIES DEVELOPMENT IMPACT FEE	7
Figure M1. Municipal Facilities Impact Fee Methodology Chart	7
MUNICIPAL FACILITIES PROPORTIONATE SHARE FACTORS.....	8
Figure M2. City of Grand Junction Functional Population	8
<i>Municipal Facilities Level of Service and Capital Costs</i>	9
Figure M3. Municipal Facilities Level of Service and Cost Factors	10
PROJECTION OF GROWTH-RELATED MUNICIPAL FACILITIES FACILITY NEEDS	10
Figure M4. 10-Year Municipal Facilities Infrastructure Needs to Accommodate Growth	11
MAXIMUM SUPPORTABLE MUNICIPAL FACILITIES IMPACT FEE	12
Figure M5. Maximum Supportable Municipal Facilities Impact Fee.....	12
REVENUE FROM MUNICIPAL FACILITIES IMPACT FEE	13
Figure M6. Estimated Revenue from Municipal Facilities Impact Fee.....	13
FIRE IMPACT FEE	14
Figure F1. Fire Facilities Impact Fee Methodology Chart.....	15
FIRE SERVICE AREA	16
Figure F2. Fire and EMS Incident Data for Two-Year Period	16
FIRE PROPORTIONATE SHARE FACTORS	16
Figure F3. City of Grand Junction Functional Population	17
<i>Fire Station Level of Service</i>	17
Figure F4. Fire Station Level of Service and Cost Factors	18
<i>Fire Apparatus Level of Service</i>	19
Figure F5. Fire Apparatus Inventory and Level of Service.....	20
PROJECTION OF GROWTH-RELATED FIRE NEEDS	21
Figure F6. 10-Year Fire Infrastructure Needs to Accommodate Growth	21

Figure F7. 10-Year Fire Apparatus Needs to Accommodate Growth	22
<i>Fire Debt Service Credit</i>	23
Figure F8. Fire Debt Principal Payment Credit	23
MAXIMUM SUPPORTABLE FIRE IMPACT FEE	24
Figure F9. Maximum Supportable Fire Impact Fee	24
REVENUE FROM FIRE IMPACT FEE	25
Figure F10. Estimated Revenue from Fire Impact Fee	25
POLICE IMPACT FEE	26
Figure P1. Police Impact Fee Methodology Chart	27
POLICE PROPORTIONATE SHARE FACTORS	27
Figure P2. City of Grand Junction Functional Population	28
<i>Police Station Level of Service</i>	28
Figure P3. Police Station Level of Service and Cost Factors	29
PROJECTION OF GROWTH-RELATED POLICE FACILITY NEEDS	30
Figure P4. 10-Year Police Space Needs to Accommodate Growth	30
<i>Police Debt Service Credit</i>	30
Figure P5. Police Debt Principal Payment Credit	31
MAXIMUM SUPPORTABLE POLICE IMPACT FEE	31
Figure P6. Maximum Supportable Police Impact Fee	32
REVENUE FROM POLICE IMPACT FEE	32
Figure P7. Estimated Revenue from Police Impact Fee	33
PARKS & RECREATION IMPACT FEE	34
Figure PR1. Parks & Recreation Impact Fee Methodology	35
PARKS & RECREATION LEVEL OF SERVICE AND COST FACTORS	36
<i>Current Inventory of Parkland and Improvements</i>	36
<i>Parkland Improvements Level of Service</i>	37
Figure PR2. Level 1 Parkland Level of Service	37
Figure PR3. Level 2 Parkland Level of Service	38
PROJECTION OF GROWTH-RELATED PARK IMPROVEMENT NEEDS	39
Figure PR4. 10-Year Level 1 Park Improvement Needs to Accommodate Growth	39
Figure PR5. 10-Year Level 2 Park Improvement Needs to Accommodate Growth	40
PARKS & RECREATION IMPACT FEE	41
Figure PR6. Maximum Supportable Park & Recreation Impact Fee	41
REVENUE FROM PARKS & RECREATION IMPACT FEE	41
Figure PR7. Estimated Revenue from Parks & Recreation Impact Fee	42
IMPLEMENTATION AND ADMINISTRATION	43
CREDITS AND REIMBURSEMENTS	43
SERVICE AREA	43
APPENDIX A: LAND USE ASSUMPTIONS	44

OVERVIEW	44
Figure A1: Grand Junction Municipal Boundary	44
RESIDENTIAL DEVELOPMENT	45
<i>Population and Housing Units</i>	45
Figure A2: Map of 201 Sewer Service Boundary and TAZ Areas	45
<i>Persons per Housing Unit</i>	45
Figure A3: Persons per Household and Persons per Housing Unit by Type of Housing.....	46
<i>Recent Residential Construction</i>	46
Figure A4: Recent Grand Junction Residential Permit Activity	47
<i>Current Population and Housing within Grand Junction City Limits</i>	47
Figure A5: Grand Junction 2018 Population and Housing Unit Estimate	47
<i>Current Population and Housing within 201 Growth Area Boundary</i>	47
Figure A6: 2018 Population and Housing Unit Estimates 201 Boundary Selected TAZ	48
<i>Projected Population and Housing Units</i>	48
Figure A7: Grand Junction Residential Development Projections for Selected TAZ Areas	48
NONRESIDENTIAL DEVELOPMENT	48
<i>Employment Density Factors and Trip Generation Factors</i>	49
Figure A8: Nonresidential Demand Indicators	49
<i>Nonresidential Floor Area and Employment</i>	49
Figure A9: 2010 Grand Junction vs. 201 Sewer Boundary Employment Distribution	50
Figure A10: Grand Junction Nonresidential Floor Area and Employment Estimates 2018.....	50
<i>Projected Nonresidential Floor Area and Employment</i>	50
Figure A11: Nonresidential Development Projections–Selected 201 Boundary TAZ Areas.....	51
SUMMARY OF GROWTH INDICATORS	52
Figure A12: Summary of Development Projections and Growth Rates	52
DEVELOPMENT PROJECTIONS	52
Figure A13: Development Projections Summary Selected TAZ Areas	53
Figure A14: Nonresidential Vehicle Trip Projections	54
APPENDIX B: LAND USE DEFINITIONS	55
RESIDENTIAL DEVELOPMENT	55
NONRESIDENTIAL DEVELOPMENT	55

EXECUTIVE SUMMARY

Impact fees are one-time payments for new development's proportionate share of the capital cost of infrastructure. The following study addresses the City of Grand Junction's Municipal Facilities, Fire, Police, and Parks & Recreation facilities. Impact fees do have limitations and should not be regarded as the total solution for infrastructure funding. Rather, they are one component of a comprehensive funding strategy to ensure provision of adequate public facilities. Impact fees may only be used for capital improvements or debt service for growth-related infrastructure. They may not be used for operations, maintenance, replacement of infrastructure, or correcting existing deficiencies. Although Colorado is a "home-rule" state and home-rule municipalities were already collecting "impact fees" under their home-rule authority granted in the Colorado Constitution, the Colorado Legislature passed enabling legislation in 2001, as discussed further below.

Colorado Impact Fee Enabling Legislation

For local governments, the first step in evaluating funding options for facility improvements is to determine basic options and requirements established by state law. Some states have more conservative legal parameters that basically restrict local government to specifically authorized actions. In contrast, "home-rule" states grant local governments broader powers that may or may not be precluded or preempted by state statutes depending on the circumstances and on the state's particular laws. Home rule municipalities in Colorado have the authority to impose impact fees based on both their home rule power granted in the Colorado Constitution and the impact fee enabling legislation enacted in 2001 by the Colorado General Assembly.

Impact fees are one-time payments imposed on new development that must be used solely to fund growth-related capital projects, typically called "system improvements". An impact fee represents new growth's proportionate share of capital facility needs. In contrast to project-level improvements, impact fees fund infrastructure that will benefit multiple development projects, or even the entire service area, as long as there is a reasonable relationship between the new development and the need for the growth-related infrastructure.

According to Colorado Revised Statute Section 29-20-104.5, impact fees must be legislatively adopted at a level no greater than necessary to defray impacts generally applicable to a broad class of property. The purpose of impact fees is to defray capital costs directly related to proposed development. The statutes of other states allow impact fee schedules to include administrative costs related to impact fees and the preparation of capital improvement plans, but this is not specifically authorized in Colorado's statute. Impact fees do have limitations and should not be regarded as the total solution for infrastructure funding. Rather, they are one component of a comprehensive portfolio to ensure adequate provision of public facilities. Because system improvements are larger and costlier, they may require bond financing and/or funding from other revenue sources. To be funded by impact fees, Section 29-20-104.5 requires that the capital improvements must have a useful life of at least five years. By law, impact fees can only be used for

capital improvements, not operating or maintenance costs. Also, impact fees cannot be used to repair or correct existing deficiencies in existing infrastructure.

Additional Legal Guidelines

Both state and federal courts have recognized the imposition of impact fees on development as a legitimate form of land use regulation, provided the fees meet standards intended to protect against regulatory takings. Land use regulations, development exactions, and impact fees are subject to the Fifth Amendment prohibition on taking of private property for public use without just compensation. To comply with the Fifth Amendment, development regulations must be shown to substantially advance a legitimate governmental interest. In the case of impact fees, that interest is the protection of public health, safety, and welfare by ensuring development is not detrimental to the quality of essential public services. The means to this end is also important, requiring both procedural and substantive due process. The process followed to receive community input (i.e. stakeholder meetings, work sessions, and public hearings) provides opportunities for comments and refinements to the impact fees.

There is little federal case law specifically dealing with impact fees, although other rulings on other types of exactions (e.g., land dedication requirements) are relevant. In one of the most important exaction cases, the U. S. Supreme Court found that a government agency imposing exactions on development must demonstrate an “essential nexus” between the exaction and the interest being protected (see *Nollan v. California Coastal Commission*, 1987). In a more recent case (*Dolan v. City of Tigard*, OR, 1994), the Court ruled that an exaction also must be “roughly proportional” to the burden created by development.

There are three reasonable relationship requirements for impact fees that are closely related to “rational nexus” or “reasonable relationship” requirements enunciated by a number of state courts. Although the term “dual rational nexus” is often used to characterize the standard by which courts evaluate the validity of impact fees under the U.S. Constitution, TischlerBise prefers a more rigorous formulation that recognizes three elements: “need,” “benefit,” and “proportionality.” The dual rational nexus test explicitly addresses only the first two, although proportionality is reasonably implied, and was specifically mentioned by the U.S. Supreme Court in the *Dolan* case. Individual elements of the nexus standard are discussed further in the following paragraphs.

All new development in a community creates additional demands on some, or all, public facilities provided by local government. If the capacity of facilities is not increased to satisfy that additional demand, the quality or availability of public services for the entire community will deteriorate. Impact fees may be used to cover the cost of development-related facilities, but only to the extent that the need for facilities is a consequence of development that is subject to the fees. The *Nollan* decision reinforced the principle that development exactions may be used only to mitigate conditions created by the developments upon which they are imposed. That principle likely applies to impact fees. In this study, the impact of development on infrastructure needs is analyzed in terms of quantifiable relationships between various types of development and the demand for specific facilities, based on applicable level-of-service standards.

The requirement that exactions be proportional to the impacts of development was clearly stated by the U.S. Supreme Court in the Dolan case and is logically necessary to establish a proper nexus. Proportionality is established through the procedures used to identify development-related facility costs, and in the methods used to calculate impact fees for various types of facilities and categories of development. The demand for facilities is measured in terms of relevant and measurable attributes of development (e.g. persons per household).

A sufficient benefit relationship requires that impact fee revenues be segregated from other funds and expended only on the facilities for which the fees were charged. The calculation of impact fees should also assume that they will be expended in a timely manner and the facilities funded by the fees must serve the development paying the fees. However, nothing in the U.S. Constitution or the state enabling legislation requires that facilities funded with fee revenues be available exclusively to development paying the fees. In other words, benefit may extend to a general area including multiple real estate developments. Procedures for the earmarking and expenditure of fee revenues are discussed near the end of this study. All of these procedural as well as substantive issues are intended to ensure that new development benefits from the impact fees they are required to pay. The authority and procedures to implement impact fees is separate from and complementary to the authority to require improvements.

Proposed Maximum Supportable Impact Fee

The impact fees are based on the actual level of service for General Government, Police, Fire, and Parks & Recreation Facilities. The Parks & Recreation components includes improvements to parks, and recreational facilities. The Parks Impact Fee is only calculated for residential development while the fee for Municipal Facilities, Fire and Police are allocated to nonresidential development as well. A summary of methodologies used in the analysis is provided in Figure 1.

Figure 1. Summary of City of Grand Junction Impact Fees

<i>Fee Category</i>	<i>Service Area</i>	<i>Incremental Expansion</i>	<i>Plan-Based</i>	<i>Cost Recovery</i>	<i>Cost Allocation</i>
Fire	Citywide	Facilities, Apparatus	N/A	N/A	Population & Nonresidential Vehicle Trips
Police	Citywide	Facilities, Vehicles	N/A	N/A	Population & Nonresidential Vehicle Trips
Municipal Facilities	Citywide	Administrative Buildings	N/A	N/A	Population & Jobs
Parks and Recreation	201 Service Bdry	Amenities	N/A	N/A	Population

Maximum Supportable Impact Fees

Figure 2 provides a schedule of the maximum supportable impact fee for Municipal Services, Fire, Police, and Parks & Recreation. The fees represent the highest amount supportable for each type of residential

and nonresidential unit, which represents new growth's fair share of the cost for capital facilities. The City may adopt fees that are less than the amounts shown. However, a reduction in impact fee revenue will necessitate an increase in other revenues, a decrease in planned capital expenditures, and/or a decrease in levels of service.

Figure 2. Maximum Supportable Impact Fee

Residential (Per Unit)

Type	Fire	Police	Parks and Recreation	Municipal Services	Maximum Supportable Fee	Current Fee	Difference
Single-Family	\$710	\$305	\$1,605	\$785	\$3,405	\$225	\$3,180
Multi-Family	\$467	\$200	\$1,055	\$516	\$2,238	\$225	\$2,013

Nonresidential (Per 1,000 square feet)

Type	Fire	Police	Parks and Recreation	Municipal Services	Maximum Supportable Fee	Current Fee	Difference
Retail/Commercial	\$489	\$206	\$0	\$471	\$1,167	\$0	\$1,167
Office/Institutional	\$191	\$81	\$0	\$598	\$870	\$0	\$870
Industrial	\$66	\$28	\$0	\$234	\$328	\$0	\$328
Warehousing	\$34	\$14	\$0	\$69	\$117	\$0	\$117

GENERAL METHODS FOR IMPACT FEES

There are three general methods for calculating impact fees. The choice of a particular method depends primarily on the timing of infrastructure construction (past, concurrent, or future) and service characteristics of the facility type being addressed. Each method has advantages and disadvantages in a particular situation and can be used simultaneously for different cost components.

Reduced to its simplest terms, the process of calculating impact fees involves two main steps: (1) determining the cost of development-related capital improvements and (2) allocating those costs equitably to various types of development. In practice, though, the calculation of impact fees can become quite complicated because of the many variables involved in defining the relationship between development and the need for facilities within the designated service area. The following paragraphs discuss three basic methods for calculating impact fees and how those methods can be applied to City of Grand Junction.

Cost Recovery Method (past improvements)

The City of Grand Junction impact fees use the cost recovery method to address existing excess capacity provided at the Public Safety Building (police headquarters). The rationale for recoupment, or cost recovery, is that new development is paying for its share of the useful life and remaining capacity of facilities already built, or land already purchased, from which new growth will benefit. This methodology is often used for utility systems that must provide adequate capacity before new development can take place.

Incremental Expansion Method (concurrent improvements)

The City of Grand Junction impact fees use the incremental expansion method to document current level-of-service (LOS) standards for the infrastructure types included in the study, using both quantitative and qualitative measures. This approach assumes there are no existing infrastructure deficiencies or surplus capacity. New development is only paying its proportionate share for growth-related infrastructure. Revenue will be used to expand or provide additional facilities, as needed, to accommodate new development. An incremental expansion cost method is best suited for public facilities that will be expanded in regular increments to keep pace with development. The incremental expansion methodology is used for four infrastructure categories included in the study. This is a conservative approach, which limits the City's General Fund exposure. If a plan-based approach were utilized, reliance on long-range growth projections would be likely, which could force the City to spend more General Fund dollars to implement the plan if growth does not occur as projected.

Plan-Based Method (future improvements)

Although not used in City of Grand Junction, the plan-based method allocates costs for a specified set of improvements to a specified amount of development. Improvements are typically identified in a long-range facility plan and development potential is identified by a land use plan. There are two basic options for determining the cost per demand unit: 1) total cost of a public facility can be divided by total service units (average cost), or 2) the growth-share of the public facility cost can be divided by the net increase in service units over the planning timeframe (marginal cost).

Evaluation of Possible Credits


Regardless of the methodology, a consideration of “credits” is integral to the development of a legally defensible impact fee methodology. There are two types of “credits” with specific characteristics, both of which should be addressed in impact fee studies and ordinances. The first is a revenue credit due to possible double payment situations, which could occur when other revenues may contribute to the capital costs of infrastructure covered by the impact fee. This type of credit is integrated into the Fire impact fee calculation, thus reducing the fee amount. The second is a site-specific credit or developer reimbursement for construction of system improvements. This type of credit is addressed in the administration and implementation of the development impact fee program.

Please note, calculations throughout this report are based on an analysis conducted using MS Excel software. Results are discussed in the memo using one- and two-digit places (in most cases). Figures are typically either truncated or rounded. In some instances, the analysis itself uses figures carried to their ultimate decimal places; therefore, the sums and products generated in the analysis may not equal the sum or product if the reader replicates the calculation with the factors shown in the report (due to the rounding of figures shown, not in the analysis).

MUNICIPAL FACILITIES DEVELOPMENT IMPACT FEE

The Municipal Facilities Impact Fee is calculated on a per capita basis for residential development and a per employee basis for nonresidential development. Figure M1 illustrates the methodology used to determine the development fee. It is intended to read like an outline, with lower levels providing a more detailed breakdown of the components. The residential portion is derived from the product of persons per housing unit (by type) multiplied by the net cost per person. The nonresidential portion is derived from the product of employees per 1,000 square feet of nonresidential space multiplied by the net cost per employee (job).

Figure M1. Municipal Facilities Impact Fee Methodology Chart



Municipal Facilities Proportionate Share Factors

Both residential and nonresidential developments increase the demand on Municipal Facilities infrastructure. To calculate the proportional share between residential and nonresidential demand on Municipal Facilities infrastructure, a functional population approach is used. The functional population approach allocates the cost of the facilities to residential and nonresidential development based on the activity of residents and workers in the City through the 24 hours in a day.

Residents that do not work are assigned 20 hours per day to residential development and four hours per day to nonresidential development (annualized averages). Residents that work in Grand Junction are assigned 14 hours to residential development and 10 hours to nonresidential development. Residents that work outside Grand Junction are assigned 14 hours to residential development. Inflow commuters are assigned 10 hours to nonresidential development. Based on 2015 functional population data for Grand Junction, the cost allocation for residential development is 65 percent while nonresidential development accounts for 35 percent of the demand for municipal facilities, see Figure M2.

Figure M2. City of Grand Junction Functional Population

Demand Units in 2015		Demand Hours/Day	Person Hours	Proportionate Share
Residential				
Estimated Residents	60,588			
Residents Not Working	37,811	20	756,220	
Employed Residents	22,777			
Employed in Grand Junction	15,497	14	216,958	
Employed outside Grand Junction	7,280	14	101,920	
<i>Residential Subtotal</i>			1,075,098	65%
Nonresidential				
Non-working Residents	37,811	4	151,244	
Jobs in Grand Junction	42,565			
Residents Employed in Grand Junction	15,497	10	154,970	
Nonresident Workers (Inflow Commuters)	27,068	10	270,680	
<i>Nonresidential Subtotal</i>			576,894	35%
TOTAL			1,651,992	100%

Source: City of Grand Junction 2015 population estimate based on 2015 Census Estimate Data; U.S. Census Bureau OnTheMap 6.5 Web Application, 2015.

Municipal Facilities Level of Service and Capital Costs

The Municipal Facilities Impact Fee is based on six primary facilities serving the public, and their associated replacement costs. The use of existing standards means there are no existing infrastructure deficiencies. New development is only paying its proportionate share for growth-related infrastructure. The floor area has been provided by the City of Grand Junction staff.

The municipal buildings included in the impact fee calculation are listed in Figure M3. In total, there is 122,187 square feet of general government municipal floor area in the City.

The functional population split for the City of Grand Junction found in Figure M2 is used to allocate the square footage and corresponding replacement cost of Municipal Facilities infrastructure in Figure M3. Of the 122,187 square feet of applicable general government facilities, 65 percent is allocated to residential growth (79,518 square feet) and 35 percent (42,669 square feet) is allocated to nonresidential growth. The 2018 population or job totals divide the floor area allocations to find the residential and nonresidential level of service standard. For example, the residential level of service is 1.20 square feet per person (79,518 square feet 66,425 residents = 1.20 square feet per person).

To estimate the replacement cost of the facilities, the average cost of \$277 per square foot is used. As a result, the replacement cost of City Facilities is \$33,845,799. To find the cost per person, the level of service standards is applied to the average replacement cost. For example, the residential cost per person is \$331.60 (1.20 square feet person x \$277 per square foot = \$331.60 per person).

Figure M3. Municipal Facilities Level of Service and Cost Factors

Facility	Square Feet	Cost Per SF*	Replacement Cost
Transportation Engineering Office	3,600	\$277	\$997,200
Municipal Service Center	38,485	\$277	\$10,660,345
Municipal Operations Center	23,345	\$277	\$6,466,565
Field Engineering Building	3,234	\$277	\$895,818
Facilities Building	7,523	\$277	\$2,083,871
City Hall	46,000	\$277	\$12,742,000
TOTAL	122,187		\$33,845,799

Level-of-Service (LOS) Standards

Population in 2018	66,425
Employment in 2018	58,660
Residential Share	65%
Nonresidential Share	35%
LOS: Square Feet per Person	1.20
LOS: Square Feet per Job	0.73

Cost Analysis

Cost per Square Foot*	\$277.00
LOS: Square Feet per Person	1.20
Cost per Person	\$331.60
LOS: Square Feet per Job	0.73
Cost per Job	\$201.49

Source: City of Grand Junction; TischlerBise analysis

*2018 National Building Cost Manual

Projection of Growth-Related Municipal Facilities Facility Needs

To estimate the 10-year growth needs for Municipal Facilities infrastructure, the current level of service (1.20 square feet per person and 0.73 square feet per job) is applied to the residential and nonresidential growth projected for the City of Grand Junction. The City is projected to increase by 12,025 residents and 11,035 jobs over the next ten years (see Appendix A). Figure M4 indicates that the City will need to construct 22,422 square feet of additional space to maintain current levels of service for Municipal Facilities. By applying the average cost of a building (\$277 per square feet), the estimated growth-related cost for Municipal Facilities is approximately \$6.2 million.

Figure M4. 10-Year Municipal Facilities Infrastructure Needs to Accommodate Growth

Type of Infrastructure	Level of Service		Demand Unit	Unit Cost / Sq. Ft.
Municipal Facilities	Residential	1.20	per persons	\$277
	Nonresidential	0.73	per jobs	

Growth-Related Need for Municipal Facilities						
Year		Population	Jobs	Residential Square Feet	Nonresidential Square Feet	Total Square Feet
Base	2018	66,425	58,660	79,518	42,669	122,187
Year 1	2019	67,558	60,018	80,874	43,657	124,531
Year 2	2020	68,691	61,025	82,230	44,389	126,619
Year 3	2021	69,911	62,109	83,691	45,178	128,869
Year 4	2022	71,131	63,192	85,151	45,966	131,117
Year 5	2023	72,351	64,276	86,612	46,754	133,366
Year 6	2024	73,570	65,360	88,072	47,542	135,614
Year 7	2025	74,790	66,444	89,532	48,331	137,863
Year 8	2026	76,010	67,527	90,993	49,119	140,112
Year 9	2027	77,230	68,611	92,453	49,907	142,360
Year 10	2028	78,450	69,695	93,913	50,696	144,609
Ten-Year Increase		12,025	11,035	14,395	8,027	22,422
Projected Expenditure				\$3,987,432	\$2,223,462	\$6,210,894
Growth-Related Expenditure on Municipal Facilities						\$6,210,894

Maximum Supportable Municipal Facilities Impact Fee

Figure M5 shows the maximum supportable Municipal Facilities Impact Fee. Impact fees for Municipal Facilities are based on persons per housing unit for residential development and employees per 1,000 square feet for nonresidential development. For residential development, the total cost per person is multiplied by the persons per housing unit to calculate the proposed fee. For nonresidential development, the total cost per job is multiplied by the jobs per 1,000 square feet to calculate the proposed fee. The fees represent the highest amount supportable for each type of development, which represents new growth's fair share of the cost for capital facilities. The City may adopt fees that are less than the amounts shown. However, a reduction in impact fee revenue will necessitate an increase in other revenues, a decrease in planned capital expenditures, and/or a decrease in levels of service.

Figure M5. Maximum Supportable Municipal Facilities Impact Fee

Fee Component	Cost per Person	Cost per Job
Municipal Facilities Space	\$331.60	\$201.49

Residential (per unit)

Development Type	Persons per Housing Unit	Maximum Supportable Fee
Single Family	2.37	\$785
Multi-Family	1.56	\$516

Nonresidential

Type	ITE Code	Unit	Employees*	Maximum Supportable Fee
Retail/Commercial	820	1,000 SF	2.34	\$471
Office/Institutional	710	1,000 SF	2.97	\$598
Industrial	130	1,000 SF	1.16	\$234
Warehousing	150	1,000 SF	0.34	\$69

*Employment densities were calculated using data from the Institute of Transportation Engineers (ITE), Trip Generation Manual, 10th Edition.

Revenue from Municipal Facilities Impact Fee

Revenue from the Municipal Facilities Impact Fee is estimated in Figure M6. There is projected to be 4,744 new housing units and 4.7 million square feet of nonresidential space in Grand Junction by 2028. To determine the revenue from each development type, the fee is multiplied by the growth. Overall, the revenue from the impact fee covers 93 percent of the capital costs generated by projected growth in the City of Grand Junction.

Figure M6. Estimated Revenue from Municipal Facilities Impact Fee

	Total Cost	Growth Cost
Municipal Facilities	\$6,210,894	\$6,210,894
Total Expenditures	\$6,210,894	\$6,210,894

Projected Development Impact Fee Revenue

		Single-Family	Multi-Family	Commercial / Retail	Office/Inst.	Industrial
		\$785 per unit	\$516 per unit	\$471 per 1,000 Sq Ft	\$598 per 1,000 Sq Ft	\$234 per 1,000 Sq Ft
Year		Housing Units		KSF	KSF	KSF
Base	2018	22,279	6,655	11,094	14,499	6,645
Year 1	2019	22,656	6,767	11,396	14,754	6,668
Year 2	2020	23,032	6,880	11,538	14,964	6,745
Year 3	2021	23,395	6,988	11,690	15,191	6,828
Year 4	2022	23,757	7,096	11,843	15,417	6,911
Year 5	2023	24,120	7,205	11,996	15,644	6,995
Year 6	2024	24,482	7,313	12,148	15,871	7,078
Year 7	2025	24,845	7,421	12,301	16,097	7,161
Year 8	2026	25,207	7,529	12,453	16,324	7,244
Year 9	2027	25,570	7,638	12,606	16,551	7,328
Year 10	2028	25,932	7,746	12,759	16,777	7,411
Ten-Year Increase		3,653	1,091	1,664	2,279	766
Projected Revenue =>		\$2,867,795	\$563,074	\$784,765	\$1,363,580	\$179,046
Projected Revenue =>						\$5,758,259
Total Expenditures =>						\$6,210,894
General Fund's Share =>						\$452,635


FIRE IMPACT FEE

The Fire Impact Fee is calculated on a per capita basis for residential development and a per vehicle trip basis for nonresidential development. Figure F1 illustrates the methodology used to determine the impact fee. It is intended to read like an outline, with lower levels providing a more detailed breakdown of the components. The residential portion is derived from the product of persons per housing unit (by type) multiplied by the net cost per person. The nonresidential portion is derived from the product of vehicle trips generated per 1,000 square feet of nonresidential space multiplied by the net cost per vehicle trip. There are two components to the Fire Facilities Impact Fee:

- Fire Facilities
- Fire Apparatus

The residential fire impact fees are calculated per housing unit. Because the Grand Junction Fire Department also provides emergency medical services and these calls represent the largest percentage of calls to which the Department responds, TischlerBise recommends using nonresidential vehicle trips as the best demand indicator for fire facilities and apparatus, as the trip rates will reflect the presence of people at nonresidential land uses. For example, vehicle trips are highest for commercial/retail developments, such as shopping centers, and lowest for industrial development. Office and institutional trip rates fall between the other two categories. This ranking of trip rates is consistent with the relative demand for fire and emergency medical services and facilities from nonresidential development. Other possible nonresidential demand indicators, such as employment or floor area, will not accurately reflect the demand for service. For example, if employees per thousand square feet were used as the demand indicator, fire impact fees would be too high for office and institutional development because offices typically have more employees per 1,000 square feet than retail uses.

Figure F1. Fire Facilities Impact Fee Methodology Chart



Fire Service Area

The Grand Junction Fire Department serves an area greater than the City of Grand Junction and the 201 Service Area Boundary. Because of this, that portion of the demand cannot be attributed to City residents and businesses or the impact fees will be disproportionate to demand. Therefore, we asked the Grand Junction Fire Department to conduct an analysis of calls for service inside and outside the City in order to determine the amount of activity directed toward residents and business inside the City limits. As shown in Figure F2, over the last two calendar years, the City of Grand Junction Fire Department has responded to slightly over 32,000 incidents. Of that total, 83 percent of the incidents were inside the City limits.

Figure F2. Fire and EMS Incident Data for Two-Year Period

<i>Location</i>	<i>Incidents</i>	<i>%</i>
Inside the City	26,536	83%
Incidents outside the City	5,534	17%
Total	32,070	100%

Source: Grand Junction Fire Department

Fire Proportionate Share Factors

Both residential and nonresidential developments increase the demand on Fire facilities and vehicles. To calculate the proportional share between residential and nonresidential demand on Fire facilities and vehicles, a functional population approach is used. The functional population approach allocates the cost of the facilities to residential and nonresidential development based on the activity of residents and workers in the City through the 24 hours in a day.

Residents that do not work are assigned 20 hours per day to residential development and four hours per day to nonresidential development (annualized averages). Residents that work in Grand Junction are assigned 14 hours to residential development and 10 hours to nonresidential development. Residents that work outside Grand Junction are assigned 14 hours to residential development. Inflow commuters are assigned 10 hours to nonresidential development. Based on 2015 functional population data for Grand Junction, the cost allocation for residential development is 65 percent while nonresidential development accounts for 35 percent of the demand for Fire infrastructure, see Figure F3.

Figure F3. City of Grand Junction Functional Population

Demand Units in 2015		Demand Hours/Day	Person Hours	Proportionate Share
Residential				
Estimated Residents	60,588			
Residents Not Working	37,811	20	756,220	
Employed Residents	22,777			
Employed in Grand Junction	15,497	14	216,958	
Employed outside Grand Junction	7,280	14	101,920	
Residential Subtotal			1,075,098	65%
Nonresidential				
Non-working Residents	37,811	4	151,244	
Jobs in Grand Junction	42,565			
Residents Employed in Grand Junction	15,497	10	154,970	
Nonresident Workers (Inflow Commuters)	27,068	10	270,680	
Nonresidential Subtotal			576,894	35%
TOTAL			1,651,992	100%

Source: City of Grand Junction 2015 population estimate based on 2015 Census Estimate Data; U.S. Census Bureau OnTheMap 6.5 Web Application, 2015.

Fire Station Level of Service

The first component of the Fire Impact Fee is based on an inventory of existing Citywide facilities and replacement costs. The use of existing standards means there are no existing infrastructure deficiencies. New development is only paying its proportionate share for growth-related infrastructure. The floor area has been provided by the City of Grand Junction staff.

The Fire Department occupies 60,577 square feet in 7 facilities. To determine the level of service factors for the impact fee calculation, the amount of facility square footage (60,577) is multiplied by the percentage of activity directed inside the City limits (83%) and then by the functional population split for the City of Grand Junction (found in Figure F3) is used to allocate the square footage and corresponding replacement cost of the fire stations in Figure F4. For example, of the 60,577 square feet of fire space in the City, 50,279 square feet is directed toward City of Grand Junction (60,577 multiplied by 83%). Of this 50,279 impact fee eligible square footage, 32,721 square feet is allocated to residential growth and 17,558 square feet is allocated to nonresidential growth.

The allocated square feet of the Grand Junction fire stations are divided by the 2018 residential and nonresidential demand units (population and nonresidential vehicle trips). The result is the current level

of service for fire stations in the City. Specifically, there is 0.49 square feet of fire stations space per capita and 0.06 square feet per nonresidential vehicle trip.

To estimate the replacement cost of the fire stations, the average cost of \$450 per square foot is used. As a result, the total replacement cost for the 60,577 square feet of facilities is \$27,259,650. To find the cost per person or cost per nonresidential vehicle trip, the level of service standards is applied to the cost per square foot for fire stations. For example, the residential cost per person is \$253.92 (0.49 square feet per person x \$450 per square foot = \$221.67 per person).

Figure F4. Fire Station Level of Service and Cost Factors

Station	Square Footage	Cost per Square Foot*	Replacement Cost
Fire Administration Building	14,576	\$450.00	\$6,559,200
Fire Station No. 1	13,544	\$450.00	\$6,094,800
Fire Station No. 2	8,461	\$450.00	\$3,807,450
Fire Station No. 3	5,477	\$450.00	\$2,464,650
Fire Station No. 4	8,982	\$450.00	\$4,041,900
Fire Station No. 5 Training	1,916	\$450.00	\$862,200
Fire Station No. 5	7,621	\$450.00	\$3,429,450
TOTAL	60,577	\$450.00	\$27,259,650

Level-of-Service (LOS) Standards

Percentage of Activity in City of Grand Junction	83%
Population in 2018	66,425
Nonresidential Vehicle Trip Ends in 2018	271,362
Residential Share	65%
Nonresidential Share	35%
LOS: Sq. Ft. per Person	0.49
LOS: Sq. Ft. per Vehicle Trip End	0.06

Cost Analysis

Cost per Square Foot*	\$450
LOS: Square Feet per Person	0.49
Cost Per Person	\$221.67
LOS: Square Feet per Vehicle Trip End	0.06
Cost per Vehicle Trip End	\$29.12

*Source: City of Grand Junction

Fire Apparatus Level of Service

The second component of the Fire impact fee involves the fire apparatus. The City's current inventory of apparatus is contained in Figure F5, which consists of 38 pieces with a total replacement value of \$12.2 million, or a weighted average cost of \$322,771 per piece of apparatus. Similar to the facilities component, the apparatus inventory is compared to the percentage of activity directed inside the City of Grand Junction, and then allocated based on the proportionate share factors shown in Figure F3. For example, of the 38 pieces of apparatus in the City, approximately 31.5 pieces of the inventory are directed toward City of Grand Junction (38 pieces of apparatus multiplied by 83%). Of the 31.5 pieces of impact fee eligible apparatus, approximately 20.5 pieces are allocated to residential growth and approximately 11 pieces are allocated to nonresidential growth. These allocations are divided by the demand units (population for residential development and nonresidential vehicle trips for nonresidential development) to calculate the current level of service. The current level of service is multiplied by the weighted average cost per fire apparatus to calculate the cost per capita and nonresidential vehicle trip.

For example, there is .00031 pieces of fire apparatus per person in Grand Junction ($20.5 \text{ apparatus} / 66,425 \text{ persons} = .00031 \text{ apparatus per person}$). As discussed above, a new piece of fire apparatus has an average cost of \$322,771, which results in the residential cost equaling \$99.72 per person ($.00031 \text{ vehicles per person} \times \$322,711 \text{ per apparatus} = \99.72 per person).

Figure F5. Fire Apparatus Inventory and Level of Service

Description	Model	# of Units	Unit Cost*	Replacement Cost
Truck	Smeal 100' Quint	1	\$1,253,000	\$1,253,000
Truck	Smeal 75' Quint	1	\$1,253,000	\$1,253,000
Engine	Smeal	4	\$714,000	\$2,856,000
Engine	E-One Pumper	2	\$714,000	\$1,428,000
Battalion	Dodge Ram	1	\$65,000	\$65,000
HazMat	BLM	1	\$300,000	\$300,000
Ambulance	Dodge/Ford/Chevy	8	\$322,000	\$2,576,000
Medic	Ford F150	1	\$75,000	\$75,000
Rescue	SVI Heavy Rescue Truck	1	\$1,000,000	\$1,000,000
Brush	HME	1	\$379,000	\$379,000
Brush	Ford F450	1	\$294,000	\$294,000
Tender	International Tender	1	\$350,000	\$350,000
UTV	Yamaha Rhino	2	\$18,000	\$36,000
ATV	Suzuki	2	\$12,000	\$24,000
Air Trailer	Air Trailer	1	\$40,000	\$40,000
Trailers	Various	4	\$10,000	\$40,000
Administrative	SUV	3	\$55,000	\$165,000
Administrative	Pick Ups	3	\$43,000	\$129,000
TOTAL		38	\$322,711	\$12,263,000

Level-of-Service (LOS) Standards

Percentage of Activity in City of Grand Junction	83%
Population in 2018	66,425
Nonresidential Vehicle Trip Ends in 2018	271,362
Residential Share	65%
Nonresidential Share	35%
LOS: Units per Person	0.00031
LOS: Units per Vehicle Trip End	0.00004

Cost Analysis

Average Cost per Unit	\$322,711
LOS: Units per Person	0.00031
Cost per Person	\$99.72
LOS: Units per Vehicle Trip End	0.00004
Cost per Vehicle Trip End	\$13.10

*Source: City of Grand Junction.

Projection of Growth-Related Fire Needs

To estimate the 10-year growth needs for Fire infrastructure, the current level of service (0.49 square feet per person and 0.06 square feet per nonresidential vehicle trip) is applied to the residential and nonresidential growth projected for the City of Grand Junction. The City is projected to increase by 12,025 residents and 40,643 nonresidential vehicle trips over the next ten years (see Appendix A). As shown in Figure F6, there is a projected need for 8,554 square feet of Fire station space in the City to accommodate the growth at the present level of service. By applying the average cost of a building (\$450 per square feet), the total projected expenditure to accommodate new development is estimated \$3.8 million.

Figure F6. 10-Year Fire Infrastructure Needs to Accommodate Growth

Level-of-Service		Demand Unit	Unit Cost
Residential	0.49		
Nonresidential	0.06	Square Feet	
		per Person	\$450
		per Trip End	

Growth-Related Need for Facilities						
Year		Population	Nonres. Vehicle Trips	Residential Sq. Ft.	Nonres. Sq. Ft.	Total
Base	2018	66,425	271,362	32,721	17,558	50,279
Year 1	2019	67,558	277,672	33,279	17,966	51,245
Year 2	2020	68,691	281,244	33,837	18,197	52,035
Year 3	2021	69,911	285,089	34,438	18,446	52,884
Year 4	2022	71,131	288,934	35,039	18,695	53,734
Year 5	2023	72,351	292,779	35,640	18,944	54,584
Year 6	2024	73,570	296,625	36,241	19,193	55,434
Year 7	2025	74,790	300,470	36,842	19,441	56,283
Year 8	2026	76,010	304,315	37,443	19,690	57,133
Year 9	2027	77,230	308,160	38,044	19,939	57,983
Year 10	2028	78,450	312,005	38,645	20,188	58,832
Ten-Year Increase		12,025	40,643	5,924	2,630	8,554
Growth-Related Expenditure				\$2,665,693	\$1,183,388	\$3,849,081

To estimate the 10-year growth needs for fire apparatus, the current level of service (.00031 apparatus per person and 0.00004 vehicles per nonresidential vehicle trip) is applied to the residential and nonresidential growth projected for the City of Grand Junction. The City is projected to increase by 12,025 residents and 40,643 nonresidential vehicle trips over the next ten years (see Appendix A). As shown in Figure F7, there is a projected need for approximately 5 additional growth-related pieces of apparatus. By applying the average cost of a vehicle (\$322,711), the total projected growth-related expenditure is estimated at approximately \$1.6 million.

Figure F7. 10-Year Fire Apparatus Needs to Accommodate Growth

<i>Level-of-Service</i>				<i>Demand Unit</i>	<i>Unit Cost</i>
Residential	0.00031	Units		per Person	\$322,711
Nonresidential	0.00004			per Trip End	

<i>Growth-Related Need for Apparatus</i>						
<i>Year</i>		<i>Population</i>	<i>Nonres. Vehicle Trips</i>	<i>Residential Vehicles</i>	<i>Nonres. Vehicles</i>	<i>Total</i>
Base	2018	66,425	271,362	21	11	32
Year 1	2019	67,558	277,672	21	11	32
Year 2	2020	68,691	281,244	21	11	33
Year 3	2021	69,911	285,089	22	12	33
Year 4	2022	71,131	288,934	22	12	34
Year 5	2023	72,351	292,779	22	12	34
Year 6	2024	73,570	296,625	23	12	35
Year 7	2025	74,790	300,470	23	12	35
Year 8	2026	76,010	304,315	23	12	36
Year 9	2027	77,230	308,160	24	13	36
Year 10	2028	78,450	312,005	24	13	37
<i>Ten-Year Increase</i>		12,025	40,643	4	2	5
<i>Growth-Related Expenditure</i>				\$1,290,842	\$645,421	\$1,613,553

Fire Debt Service Credit

The City of Grand Junction has existing debt obligations from past fire facility projects: Tax Revenue Bond Series 2010A and Tax Revenue Build America Bond Series 2010B. The proceeds from these bonds funded a number of fire facilities including Fire Station #1, #2 and the Fire Administration building for a total of \$7,100,000 of improvements, representing 20 percent of the 2010 Bonds. Figure F8 lists the remaining principal payment schedules for the bonds.

The total remaining annual principal payment schedule is distributed to the equivalent residential and nonresidential share, City's population and vehicle trip ends, to find the debt cost per attributed user. To account for the time value of money, annual payments are discounted using a net present value formula based on the applicable discount (7.1%) rate. This results in a credit of \$21.68 per person, and \$2.94 per nonresidential trip end.

Figure F8. Fire Debt Principal Payment Credit

Year	Principal Payment	Residential Share (65%)	Population	Debt Cost per Capita	Nonresidential Share (35%)	Nonres. Vehicle Trips	Debt Cost per Trip End
2019	\$165,000	\$107,250	67,558	\$1.59	\$57,750	277,672	\$0.21
2020	\$171,000	\$111,150	68,691	\$1.62	\$59,850	281,244	\$0.21
2021	\$177,000	\$115,050	69,911	\$1.65	\$61,950	285,089	\$0.22
2022	\$185,000	\$120,250	71,131	\$1.69	\$64,750	288,934	\$0.22
2023	\$193,000	\$125,450	72,351	\$1.73	\$67,550	292,779	\$0.23
2024	\$202,000	\$131,300	73,570	\$1.78	\$70,700	296,625	\$0.24
2025	\$211,000	\$137,150	74,790	\$1.83	\$73,850	300,470	\$0.25
2026	\$220,000	\$143,000	76,010	\$1.88	\$77,000	304,315	\$0.25
2027	\$230,000	\$149,500	77,230	\$1.94	\$80,500	308,160	\$0.26
2028	\$241,000	\$156,650	78,450	\$2.00	\$84,350	312,005	\$0.27
2029	\$252,000	\$163,800	79,862	\$2.05	\$88,200	316,292	\$0.28
2030	\$265,000	\$172,250	81,300	\$2.12	\$92,750	320,823	\$0.29
2031	\$278,000	\$180,700	82,763	\$2.18	\$97,300	325,436	\$0.30
2032	\$291,000	\$189,150	84,253	\$2.25	\$101,850	330,132	\$0.31
2033	\$306,000	\$198,900	85,769	\$2.32	\$107,100	334,912	\$0.32
2034	\$321,000	\$208,650	87,313	\$2.39	\$112,350	339,778	\$0.33
2035	\$337,000	\$219,050	88,885	\$2.46	\$117,950	344,732	\$0.34
2036	\$354,000	\$230,100	90,485	\$2.54	\$123,900	349,775	\$0.35
2037	\$372,000	\$241,800	92,113	\$2.63	\$130,200	354,909	\$0.37
2038	\$390,000	\$253,500	93,771	\$2.70	\$136,500	360,135	\$0.38
2039	\$409,000	\$265,850	95,459	\$2.78	\$143,150	365,456	\$0.39
2040	\$430,000	\$279,500	97,178	\$2.88	\$150,500	370,872	\$0.41
Total	\$6,000,000	\$3,900,000			\$2,100,000		

Discount Rate		7.1%		7.1%
Net Present Value		\$21.68		\$2.94

Maximum Supportable Fire Impact Fee

Figure F9 shows the maximum supportable Fire Impact Fee. Impact fees for Fire are based on persons per housing unit for residential development and vehicle trips per 1,000 square feet for nonresidential development. For residential development, the total cost per person is multiplied by the persons per housing unit to calculate the proposed fee. For nonresidential development, the total cost per vehicle trip is multiplied by the trips per 1,000 square feet, hotel room or other applicable factor to calculate the proposed fee.

The fees represent the highest amount supportable for each type of development, which represents new growth's fair share of the cost for capital facilities. The City may adopt fees that are less than the amounts shown. However, a reduction in impact fee revenue will necessitate an increase in other revenues, a decrease in planned capital expenditures, and/or a decrease in levels of service.

Figure F9. Maximum Supportable Fire Impact Fee

<i>Fee Component</i>	<i>Cost per Person</i>	<i>Cost per Vehicle Trip</i>
Facilities	\$221.67	\$29.12
Vehicles	\$99.72	\$13.10
Existing Principal Credit	(\$21.68)	(\$2.94)
NET COST PER DEMAND UNIT	\$299.71	\$39.28

Residential

<i>Housing Type</i>	<i>Persons per Housing Unit</i>	<i>Maximum Supportable Fee</i>
Single-Family	2.37	\$710
Multi-Family	1.56	\$467

Nonresidential

<i>Type</i>	<i>ITE Code</i>	<i>Unit</i>	<i>Average Daily Vehicle Trips*</i>	<i>Trip Adjustment Factor*</i>	<i>Maximum Supportable Fee</i>
Retail/Commercial	820	1,000 SF	37.75	33%	\$489
Office/Institutional	710	1,000 SF	9.74	50%	\$191
Industrial	130	1,000 SF	3.37	50%	\$66
Warehousing	150	1,000 SF	1.74	50%	\$34

*Institute of Transportation Engineers (ITE), Trip Generation Manual, 10th Edition, 2017

Revenue from Fire Impact Fee

Revenue from the Fire Impact Fee is estimated in Figure F10. There is projected to be 4,744 new housing units and 4.7 million square feet of new nonresidential development in Grand Junction by 2028. To find the revenue from each development type, the fee is multiplied by the growth. Overall, the revenue from the impact fee covers approximately 80 percent of the capital costs generated by projected growth in the City of Grand Junction.

Figure F10. Estimated Revenue from Fire Impact Fee

	Total Cost	Growth Cost
Facilities	\$3,849,081	\$3,849,081
Vehicles	\$1,613,553	\$1,613,553
Total Expenditures	\$5,462,634	\$5,462,634

Projected Fire and Rescue Impact Fee Revenue

		Single-Family	Multi-Family	Commercial/ Retail	Office/Instit.	Industrial
		\$710 per Unit	\$467 per Unit	\$489 per KSF	\$191 per KSF	\$66 per KSF
Year		Housing Units	Housing Units	KSF	KSF	KSF
Base	2018	22,279	6,655	11,094	14,499	6,645
1	2019	22,656	6,767	11,396	14,754	6,668
2	2020	23,032	6,880	11,538	14,964	6,745
3	2021	23,395	6,988	11,690	15,191	6,828
4	2022	23,757	7,096	11,843	15,417	6,911
5	2023	24,120	7,205	11,996	15,644	6,995
6	2024	24,482	7,313	12,148	15,871	7,078
7	2025	24,845	7,421	12,301	16,097	7,161
8	2026	25,207	7,529	12,453	16,324	7,244
9	2027	25,570	7,638	12,606	16,551	7,328
10	2028	25,932	7,746	12,759	16,777	7,411
10-year Increase		3,653	1,091	1,664	2,279	766
10-year Projected Revenue		\$2,593,395	\$509,224	\$814,447	\$435,874	\$50,701
Projected Revenue =>						\$4,403,640
Total Expenditures =>						\$5,462,634
General Fund's Share =>						\$1,058,994

POLICE IMPACT FEE


The Police Impact Fee is calculated on a per capita basis for residential development and a per vehicle trip basis for nonresidential development. Figure P1 illustrates the methodology used to determine the impact fee. It is intended to read like an outline, with lower levels providing a more detailed breakdown of the components. The residential portion is derived from the product of persons per housing unit (by type) multiplied by the net cost per person. The nonresidential portion is derived from the product of vehicle trips generated per 1,000 square feet of nonresidential space multiplied by the net cost per vehicle trip. There are two components to the Police Impact Fee:

- Police Station – Incremental Expansion

One of the key considerations when developing impact fees is the ability to establish the existing level of service. Further detail about current and future level of service is provided in following sections of the report. For the police station component, the cost recovery methodology is used to calculate the portion of the facility attributed to future growth so that new development pays only its fair share of the cost of existing excess capacity which was provided by the original overbuilding of the facilities. In consideration of any outstanding debt associated with facility construction, TischlerBise incorporates a residential level-of-service debt recovery calculation based on the final year of debt payment, 2040, and the correlating residential population and vehicle trips. Additional detail regarding the debt recovery is provided in following sections of the report.

The residential police impact fees are calculated per housing unit. TischlerBise recommends using nonresidential vehicle trips as the best demand indicator for police facilities. Trip generation rates are used for nonresidential development because vehicle trips are highest for commercial/retail developments, such as shopping centers, and lowest for industrial development. Office and institutional trip rates fall between the other two categories. This ranking of trip rates is consistent with the relative demand for police services and facilities from nonresidential development. Other possible nonresidential demand indicators, such as employment or floor area, will not accurately reflect the demand for service. For example, if employees per thousand square feet were used as the demand indicator, police impact fees would be too high for office and institutional development because offices typically have more employees per 1,000 square feet than retail uses.

Figure P1. Police Impact Fee Methodology Chart



Police Proportionate Share Factors

Both residential and nonresidential developments increase the demand on police facilities. To calculate the proportional share between residential and nonresidential demand on police facilities, a functional population approach is used. The functional population approach allocates the cost of the facilities to residential and nonresidential development based on the activity of residents and workers in the City through the 24 hours in a day.

Residents that do not work are assigned 20 hours per day to residential development and four hours per day to nonresidential development (annualized averages). Residents that work in Grand Junction are assigned 14 hours to residential development and 10 hours to nonresidential development. Residents that work outside Grand Junction are assigned 14 hours to residential development. Inflow commuters are assigned 10 hours to nonresidential development. Based on 2015 functional population data for Grand

Junction, the cost allocation for residential development is 65 percent while nonresidential development accounts for 35 percent of the demand for police facilities, see Figure P2.

Figure P2. City of Grand Junction Functional Population

Demand Units in 2015		Demand Hours/Day	Person Hours	Proportionate Share
Residential				
Estimated Residents	60,588			
Residents Not Working	37,811	20	756,220	
Employed Residents	22,777			
Employed in Grand Junction	15,497	14	216,958	
Employed outside Grand Junction	7,280	14	101,920	
<i>Residential Subtotal</i>			1,075,098	65%
Nonresidential				
Non-working Residents	37,811	4	151,244	
Jobs in Grand Junction	42,565			
Residents Employed in Grand Junction	15,497	10	154,970	
Nonresident Workers (Inflow Commuters)	27,068	10	270,680	
<i>Nonresidential Subtotal</i>			576,894	35%
TOTAL			1,651,992	100%

Source: City of Grand Junction 2015 population estimate based on 2015 Census Estimate Data; U.S. Census Bureau OnTheMap 6.5 Web Application, 2015.

Police Station Level of Service

The first component of the Police Impact Fee is based on an inventory of existing citywide facilities and replacement costs. The use of existing standards means there are no existing infrastructure deficiencies. New development is only paying its proportionate share for growth-related infrastructure. The floor area has been provided by the City of Grand Junction staff.

The City of Grand Junction Police Department is housed in the Public Safety Building. The Police Department occupies 63,863 square feet. To determine the residential level of service, the current Police space square footage (63,863) is multiplied by the residential proportionate share factor (65%) and divided by the current population (66,425) for a level of service standard of 0.63 square feet per person. The nonresidential level of service standard of 0.08 square feet per nonresidential vehicle trip was determined by multiplying the current facility square footage (63,863) by the nonresidential proportionate share factor (35%) and divided by the current average daily nonresidential vehicle trips (271,362).

As shown in Figure P3, the estimated replacement cost is \$344.20 per square foot. I do know there was some concern about the fleet issue and our dire needs there. This cost is based on the estimated cost for construction of a future Police Annex prepared by the Blythe Group. When the residential (0.63 per person) and nonresidential (0.08 per vehicle trip) per square foot level of service standards are multiplied by the cost per square foot (\$344.20), the resulting cost per demand units are \$215.36 per person and \$28.29 per vehicle trip.

Figure P3. Police Station Level of Service and Cost Factors

<i>Facility Components</i>	<i>Square Footage</i>	<i>Cost per Square Foot*</i>	<i>Replacement Cost</i>
Police Station Building	63,863	\$344.20	\$14,317,814
TOTAL	63,863	\$344.20	\$14,317,814

**Source: City of Grand Junction*

Level-of-Service (LOS) Standards

Population in 2018	66,425
Nonresidential Vehicle Trip Ends in 2018	271,362
Residential Share	65%
Nonresidential Share	35%
LOS: Square Feet per Person	0.63
LOS: Square Feet per Vehicle Trip End	0.08

Cost Analysis

Cost per Square Foot*	\$344.20
LOS: Square Feet per Person	0.63
Cost per Person	\$215.36
LOS: Square Feet per Vehicle Trip	0.08
Cost per Vehicle Trip	\$28.29

Projection of Growth-Related Police Facility Needs

To estimate the 10-year growth needs for Police space, the current level of service (.63 square feet per person and 0.08 square feet per nonresidential vehicle trip) is applied to the residential and nonresidential growth projected for the City of Grand Junction. The City is projected to increase by 12,025 residents and 40,643 nonresidential vehicle trips over the next ten years (see Appendix A). Listed in Figure P4, there is projected need for 10,864 square feet of growth-related Police space to accommodate new development in the City at the present level of service. By applying the average cost per square foot (\$344.20), the total projected growth-related building space expenditure is approximately \$3.7 million.

Figure P4. 10-Year Police Space Needs to Accommodate Growth

Level-of-Service				Demand Unit	Unit Cost
Residential	0.63	Square Feet		per Person	\$344
Nonresidential	0.08			per Trip End	

Growth-Related Need for Facilities						
Year		Population	Nonres. Vehicle Trips	Residential Sq. Ft.	Nonres. Sq. Ft.	Total
Base	2018	66,425	271,362	41,561	22,302	63,863
Year 1	2019	67,558	277,672	42,270	22,820	65,091
Year 2	2020	68,691	281,244	42,979	23,114	66,093
Year 3	2021	69,911	285,089	43,743	23,430	67,172
Year 4	2022	71,131	288,934	44,506	23,746	68,252
Year 5	2023	72,351	292,779	45,269	24,062	69,331
Year 6	2024	73,570	296,625	46,032	24,378	70,410
Year 7	2025	74,790	300,470	46,796	24,694	71,490
Year 8	2026	76,010	304,315	47,559	25,010	72,569
Year 9	2027	77,230	308,160	48,322	25,326	73,648
Year 10	2028	78,450	312,005	49,086	25,642	74,727
Ten-Year Increase		12,025	40,643	7,524	3,340	10,864
Growth-Related Expenditure				\$2,589,761	\$1,149,628	\$3,739,389

Police Debt Service Credit

The City of Grand Junction has existing debt obligations for the construction of the present Public Safety Building. The proceeds from these bonds funded a number of fire facilities including Fire Station #1, #2 and the Fire Administration building for a total of \$7,100,000 of improvements, representing 20 percent of the 2010 Bonds. Figure P5 lists the remaining principal payment schedule for the bonds, which is totals \$24 million.

The total remaining annual principal payment schedule is distributed to the equivalent residential and nonresidential share, City's population and vehicle trip ends, to find the debt cost per attributed user. To

account for the time value of money, annual payments are discounted using a net present value formula based on the applicable discount (7.1%) rate. This results in a credit of \$86.71 per person, and \$11.74 per nonresidential trip end.

Figure P5. Police Debt Principal Payment Credit

Year	Principal Payment	Residential Share (65%)	Population	Debt Cost per Capita	Nonresidential Share (35%)	Nonres. Vehicle Trips	Debt Cost per Trip End
2019	\$660,000	\$429,000	67,558	\$6.35	\$231,000	277,672	\$0.83
2020	\$684,000	\$444,600	68,691	\$6.47	\$239,400	281,244	\$0.85
2021	\$708,000	\$460,200	69,911	\$6.58	\$247,800	285,089	\$0.87
2022	\$740,000	\$481,000	71,131	\$6.76	\$259,000	288,934	\$0.90
2023	\$772,000	\$501,800	72,351	\$6.94	\$270,200	292,779	\$0.92
2024	\$808,000	\$525,200	73,570	\$7.14	\$282,800	296,625	\$0.95
2025	\$844,000	\$548,600	74,790	\$7.34	\$295,400	300,470	\$0.98
2026	\$880,000	\$572,000	76,010	\$7.53	\$308,000	304,315	\$1.01
2027	\$920,000	\$598,000	77,230	\$7.74	\$322,000	308,160	\$1.04
2028	\$964,000	\$626,600	78,450	\$7.99	\$337,400	312,005	\$1.08
2029	\$1,008,000	\$655,200	79,862	\$8.20	\$352,800	316,292	\$1.12
2030	\$1,060,000	\$689,000	81,300	\$8.47	\$371,000	320,823	\$1.16
2031	\$1,112,000	\$722,800	82,763	\$8.73	\$389,200	325,436	\$1.20
2032	\$1,164,000	\$756,600	84,253	\$8.98	\$407,400	330,132	\$1.23
2033	\$1,224,000	\$795,600	85,769	\$9.28	\$428,400	334,912	\$1.28
2034	\$1,284,000	\$834,600	87,313	\$9.56	\$449,400	339,778	\$1.32
2035	\$1,348,000	\$876,200	88,885	\$9.86	\$471,800	344,732	\$1.37
2036	\$1,416,000	\$920,400	90,485	\$10.17	\$495,600	349,775	\$1.42
2037	\$1,488,000	\$967,200	92,113	\$10.50	\$520,800	354,909	\$1.47
2038	\$1,560,000	\$1,014,000	93,771	\$10.81	\$546,000	360,135	\$1.52
2039	\$1,636,000	\$1,063,400	95,459	\$11.14	\$572,600	365,456	\$1.57
2040	\$1,720,000	\$1,118,000	97,178	\$11.50	\$602,000	370,872	\$1.62
Total	\$24,000,000	\$15,600,000			\$8,400,000		
Discount Rate				7.1%	7.1%		
Net Present Value				\$86.71	\$11.74		

Maximum Supportable Police Impact Fee

Figure P6 shows the maximum supportable Police Impact Fee. Impact fees for Police are based on persons per housing unit for residential development and vehicle trips per 1,000 square feet for nonresidential development. For residential development, the total cost per person is multiplied by the housing unit size to calculate the proposed fee. For nonresidential development, the total cost per vehicle trip is multiplied by the trips per 1,000 square feet to calculate the proposed fee.

The fees represent the highest amount supportable for each type of development, which represents new growth's fair share of the cost for capital facilities. The City may adopt fees that are less than the amounts shown. However, a reduction in impact fee revenue will necessitate an increase in other revenues, a decrease in planned capital expenditures, and/or a decrease in levels of service.

Figure P6. Maximum Supportable Police Impact Fee

<i>Fee Component</i>	<i>Cost per Person</i>	<i>Cost per Vehicle Trip</i>
Police Space	\$215.36	\$28.29
Existing Principal Credit	(\$86.71)	(\$11.74)
NET COST PER DEMAND UNIT	\$128.65	\$16.55

Residential

<i>Housing Type</i>	<i>Persons per Housing Unit</i>	<i>Maximum Supportable Fee</i>
Single-Family	2.37	\$305
Multi-Family	1.56	\$200

Nonresidential

<i>Type</i>	<i>ITE Code</i>	<i>Unit</i>	<i>Average Daily Vehicle Trips*</i>	<i>Trip Adjustment Factor*</i>	<i>Maximum Supportable Fee</i>
Retail/Commercial	820	1,000 SF	37.75	33%	\$206
Office/Institutional	710	1,000 SF	9.74	50%	\$81
Industrial	130	1,000 SF	3.37	50%	\$28
Warehousing	150	1,000 SF	1.74	50%	\$14

*Institute of Transportation Engineers (ITE), Trip Generation Manual, 10th Edition, 2017

Revenue from Police Impact Fee

Revenue from the Police Impact Fee is estimated in Figure P7. There is projected to be 4,744 new housing units and 4.7 million square feet of nonresidential development in Grand Junction by 2028. To find the revenue from each development type, the fee is multiplied by the growth for each land use. Overall, the projected revenue from the Police impact fee totals approximately \$1.6 million. Impact fee revenue is less than the projected expenditures due to the required debt credit.

Figure P7. Estimated Revenue from Police Impact Fee

	Growth Cost
Police Facilities	\$3,739,389
Total Expenditures	\$3,739,389

Projected Development Impact Fee Revenue

		Single-Family	Multi-Family	Commercial / Retail	Office/Instit.	Industrial
		\$305 per unit	\$200 per unit	\$81 per 1000 Sq Ft	\$81 per 1000 Sq Ft	\$28 per 1000 Sq Ft
Year		Housing Units	Housing Units	KSF	KSF	KSF
Base	2018	22,279	6,655	11,094	14,499	6,645
Year 1	2019	22,656	6,767	11,396	14,754	6,668
Year 2	2020	23,032	6,880	11,538	14,964	6,745
Year 3	2021	23,395	6,988	11,690	15,191	6,828
Year 4	2022	23,757	7,096	11,843	15,417	6,911
Year 5	2023	24,120	7,205	11,996	15,644	6,995
Year 6	2024	24,482	7,313	12,148	15,871	7,078
Year 7	2025	24,845	7,421	12,301	16,097	7,161
Year 8	2026	25,207	7,529	12,453	16,324	7,244
Year 9	2027	25,570	7,638	12,606	16,551	7,328
Year 10	2028	25,932	7,746	12,759	16,777	7,411
Ten-Year Increase		3,653	1,091	1,664	2,279	766
Projected Revenue =>		\$1,113,195	\$218,580	\$134,161	\$183,665	\$21,364
Projected Revenue =>					\$1,670,965	
Total Expenditures =>					\$3,739,389	
General Fund's Share =>					\$2,068,424	


PARKS & RECREATION IMPACT FEE

The Parks & Recreation Impact Fee is based on the incremental expansion methodology. The impact fee methodology assumes the City will construct additional recreation improvements through the development of existing parks and banked park land to serve future growth to maintain current levels of service incrementally over time. The study includes only the replacement costs of improvements to park and recreational facilities, land acquisition is not included. However, the City will still maintain its current park land dedication requirement. Due to the recognition that Grand Junction Parks provide services to the larger population residing throughout the broader 201 Sewer Service Boundary, recreation capital improvements are allocated 100 percent to residential development within this area to establish the current level of service. No revenue credit is necessary to avoid double payments as there is no current debt obligations for the park improvements included in the impact fee calculations. There are two components to the Parks and Recreation Impact Fee:

- Level 1 Parkland Improvements
- Level 2 Parkland Improvements

Figure PR1 diagrams the general methodology used to calculate the Parks & Recreation impact fee. It is intended to read like an outline, with lower levels providing a more detailed breakdown of the impact fee components. The Parks and Recreation impact fee is derived from the product of persons per housing unit (by type of unit) multiplied by the net capital cost per person. The boxes in the next level down indicate detail on the components included in the fee.

Figure PR1. Parks & Recreation Impact Fee Methodology



Parks & Recreation Level of Service and Cost Factors

The Parks & Recreation Impact Fee is based on an inventory of existing developed City parks and current values of recreation improvements. The impact fee does not include a land purchase component as it is assumed the Parks and Recreation Department's focus over the next 5-10 years will be the buildout of existing park land. However, as mentioned previously, the City will still maintain its current park land dedication requirement. Improvement costs have been provided by the City of Grand Junction staff, referencing the *2011 City of Grand Junction Park Inventory and Future Needs Assessment* report, (updated in 2017). The use of existing standards means there are no existing infrastructure deficiencies. New development is only paying its proportionate share for growth-related infrastructure.

Discussions with City staff indicate the City's park system essentially serves residents who reside within the 201 Sewer Service Boundary. For purposes of determining level of service standards, this population base will be referred to as the "park population," which is larger than the existing population base of the City.

Current Inventory of Parkland and Improvements

Figure PR2 and PR3 lists the current inventory of parkland owned by the City of Grand Junction. For the purpose of this study, City staff allocated parks into one of two categories, Level-1 and Level-2 facilities. Figures PR2 and PR3 also indicate the total amount of Level-1 and Level-2 park acreage compared to the amount that is actually developed.

Level-1 parks are those improved with Phase-1 infrastructure, consisting of adequate soil preparation, irrigation systems, sewer and electrical services along with turf and tree plantings. Based on the development cost identified in the *Parks Inventory and Future Needs Assessment Report*, Phase-1 park improvements average \$112,500 per acre.

Level-2 parks are categorized as parks with Phase-II improvements, typically including a wide range of amenities including; restroom facilities, playgrounds, shelters and walking paths. Special features in these parks can include, but are not limited to; swimming pools, tennis courts, sports fields, disk golf, skate parks and many other like features.

The *Parks Inventory and Future Needs Assessment Report* estimates Phase-2 park improvements to average \$80,000 per acre (plus the cost of Level-1 improvements), for a total of \$192,500 per acre. In total, there are seven Level-1 parks with an improved value of \$812,250, and 29 Level-2 parks with a total improved value of \$56.7 million.

Parkland Improvements Level of Service

To calculate the current level of service, the existing developed parkland acreage, (10.32 for Level-1 parks and 357.54 for Level-2 parks) is divided by the current park population (103,224). This results in level of service standards of 0.0001 acres of developed Level-1 parkland per person and 0.0035 acres of developed Level-2 parkland per person.

The parkland improvements cost per acre (\$112,500 Level-1 and \$192,500 Level-2) is then utilized to generate a cost per person factor which is calculated by applying the level of service factor to the total development cost per acre. As shown in Figure PR2, Level-1 parkland improvements of 0.0001 acres per person x \$112,500 per acres = \$11.25 per person. Similarly, Figure PR3 displays the breakdown for Level-2 parkland in the City, which results in park development cost of \$666.76 per person.

Figure PR2. Level 1 Parkland Level of Service

Park	Park Type	Total Acreage	Developed Acreage	Improved Value
Autumn Ridge Park	Neighborhood/Mini Park	1.5	1.5	\$168,750
Hidden Valley Park	Neighborhood/Mini Park	7	1	\$112,500
Hillcrest Park	Neighborhood/Mini Park	0.23	0.23	\$25,875
Lilac Park	Undeveloped/Open Space	1.7	1.7	\$191,250
Ridges Tot Lot Park	Neighborhood/Mini Park	1.8	1.8	\$201,375
Shadow Lake Park	Neighborhood/Mini Park	5.7	1	\$112,500
Spring Valley Park	Neighborhood/Mini Park	3.1	3.1	\$348,750
TOTAL		21.02	10.32	\$1,161,000

Level-of-Service (LOS) Standards

Developed Acreage	10.32
Park Population in 2018 (includes 201 Boundary)	103,224
LOS: Improved Acres per Person	0.0001

Cost Analysis

Improvement Value per Acre*	\$112,500
LOS: Improved Acres per Person	0.0001
Cost per Person	\$11.25

*Source: City of Grand Junction

Figure PR3. Level 2 Parkland Level of Service

Park	Park Type	Total Acreage	Developed Acreage	Improved Value
Canyon View Park	Community/Regional Park	114.2	114.2	\$21,983,500
Columbine Park	Community/Regional Park	12	12	\$2,310,000
Cottonwood Meadows Park	Neighborhood/Mini Park	0.8	0.8	\$154,000
Darla Jean Park	Neighborhood/Mini Park	2.2	2.2	\$423,500
Duck Pond Orchard Mesa Park	Neighborhood/Mini Park	4.4	4.4	\$847,000
Duck Pond Park - Ridges	Neighborhood/Mini Park	2.82	2.82	\$542,850
Eagle Rim Park	Neighborhood/Mini Park	12	12	\$2,310,000
Emerson Park	Neighborhood/Mini Park	2.52	2.52	\$485,100
Hawthorne Park	Neighborhood/Mini Park	3.5	3.5	\$673,750
Honeycomb Park	Neighborhood/Mini Park	3.5	3.5	\$673,750
Las Colonias Park	Community/Regional Park	140	115	\$10,060,000
Lincoln Park	Community/Regional Park	42	42	\$8,085,000
Pineridge Park	Neighborhood/Mini Park	15.7	3	\$577,500
Paradise Hills Park	Neighborhood/Mini Park	5.57	2.78	\$535,150
Rocket Park	Neighborhood/Mini Park	2.7	2.7	\$519,750
Riverside Park	Neighborhood/Mini Park	1.5	1.5	\$288,750
Sherwood Park	Neighborhood/Mini Park	13.87	13.87	\$2,669,975
Spring Valley II Park	Neighborhood/Mini Park	2.52	2.52	\$485,100
Washington Park	Neighborhood/Mini Park	3	3	\$577,500
Whitman Park	Neighborhood/Mini Park	2.5	2.5	\$481,250
Williams Park	Neighborhood/Mini Park	0.37	0.37	\$71,225
Westlake Park	Neighborhood/Mini Park	10	5.5	\$1,058,750
Wingate Park	Neighborhood/Mini Park	4.86	4.86	\$935,550
Burkey Park North	Undeveloped/Open Space	18.37	0	\$0
Burkey Park South	Undeveloped/Open Space	9.61	0	\$0
Flint Ridge	Undeveloped/Open Space	3.3	0	\$0
Horizon Park	Undeveloped/Open Space	12.65	0	\$0
Matchett Park	Undeveloped/Open Space	205.52	0	\$0
Saccomanno Park	Undeveloped/Open Space	30.73	0	\$0
TOTAL		682.71	357.54	\$56,748,950

Level-of-Service (LOS) Standards

Developed Acreage	357.54
Park Population in 2018 (includes 201 Boundary)	103,224
LOS: Improved Acres per Person	0.0035

Cost Analysis

Improvement Value per Acre*	\$192,500
LOS: Improved Acres per Person	0.0035
Cost per Person	\$666.76

*Source: City of Grand Junction

Projection of Growth-Related Park Improvement Needs

To estimate the 10-year growth needs for Level 1 park improvements, the current level of service (0.0001 acres person) is applied to the projected park population growth. The 201 Sewer Service area is projected to increase by 18,688 residents over the next ten years (see Appendix A). As shown in Figure PR4, it is projected that the City will need to develop 1.3 acres of Level 1 park land to accommodate the needs generated by new development. By applying the average development cost for Level 1 parks (\$112,500 per acre), the estimated growth-related expenditure is approximately \$210,000.

Figure PR4. 10-Year Level 1 Park Improvement Needs to Accommodate Growth

Type	Level of Service	Demand Unit	Unit Cost / Acre
Level 1 Park Improvements	0.0001 Acres	per person	\$112,500

Growth-Related Need for Level 1 Park Improvements			
Year		Population	Improved Acres
Base	2018	103,224	10.32
Year 1	2019	104,985	10.50
Year 2	2020	106,746	10.67
Year 3	2021	108,642	10.86
Year 4	2022	110,538	11.05
Year 5	2023	112,434	11.24
Year 6	2024	114,329	11.43
Year 7	2025	116,225	11.62
Year 8	2026	118,121	11.81
Year 9	2027	120,016	12.00
Year 10	2028	121,912	12.19
Ten-Year Increase		18,688	1.87
Projected Expenditure			\$210,375

Growth-Related Expenditure on Level 1 Park Improvements	\$210,375
--	------------------

To estimate the 10-year growth needs for Level 2 park improvements, the current level of service (0.0035 acres person respectively for Level-2 improvements) is applied to the projected park population growth. The 201 Sewer Service area is projected to increase by 18,688 residents over the next ten years (see Appendix A). As shown in Figure PR5, it is projected that the City will need to develop 65 acres of Level 2 park land to accommodate the needs generated by new development. By applying the average development cost for Level 2 parks (\$192,500 per acre), the estimated growth-related expenditure is approximately \$12.5 million.

Figure PR5. 10-Year Level 2 Park Improvement Needs to Accommodate Growth

Type	Level of Service	Demand Unit	Unit Cost / Acre
Level 2 Park Improvements	0.0035 Acres	per 1,000 persons	\$192,500

Growth-Related Need for Level 2 Park Improvements			
Year		Population	Improved Acres
Base	2018	103,224	357.54
Year 1	2019	104,985	363.64
Year 2	2020	106,746	369.74
Year 3	2021	108,642	376.31
Year 4	2022	110,538	382.87
Year 5	2023	112,434	389.44
Year 6	2024	114,329	396.00
Year 7	2025	116,225	402.57
Year 8	2026	118,121	409.14
Year 9	2027	120,016	415.70
Year 10	2028	121,912	422.27
Ten-Year Increase		18,688	65
Projected Expenditure			\$12,512,500

Growth-Related Expenditure Level 2 Park Improvements	\$12,512,500
--	--------------

Parks & Recreation Impact Fee

Figure PR6 shows the cost factors for each component of the City of Grand Junction's Parks and Recreation Impact Fee. Impact fees for parks and recreation are based on persons per housing unit and are only assessed against residential development. The fees for park improvements are calculated per person, so by multiplying the total cost per person by the housing unit size calculates the maximum supportable fee.

The fees represent the highest amount supportable for each type of housing unit, which represents new growth's fair share of the cost for capital facilities. The City may adopt fees that are less than the amounts shown. However, a reduction in impact fee revenue will necessitate an increase in other revenues, a decrease in planned capital expenditures, and/or a decrease in levels of service.

Figure PR6. Maximum Supportable Park & Recreation Impact Fee

Fee Component	Cost per Person
Level 1 Parkland Improvements	\$11.25
Level 2 Parkland Improvements	\$666.76
COST PER DEMAND UNIT	\$678.01

Type	Persons per Housing Unit	Maximum Supportable Fee	Current Fee	Increase / (Decrease)
Single-Family	2.37	\$1,605	\$225	\$1,380
Multi-Family	1.56	\$1,055	\$225	\$830

Revenue from Parks & Recreation Impact Fee

Revenue from the City's Parks & Recreation Impact Fee is estimated in Figure PR7. Demand for park improvements is driven by both City residents and current/future residents within the 201 Sewer Service Boundary. Therefore, it is difficult to estimate impact fee revenue for parks and recreation because it is not known when (and if) the projected housing units in the 201 Sewer Service Boundary will be annexed into the City of Grand Junction prior to their construction (which is the time the impact fee is paid). Therefore, the impact fee revenue projection is based on projected units in the City of Grand Junction over the next ten years. By multiplying the projected residential growth in the City by the impact fee amounts, we estimate projected impact fee revenue of approximately \$7.0 million. Projected expenditures total \$12.7 million.

Figure PR7. Estimated Revenue from Parks & Recreation Impact Fee

	Growth Cost
Level 1 Parkland Improvements	\$210,375
Level 2 Parkland Improvements	\$12,512,500
Total Expenditures	\$12,722,875

Projected Development Impact Fee Revenue

		Single-Family	Multi-Family
		\$1,605 per unit	\$1,055 per unit
Year		Housing Units	Housing Units
Base	2018	22,279	6,655
Year 1	2019	22,656	6,767
Year 2	2020	23,032	6,880
Year 3	2021	23,395	6,988
Year 4	2022	23,757	7,096
Year 5	2023	24,120	7,205
Year 6	2024	24,482	7,313
Year 7	2025	24,845	7,421
Year 8	2026	25,207	7,529
Year 9	2027	25,570	7,638
Year 10	2028	25,932	7,746
Ten-Year Increase		3,653	1,091
Projected Revenue =>		\$5,863,453	\$1,151,246
Projected Revenue =>			\$7,014,699
Total Expenditures =>			\$12,722,875
General Fund's Share =>			\$5,708,176

IMPLEMENTATION AND ADMINISTRATION

Impact fees should be periodically evaluated and updated to reflect recent data. City of Grand Junction will continue to adjust for inflation. If cost estimates or demand indicators change significantly, the City should redo the fee calculations.

Colorado's enabling legislation allows local governments to "waive an impact fee or other similar development charge on the development of low or moderate income housing, or affordable employee housing, as defined by the local government."

Credits and Reimbursements

A general requirement that is common to development impact fee methodologies is the evaluation of credits. A revenue credit may be necessary to avoid potential double payment situations arising from one-time development impact fees plus on-going payment of other revenues that may also fund growth-related capital improvements. The determination of revenue credits is dependent upon the development impact fee methodology used in the cost analysis and local government policies.

Policies and procedures related to site-specific credits should be addressed in the resolution or ordinance that establishes the development impact fees. Project-level improvements, required as part of the development approval process, are not eligible for credits against development impact fees. If a developer constructs a system improvement included in the fee calculations, it will be necessary to either reimburse the developer or provide a credit against the fees due from that particular development. The latter option is more difficult to administer because it creates unique fees for specific geographic areas.

Service Area

A development impact fee service area is a region in which a defined set of improvements provide benefit to an identifiable amount of new development. Within a service area, all new development of a type (single-family, commercial, etc.) is assessed at the same development impact fee rate. Land use assumptions and development impact fees are each defined in terms of this geography, so that capital facility demand, projects needed to meet that demand, and capital facility cost are all quantified in the same terms. Development impact fee revenue collected within a service area is required to be spent within that service area.

Implementation of a large number of small service areas is problematic. Administration is complicated and, because funds collected within the service area must be spent within that area multiple service areas may make it impossible to accumulate sufficient revenue to fund any projects within the time allowed.

As part of our analysis of the City and the type of facilities and improvements included in the development impact fee calculation, TischlerBise has determined that a citywide service area is appropriate for the City of Grand Junction for all impact fees with the exception of parks and recreation, which includes the 201 Service Area Boundary.


APPENDIX A: LAND USE ASSUMPTIONS

Overview

The City of Grand Junction, Colorado, retained TischlerBise to analyze the impacts of development on its capital facilities and to calculate impact fees based on that analysis. The population, housing unit, and job projections contained in this document provide the foundation for the impact fee study. To evaluate demand for growth-related infrastructure from various types of development, TischlerBise prepared documentation on demand indicators by type of housing unit, jobs and floor area by type of nonresidential development. These metrics (explained further below) are the demand indicators to be used in the impact fee study.

Impact fees are based on the need for growth-related capital improvements, and they must be proportionate by type of land use. The demographic data and development projections are used to demonstrate proportionality and to anticipate the need for future infrastructure. Demographic data reported by the U.S. Census Bureau, and data provided by Grand Junction and Mesa County Regional Transportation Planning Organization (RTPO) staff, are used to calculate base year estimates and annual *projections* for a 10-year horizon. Impact fee studies typically look out five to ten years, with the expectation that fees will be updated every three to five years.

Figure A1: Grand Junction Municipal Boundary




Residential Development

Current estimates and future projections of residential development are detailed in this section, including population and housing units by type (e.g., single-family versus multi-family units).

Population and Housing Units

Due to differing development patterns both in and outside of City limits, TischlerBise reviewed base year population and housing unit estimates for the City of Grand Junction and specific TAZ boundaries from the Transportation Master Plan which are also associated with the 201 Sewer Service Area Boundary. The task at hand is to provide baseline population and housing unit estimates for those areas of the 201 Sewer Service Area Boundary which can reasonably be expected to be annexed into the City of Grand Junction over the next ten years. Figure A2 depicts the 201 Sewer Service Area Boundary (light blue line) and TAZ areas (yellow) incorporated into the study population and housing estimates.

Figure A2: Map of 201 Sewer Service Boundary and TAZ Areas



Persons per Housing Unit

In 2010 the U.S. Census Bureau transitioned from the traditional long-form questionnaire to the American Community Survey (ACS), which is less detailed and has smaller sample sizes. As a result, Census data now has more limitations than before. For example, data on detached housing units are now combined with attached single units (commonly known as townhouses). For impact fees in Grand Junction, “single-family” residential includes detached units and townhouses that share a common sidewall but are constructed on

an individual parcel of land. The second residential category includes all multi-family structures with two or more units on an individual parcel of land. The third residential category (All Other Types) includes mobile homes and recreational vehicles.

According to the Census Bureau, a household is a housing unit that is occupied by year-round residents. Impact fees often use per capita standards and persons per housing unit, or persons per household, to derive proportionate-share fee amounts. When persons per housing unit are used in the fee calculations, infrastructure standards are derived using year-round population. When persons per household are used in the fee calculations, the impact fee methodology assumes all housing units will be occupied, this requiring seasonal or peak population to be used when deriving infrastructure standards.

To estimate population for future years, the analysis applies growth assumptions derived from the *Grand Valley 2040 Transportation Master Plan 201 TAZ Estimates*, City GIS parcel data, 2018 ESRI Business Survey, Mesa County Building Permit data and standards from the Institute of Transportation Engineers, 10th addition. For the impact fee calculations, TischlerBise will rely on the above referenced as well as a variety of local and regional data sources including the 2017 ACS results shown at the top of Figure A3. Collectively, this information is used to indicate the relative number of persons per housing unit, by units in a residential structure, (2.37 PPHU Single-Family, 1.70 PPHU Multi-Family) and the housing mix (67% Single-Family, 27% Multi-Family) in Grand Junction. Because of the minimal seasonal population residing in the City, TischlerBise recommends that impact fees for residential development be imposed according to housing unit type.

Figure A3: Persons per Household and Persons per Housing Unit by Type of Housing

<i>Units in Structure</i>	<i>Persons</i>	<i>Households</i>	<i>Persons per Household</i>	<i>Housing Units</i>	<i>Persons per Housing Unit</i>	<i>Housing Mix</i>	<i>Vacancy Rate⁴</i>
Single-Family Units ¹	46,611	18,710	2.49	19,679	2.37	73%	4.92%
Multi-Family Units	11,391	6,788	1.68	7,316	1.56	27%	7.22%
Subtotal	58,002	25,498	2.27	26,995	2.15		5.55%
Group Quarters	2,880						
Total	60,882						

Source: U.S. Census Bureau, 2017 American Community Survey, Tables B25024, B25032, B25033, and B26001

1. Includes detached and attached units (i.e. townhouses) and mobile homes.

Recent Residential Construction

The City of Grand Junction provided TischlerBise with recent City residential building permit activity, shown in Figure A4. A total of 2,356 single-family and 514 multi-family permits were issued in the City from 2011 through 2018. Unit distribution over this period was 18 percent multi-family and 82 percent single-family. This ratio is slightly higher than the overall housing unit mix in the City which based on GIS parcel data analysis show that 77 percent of existing residential structures are single-family units and 23 percent are multi-family. It is worth mentioning that at the time of the writing of this report, over 150 multi-family units are in some stage of development review, which if constructed, would bring the 10-year average unit split closer to ratio reflected in the GIS parcel data.

Figure A4: Recent Grand Junction Residential Permit Activity

Year	Single Family	%	Multi-Family	%	Total
2011-2018	2,356	82%	514	18%	2,870

Source: City of Grand Junction, CO Building Permit Data

Current Population and Housing within Grand Junction City Limits

By December 31, 2018, Grand Junction's population grew to approximately 66,425 residing in 28,934 housing units according to analysis performed by TischlerBise which relied on the 2017 DOLA population estimate of 66,224, plus 1,201 new residents which represents observed growth over 2018. This rate of growth is above the average annual growth from 2011-2018 of 359 units and 798 persons per year (295 SF units x 2.37 PPHU=699) +(64 MF units x 1.56 PPHU=99) as shown below in Figure A5.

Figure A5: Grand Junction 2018 Population and Housing Unit Estimate

	DOLA 2017 est.	2011-2018 New Construction ¹	Avg. Annual New Units 2011-2018	2018 Housing Units Added	PPHU ²	Est. 2018 Population Growth	Total
Single-Family Units		2,356	295	498	2.37	1,180	
Multi-Family Units		514	64	13	1.56	20	
Housing Units	28,423		359	511			28,934
Population	65,224					1,201	66,425

Sources: 1.City of Grand Junction Building Permit Data, TischlerBise Analysis

2. U.S. Census 2017 ACS 5-year Estimate

Current Population and Housing within 201 Growth Area Boundary

Population and housing unit estimates for the 201 Sewer Service Area Boundary were compiled from sewer boundary specific TAZ areas, less specific portions of zones which included neighborhood sewer systems and therefore are unlikely to be annexed into the City. TischlerBise applied the population, housing unit estimates found within the *Grand Valley 2040 Transportation Master Plan* in each TAZ) to derive the number of existing housing units in the service area but outside of the City limits. The resulting estimates, shown in Figure A6, suggest approximately 14,217 housing units (28,934 units within current municipal boundary-43,151 units within the sewer service area) exist in the 201 Sewer Service Area Boundary, outside of the City limits for which *impact fees will not be collected*. Deducting the estimated 2018 Grand Junction population from the 201 Sewer Service Area Boundary TAZ area (66,425-103,224) results in an estimated population of 36,800 currently residing in the 201 Sewer Service Area, outside of City limits.

Figure A6: 2018 Population and Housing Unit Estimates 201 Boundary Selected TAZ

Development Type	2018	2018	
Residential	City Limits	201 Sewer Service Boundary	Total
Population	66,425	36,800	103,224
Housing Units	28,934	14,217	43,151

Source: Grand Valley 2040 Transportation Master Plan 201 TAZ Estimates

Projected Population and Housing Units

The selected Transportation Master Plan TAZ areas, shown in Figure A7, include new housing unit projections from 2018 to 2028 of 708 units annually. A total of 50,227 housing units, (7,076 net new units) are projected in the area by 2028. Given historic housing dispersion throughout the 201 Sewer Boundary and observed residential unit composition for the area, housing estimates were broken down between existing City limits and areas currently outside but within the 201 Boundary. As observed within the City GIS parcel data, 77 percent of current Grand Junction housing units are single-family. City housing unit growth projections have mirrored this observed ratio resulting in an estimated addition of 3,653 single-family and 1,091 multi-family units by 2028. For areas outside current City limits but within the 201 Sewer Service Area Boundary, 100 percent the grow of new housing units, 2,331, have been attributed to single-family development reflecting the rural composition of the area.

The Transportation Master Plan model estimates a ten-year population increase of 18,688 persons for the selected 201 Sewer Service Area boundary TAZ areas. All totals shown below in Figure A7 represent estimates as of January 1st of each year.

Figure A7: Grand Junction Residential Development Projections for Selected TAZ Areas

		5-Year Increment							
		2018	2019	2020	2021	2022	2023	2028	10-Year Increase
		Base Year	1	2	3	4	5	10	
POPULATION									
	Grand Junction	66,425	67,558	68,691	69,911	71,131	72,351	78,450	12,025
	201 /Outside City	36,800	37,428	38,055	38,731	39,407	40,083	43,462	6,662
	Total	103,224	104,985	106,746	108,642	110,538	112,434	121,912	18,688
HOUSING UNITS									
	GJ Single-Family	22,279	22,656	23,032	23,395	23,757	24,120	25,932	3,653
	GJ Multi-Family	6,655	6,767	6,880	6,988	7,096	7,205	7,746	1,091
Grand Junction Total		28,934	29,423	29,912	30,383	30,854	31,324	33,678	4,744
	201 Bdry Single-Family	14,217	14,458	14,698	14,929	15,161	15,392	16,549	2,331
	Total Housing Units	43,151	43,881	44,610	45,312	46,014	46,717	50,227	7,076

Nonresidential Development

In addition to data on residential development, the calculation of impact fees requires data on nonresidential development. All land use assumptions and projected growth rates are consistent with socioeconomic data from the Grand Valley 2040 Regional Transportation Plan and the 2018 ESRI Business Summary Report for Grand Junction. TischlerBise uses the term “jobs” to refer to employment by place of

work. In Figure A8, the nonresidential development prototypes used by TischlerBise to derive nonresidential floor area and average weekday vehicle trips ends are shown.

Employment Density Factors and Trip Generation Factors

The prototype for future projections of commercial / retail development is an average-size Shopping Center (ITE 820). Commercial / retail development (i.e. retail and eating / drinking places) is assumed to average 427 square feet per job. For future industrial development, Industrial Park (ITE 130) is a reasonable proxy with an average of 864 square feet per job. For office / other service development, General Office (ITE 710) is the prototype for future development, with an average of 337 square feet per job.

Figure A8: Nonresidential Demand Indicators

ITE Code	Land Use / Size	Demand Unit	Wkdy Trip Ends Per Dmd Unit*	Wkdy Trip Ends Per Employee*	Emp Per Dmd Unit	Sq. Ft. Per Emp
110	Light Industrial	1,000 Sq Ft	4.96	3.05	1.63	615
130	Industrial Park	1,000 Sq Ft	3.37	2.91	1.16	864
140	Manufacturing	1,000 Sq Ft	3.93	2.47	1.59	628
150	Warehousing	1,000 Sq Ft	1.74	5.05	0.34	2,902
254	Assisted Living	bed	2.60	4.24	0.61	na
320	Motel	room	3.35	25.17	0.13	na
520	Elementary School	1,000 Sq Ft	19.52	21.00	0.93	1,076
530	High School	1,000 Sq Ft	14.07	22.25	0.63	1,581
540	Community College	student	1.15	14.61	0.08	na
550	University/College	student	1.56	8.89	0.18	na
565	Day Care	student	4.09	21.38	0.19	na
610	Hospital	1,000 Sq Ft	10.72	3.79	2.83	354
710	General Office (avg size)	1,000 Sq Ft	9.74	3.28	2.97	337
760	Research & Dev Center	1,000 Sq Ft	11.26	3.29	3.42	292
770	Business Park	1,000 Sq Ft	12.44	4.04	3.08	325
820	Shopping Center (avg size)	1,000 Sq Ft	37.75	16.11	2.34	427

* Trip Generation, Institute of Transportation Engineers, 10th Edition (2017).

Nonresidential Floor Area and Employment

To determine future employment growth TischlerBise utilized different data sources to forecast future nonresidential development in the study area. To project future employment, our analysis relies on the observed 2018 jobs to population ratio of .88 (88 jobs per 100 residents) resulting in a 1.8 percent annual growth in employment rather than the 2.3 percent annual growth forecasted in the Transportation Master Plan. In order better understand the relationship between Grand Junction City limits employment and nonresidential growth and areas outside but within the 201 Sewer Boundary, TischlerBise reviewed the areas separately. The findings show that for the base year of 2010, 99.5 percent of all 201 Boundary jobs were located within Grand Junction while .5 percent were located outside of the City. Utilizing this ratio as a proxy allows for the allocation of future projected nonresidential floor area and estimated job growth between the 201 Sewer Boundary and City limits.

Figure A9: 2010 Grand Junction vs. 201 Sewer Boundary Employment Distribution

Total Employment	2010		
	City Limits	Sewer Service Boundary	Total
Jobs	57,609	283	57,892

Source: Grand Valley 2040 Transportation Master Plan 201 TAZ Estimates for City Growth Boundary

TischlerBise then applied ESRI employment estimates (58,660) for Grand Junction to derive a 2018 base, with jobs allocated to one of three nonresidential categories: Commercial / Retail, Industrial / Flex, and Office / Institutional. Grand Junction staff provided floor area estimates from their GIS data for 2018 totaling approximately 32,237,608 million square feet of nonresidential construction. This results in a base year estimate of approximately 33 percent of jobs occupying 11 million square feet of Commercial / Retail development, 18 percent of jobs occupying 6.6 million square feet of Industrial development, and 49 percent of jobs occupying approximately 14.5 million square feet of Office / Institutional development.

Figure A10: Grand Junction Nonresidential Floor Area and Employment Estimates 2018

Industry Sector	2018 Jobs ¹	Share of Total Jobs	SF per Employee ²	2018 Estimated Floor Area ²	Jobs per 1,000 SF
Commercial/Retail ³	19,099	33%	581	11,094,208	1.72
Office/Institutional ⁴	28,811	49%	503	14,498,503	1.99
Industrial/Flex ⁵	10,750	18%	618	6,644,897	1.62
TOTAL	58,660	100%		32,237,608	

1. ESRI Business Summary, Grand Junction, CO, 2018.

2. City of Grand Junction GIS Parcel Data, 2018

3. Major sector is Eating & Drinking places.

4. Major sectors are Health Services and Other Services.

5. Major sector are Construction and Manufacturing.

Projected Nonresidential Floor Area and Employment

Once the 2018 employment data was derived for the City, TischlerBise then established future employment growth by industry across the entire 201 Sewer Service Area Boundary. TAZ employment growth projections were distributed according to observed 2018 ESRI employment sector percentages for the City of Grand Junction (33% Commercial/Retail, 49% Office/Institutional, 18 % Industrial/Flex) (Figure A10). The resulting analysis results in an increase of 11,090 jobs throughout the study area of which 11,035 (11,090 x 99.5%) can be attributed to growth within the City limits. To calculate growth of nonresidential floor area, TischlerBise applied ITE Sq. Ft. per employee estimates (Figure A8) by estimated sector employment to derive net new annual growth. Projected nonresidential development over the next ten years results in an increase of 4.73 million square feet of floor area of which 4.7 million Sq. Ft. are projected to be developed within existing City limits. All totals shown below in Figure A11 represent estimates as of January 1st of each year.

Figure A11: Nonresidential Development Projections–Selected 201 Boundary TAZ Areas

		5-Year Increment						10-Year Increase	
		2018	2019	2020	2021	2022	2023		2028
		Base Year	1	2	3	4	5		10
POPULATION									
	Grand Junction	66,425	67,558	68,691	69,911	71,131	72,351	78,450	12,025
	201 /Outside City	36,800	37,428	38,055	38,731	39,407	40,083	43,462	6,662
	Total	103,224	104,985	106,746	108,642	110,538	112,434	121,912	18,688
EMPLOYMENT BY TYPE									
	GJ Commercial/Retail	19,099	19,806	20,138	20,496	20,853	21,211	22,999	3,900
	GJ Office/Institutional	28,811	29,409	29,902	30,433	30,964	31,495	34,150	5,339
	GJ Industrial/Flex	10,750	10,803	10,984	11,180	11,375	11,570	12,545	1,795
	Grand Junction Total	58,660	60,018	61,025	62,109	63,192	64,276	69,695	11,035
	201 Commercial/Retail	97	99	101	102	104	106	115	18
	201 Office/Institutional	144	147	150	152	155	157	171	27
	201 Industrial/Flex	53	54	55	56	57	58	63	10
	Total Employment	58,953	60,318	61,330	62,419	63,508	64,597	70,043	11,090
NONRES. FLOOR AREA (X 1,000 SF)									
	GJ Commercial/Retail	11,094	11,396	11,538	11,690	11,843	11,996	12,759	1,664
	GJ Office/Institutional	14,499	14,754	14,964	15,191	15,417	15,644	16,777	2,279
	GJ Industrial/Flex	6,645	6,668	6,745	6,828	6,911	6,995	7,411	766
	Grand Junction Total	32,238	32,817	33,247	33,709	34,172	34,634	36,947	4,709
	201 Commercial/Retail	41	42	43	44	44	45	49	8
	201 Office/Institutional	48	50	50	51	52	53	58	9
	201 Industrial/Flex	32	33	34	34	35	36	39	6
	201 Bdry Total	122	125	127	129	132	134	145	23
	Total Nonres. Floor Area	32,360	32,942	33,247	33,709	34,172	34,634	36,947	4,732

* Nonres Floor Area derived from Trip Generation, Institute of Transportation Engineers, 10th Edition (2017) Sq. Ft Per Emp. Multiplied by net new employment by sector.

* Population growth from TMP for Taz areas of 1.8%.

* Housing unit growth from TMP for TAZ areas of 1.6%

*Employment growth reflecting 2018 job/population ratio .8883. Applies sector % distribution from 2018 ESRI data.

*201 Outside City Employment .05% of Grand Junction employment held constant.

Summary of Growth Indicators

Key development projections for Grand Junction’s impact fee study are housing units and nonresidential floor area, summarized above. These projections are used to estimate impact fee revenue and to indicate the anticipated need for growth-related infrastructure. The goal is to have reasonable projections without being overly concerned with precision, because impact fees methodologies are designed to reduce sensitivity to development projections in the determination of the proportionate-share fee amounts. If actual development is slower than projected, impact fee revenue will decline, but so will the need for growth-related infrastructure. In contrast, if development is faster than anticipated, Grand Junction will receive more impact fee revenue, but it will also need to accelerate infrastructure improvements to keep pace with the actual rate of development.

Based on these projections, development in the combined 201 Sewer Service area and City over the next ten years is expected to average 707 residential units per year and 473,000 square feet of nonresidential floor area per year. Although significantly above the average annual increase of 359 housing units from 2011 to 2018, these projections include the larger 201 Sewer Growth Boundary.

Figure A12: Summary of Development Projections and Growth Rates

5-Year Increment								2018 to 2028 Average Annual	
	2018	2019	2020	2021	2022	2023	2028	Increase	Compound Growth Rate
GJ Housing Units	28,934	29,423	29,912	30,383	30,854	31,324	33,678	474	1.53%
201 Growth Bdry Housing Units	14,217	14,458	14,698	14,929	15,392	16,549	16,549	233	1.53%
GJ Nonresidential Sq. Ft x1,000	32,238	32,817	33,247	33,709	34,172	34,634	36,947	471	1.37%
201 Growth Bdry Nonresidential Sq. Ft x1,000	122	125	127	129	132	134	145	2	1.74%

Development Projections

Provided below is a summary of cumulative development projections used in the development impact fee study. Base year estimates for 2018 are used in the development impact fee calculations and *reflect the entirety of the City and Sewer Service 201 growth boundary*. Development projections are used to illustrate a possible future pace of demand for service units and cash flows resulting from revenues and expenditures associated with those demands. All totals represent estimates as of January 1st of each year.

Figure A13: Development Projections Summary Selected TAZ Areas

	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	10-Year Increase
	Base Year	1	2	3	4	5	6	7	8	9	10	
POPULATION												
Grand Junction	66,425	67,558	68,691	69,911	71,131	72,351	73,570	74,790	76,010	77,230	78,450	12,025
201 /Outside City	36,800	37,428	38,055	38,731	39,407	40,083	40,759	41,435	42,110	42,786	43,462	6,662
Total	103,224	104,985	106,746	108,642	110,538	112,434	114,329	116,225	118,121	120,016	121,912	18,688
HOUSING UNITS												
GJ Single-Family	22,279	22,656	23,032	23,395	23,757	24,120	24,482	24,845	25,207	25,570	25,932	3,653
GJ Multi-Family	6,655	6,767	6,880	6,988	7,096	7,205	7,313	7,421	7,529	7,638	7,746	1,091
Grand Junction Total	28,934	29,423	29,912	30,383	30,854	31,324	31,795	32,266	32,737	33,208	33,678	4,744
201 Bdry Single-Family	14,217	14,458	14,698	14,929	15,161	15,392	15,623	15,855	16,086	16,317	16,549	2,331
Total Housing Units	43,151	43,881	44,610	45,312	46,014	46,717	47,419	48,121	48,823	49,525	50,227	7,076
EMPLOYMENT BY TYPE												
GJ Commercial/Retail	19,099	19,806	20,138	20,496	20,853	21,211	21,569	21,926	22,284	22,642	22,999	3,900
GJ Office/Institutional	28,811	29,409	29,902	30,433	30,964	31,495	32,026	32,557	33,088	33,619	34,150	5,339
GJ Industrial/Flex	10,750	10,803	10,984	11,180	11,375	11,570	11,765	11,960	12,155	12,350	12,545	1,795
Grand Junction Total	58,660	60,018	61,025	62,109	63,192	64,276	65,360	66,444	67,527	68,611	69,695	11,035
201 Commercial/Retail	97	99	101	102	104	106	108	110	111	113	115	18
201 Office/Institutional	144	147	150	152	155	157	160	163	165	168	171	27
201 Industrial/Flex	53	54	55	56	57	58	59	60	61	62	63	10
Total Employment	58,953	60,318	61,330	62,419	63,508	64,597	65,687	66,776	67,865	68,954	70,043	11,090
NONRES. FLOOR AREA (X 1,000 SF)												
GJ Commercial/Retail	11,094	11,396	11,538	11,690	11,843	11,996	12,148	12,301	12,453	12,606	12,759	1,664
GJ Office/Institutional	14,499	14,754	14,964	15,191	15,417	15,644	15,871	16,097	16,324	16,551	16,777	2,279
GJ Industrial/Flex	6,645	6,668	6,745	6,828	6,911	6,995	7,078	7,161	7,244	7,328	7,411	766
Grand Junction Total	32,238	32,817	33,247	33,709	34,172	34,634	35,097	35,559	36,022	36,484	36,947	4,709
201 Commercial/Retail	41	42	43	44	44	45	46	47	48	48	49	8
201 Office/Institutional	48	50	50	51	52	53	54	55	56	57	58	9
201 Industrial/Flex	32	33	34	34	35	36	36	37	37	38	39	6
201 Bdry Total	122	125	127	129	132	134	136	138	141	143	145	23
Total Nonres. Floor Area	32,360	32,942	33,247	33,709	34,172	34,634	35,097	35,559	36,022	36,484	36,947	4,732

* Nonres Floor Area derived from Trip Generation, Institute of Transportation Engineers, 10th Edition (2017) Sq. Ft Per Emp. Multiplied by net new employment by sector.

* Population growth from TMP for Taz areas of 1.8%.

* Housing unit growth from TMP for TAZ areas of 1.6%

*Employment growth reflecting 2018 job/population ratio .8883. Applies sector % distribution from 2018 ESRI data.

*201 Outside City Employment .05% of Grand Junction employment held constant.

Found below in Figure A14, in the base year, there is a total of 271,362 average weekday vehicle trips in the City of Grand Junction. The trip totals are calculated by multiplying the average weekday vehicle trip factors with the base year nonresidential floor area.

To project the 10-year increase in trips, the growth in nonresidential floor area is used. It is projected that over the next ten years there will be an increase of 40,643 nonresidential vehicle trips in the City of Grand Junction.

Figure A14: Nonresidential Vehicle Trip Projections

	5-Year Increment-->							10-Year Increase
	2018 Base Yr	2019 1	2020 2	2021 3	2022 4	2023 5	2028 10	
Commercial/Retail	184,275	189,286	191,641	194,176	196,711	199,246	211,921	27,647
Office/Institutional	70,608	71,850	72,875	73,979	75,083	76,186	81,705	11,097
Industrial/Flex	16,479	16,536	16,727	16,934	17,140	17,347	18,379	1,900
Total Nonres. Vehicle Trips	271,362	277,672	281,244	285,089	288,934	292,779	312,005	40,643

1. Trip rates are customized for Grand Junction.

2. Trip rates are from the Institute of Transportation Engineers (ITE) Trip Generation Manual (2017).

APPENDIX B: LAND USE DEFINITIONS

Residential Development

As discussed below, residential development categories are based on data from the U.S. Census Bureau, American Community Survey. Grand Junction will collect development fees from all new residential units. One-time development fees are determined by site capacity (i.e. number of residential units). This category also contains mobile homes and recreational vehicles

Single-Family: Single-Family detached is a one-unit structure detached from any other house, that is, with open space on all four sides. Such structures are considered detached even if they have an adjoining shed or garage. A one-family house that contains a business is considered detached as long as the building has open space on all four sides. Also included in the definition is Single family attached (townhouse), which is a one-unit structure that has one or more walls extending from ground to roof separating it from adjoining structures. In row houses (sometimes called townhouses), double houses, or houses attached to nonresidential structures, each house is a separate, attached structure if the dividing or common wall goes from ground to roof.

Multi-Family: 2+ units (duplexes and apartments) are units in structures containing two or more housing units, further categorized as units in structures with “2, 3 or 4, 5 to 9, 10 to 19, 20 to 49, and 50 or more apartments.”

Nonresidential Development

The proposed general nonresidential development categories (defined below using 2017 ITE Land Use Code) can be used for all new construction within Grand Junction. Nonresidential development categories represent general groups of land uses that share similar average weekday vehicle trip generation rates and employment densities (i.e., jobs per thousand square feet of floor area).

Land Use: 820 Shopping Center Description. A shopping center is an integrated group of commercial establishments that is planned, developed, owned, and managed as a unit. A shopping center’s composition is related to its market area in terms of size, location, and type of store. A shopping center also provides on-site parking facilities sufficient to serve its own parking demands. Factory outlet center (Land Use 823) is a related use.

Land Use: 710 General Office Building Description. A general office building houses multiple tenants; it is a location where affairs of businesses, commercial or industrial organizations, or professional persons or firms are conducted. An office building or buildings may contain a mixture of tenants including professional services, insurance companies, investment brokers, and tenant services, such as a bank or savings and loan institution, a restaurant, or cafeteria and service retail facilities. A general office building with a gross floor area of 5,000 square feet or less is classified as a small office building (Land Use 712). Corporate headquarters building (Land Use 714), single tenant office building (Land Use 715), office park (Land Use 750), research and development center (Land Use 760), and business park (Land Use 770) are

additional related uses. If information is known about individual buildings, it is suggested that the general office building category be used rather than office parks when estimating trip generation for one or more office buildings in a single development. The office park category is more general and should be used when a breakdown of individual or different uses is not known. If the general office building category is used and if additional buildings, such as banks, restaurants, or retail stores are included in the development, the development should be treated as a multiuse project. On the other hand, if the office park category is used, internal trips are already reflected in the data and do not need to be considered. When the buildings are interrelated (defined by shared parking facilities or the ability to easily walk between buildings) or house one tenant, it is suggested that the total area or employment of all the buildings be used for calculating the trip generation. When the individual buildings are isolated and not related to one another, it is suggested that trip generation be calculated for each building separately and then summed.

Land Use: 130 Industrial Park Description. An industrial park contains a number of industrial or related facilities. It is characterized by a mix of manufacturing, service, and warehouse facilities with a wide variation in the proportion of each type of use from one location to another. Many industrial parks contain highly diversified facilities—some with a large number of small businesses and others with one or two dominant industries. General light industrial (Land Use 110) and manufacturing (Land Use 140) are related uses.

Land Use: 150 Warehousing Description. A warehouse is primarily devoted to the storage of materials, but it may also include office and maintenance areas. High-cube transload and short-term storage warehouse (Land Use 154), high-cube fulfillment center warehouse (Land Use 155), high-cube parcel hub warehouse (Land Use 156), and high-cube cold storage warehouse (Land Use 157) are related uses.



Impact Fee Study Workshop

Grand Junction, Colorado
8/19/19

TischlerBise
FISCAL | ECONOMIC | PLANNING


■ 40-Year National Practice

- » Impact fees
- » Fiscal impact analysis
- » Economic impact analysis
- » Infrastructure funding strategies
- » Market feasibility

Adams County	Arapahoe County	Aurora	Boulder
Castle Pines	Castle Rock	Centennial	Colorado Springs
Durango	Eaton	Erie	Evans
Fort Collins	Garfield County	Grand Junction	Greeley
Johnstown	La Plata County	Larimer County	Lone Tree
Longmont	Louisville	Mead	Mesa County
Montezuma County	Parker	Pitkin County	Pueblo
Steamboat Springs	Thornton	Vail	Westminster

Legal and Methodology

- One time payments to fund system improvements
- Cannot be deposited into General Fund
- Basic legal requirements are need, benefit, and proportionality
- General Methods
 - » Plan Based
 - » Cost Recovery
 - » Incremental Expansion





Impact Fees in Colorado

- Governed by Senate Bill 15
 - » October 2001
- Improvement or facility that:
 - » Is directly related to any service that a local government is authorized to provide;
 - » Has a useful life of five years or longer
- Specific accounting requirements
- Allows a local government to waive an impact fee on the development of low/moderate income housing
 - » Does not address whether the local government is required to “make up” the difference



Grand Junction Impact Fee Program

- Existing impact fees
 - » Parks
 - » Water plant investment fee
 - » Wastewater plant investment fee
- Potential impact fees as part of this study
 - » Parks (updated)
 - » Fire/EMS (new)
 - » Police (new)
 - » Municipal facilities (new)



Fire Impact Fee

- Consumption-based approach
- Service area exceeds City limits
 - » 83% of incidents are inside City
- Components
 - » Stations
 - » Vehicles/Apparatus
- Credit for existing debt

Fire 10-Year Facility/Apparatus Demand

Level-of-Service		Demand Unit	Unit Cost
Residential	0.49		
Nonresidential	0.06	Square Feet	per Person
		per Trip End	\$450

Growth-Related Need for Facilities						
Year		Population	Nonres. Vehicle Trips	Residential Sq. Ft.	Nonres. Sq. Ft.	Total
Base	2018	66,425	271,362	32,721	17,558	50,279
Year 1	2019	67,558	277,672	33,279	17,966	51,245
Year 2	2020	68,691	281,244	33,837	18,197	52,035
Year 3	2021	69,911	285,089	34,438	18,446	52,884
Year 4	2022	71,131	288,934	35,039	18,695	53,734
Year 5	2023	72,351	292,779	35,640	18,944	54,584
Year 6	2024	73,570	296,625	36,241	19,193	55,434
Year 7	2025	74,790	300,470	36,842	19,441	56,283
Year 8	2026	76,010	304,315	37,443	19,690	57,133
Year 9	2027	77,230	308,160	38,044	19,939	57,983
Year 10	2028	78,450	312,005	38,645	20,188	58,833
Ten-Year Increase		12,025	40,643	5,924	2,630	8,554
Growth-Related Expenditure				\$2,665,693	\$1,183,388	\$3,849,081

Level-of-Service		Demand Unit	Unit Cost
Residential	0.00031		
Nonresidential	0.00004	Units	per Person
		per Trip End	\$322,711

Growth-Related Need for Apparatus						
Year		Population	Nonres. Vehicle Trips	Residential Vehicles	Nonres. Vehicles	Total
Base	2018	66,425	271,362	21	11	32
Year 1	2019	67,558	277,672	21	11	32
Year 2	2020	68,691	281,244	21	11	33
Year 3	2021	69,911	285,089	22	12	33
Year 4	2022	71,131	288,934	22	12	34
Year 5	2023	72,351	292,779	22	12	34
Year 6	2024	73,570	296,625	23	12	35
Year 7	2025	74,790	300,470	23	12	35
Year 8	2026	76,010	304,315	23	12	36
Year 9	2027	77,230	308,160	24	13	36
Year 10	2028	78,450	312,005	24	13	37
Ten-Year Increase		12,025	40,643	4	2	5
Growth-Related Expenditure				\$1,290,842	\$645,421	\$1,613,553

Maximum Supportable Fire Impact Fee

<i>Fee Component</i>	<i>Cost per Person</i>	<i>Cost per Vehicle Trip</i>
Facilities	\$221.67	\$29.12
Vehicles	\$99.72	\$13.10
Existing Principal Credit	(\$21.68)	(\$2.94)
NET COST PER DEMAND UNIT	\$299.71	\$39.28

Residential

<i>Housing Type</i>	<i>Persons per Housing Unit</i>	<i>Maximum Supportable Fee</i>
Single-Family	2.37	\$710
Multi-Family	1.56	\$467

Nonresidential

<i>Type</i>	<i>ITE Code</i>	<i>Unit</i>	<i>Average Daily Vehicle Trips*</i>	<i>Trip Adjustment Factor*</i>	<i>Maximum Supportable Fee</i>
Retail/Commercial	820	1,000 SF	37.75	33%	\$489
Office/Institutional	710	1,000 SF	9.74	50%	\$191
Industrial	130	1,000 SF	3.37	50%	\$66
Warehousing	150	1,000 SF	1.74	50%	\$34

*Institute of Transportation Engineers (ITE), Trip Generation Manual, 10th Edition, 2017



Police Impact Fee

- Consumption-based approach
- Components
 - » Police space
 - » Vehicles funded through Proposition 2B
- Citywide service area

Police 10-Year Facility Demand

Police Station Level-of-Service Standards

Level-of-Service		Demand Unit	Unit Cost
Residential	0.63	per Person	\$344
Nonresidential	0.08	per Trip End	

Growth-Related Need for Facilities						
Year		Population	Nonres. Vehicle Trips	Residential Sq. Ft.	Nonresidential Sq. Ft.	Total
Base	2018	66,425	271,362	41,561	22,302	63,863
Year 1	2019	67,558	277,672	42,270	22,820	65,091
Year 2	2020	68,691	281,244	42,979	23,114	66,093
Year 3	2021	69,911	285,089	43,743	23,430	67,172
Year 4	2022	71,131	288,934	44,506	23,746	68,252
Year 5	2023	72,351	292,779	45,269	24,062	69,331
Year 6	2024	73,570	296,625	46,032	24,378	70,410
Year 7	2025	74,790	300,470	46,796	24,694	71,490
Year 8	2026	76,010	304,315	47,559	25,010	72,569
Year 9	2027	77,230	308,160	48,322	25,326	73,648
Year 10	2028	78,450	312,005	49,086	25,642	74,727
Ten-Year Increase		12,025	40,643	7,524	3,340	10,864
Growth-Related Expenditure				\$2,589,761	\$1,149,628	\$3,739,389

Maximum Supportable Police Impact Fee

<i>Fee Component</i>	<i>Cost per Person</i>	<i>Cost per Vehicle Trip</i>
Police Space	\$215.36	\$28.29
Existing Principal Credit	(\$86.71)	(\$11.74)
NET COST PER DEMAND UNIT	\$128.65	\$16.55

Residential

<i>Housing Type</i>	<i>Persons per Housing Unit</i>	<i>Maximum Supportable Fee</i>
Single-Family	2.37	\$305
Multi-Family	1.56	\$200

Nonresidential

<i>Type</i>	<i>ITE Code</i>	<i>Unit</i>	<i>Average Daily Vehicle Trips*</i>	<i>Trip Adjustment Factor*</i>	<i>Maximum Supportable Fee</i>
Retail/Commercial	820	1,000 SF	37.75	33%	\$206
Office/Institutional	710	1,000 SF	9.74	50%	\$81
Industrial	130	1,000 SF	3.37	50%	\$28
Warehousing	150	1,000 SF	1.74	50%	\$14

*Institute of Transportation Engineers (ITE), Trip Generation Manual, 10th Edition, 2017



Municipal Facilities Impact Fee

- Consumption-based approach
- Citywide service area
- Components
 - » General Government Space

Municipal Facilities 10-Year Demand

Type of Infrastructure	Level of Service		Demand Unit	Unit Cost / Sq. Ft.
Municipal Facilities	Residential	1.20	per persons	\$277
	Nonresidential	0.73	per jobs	

Growth-Related Need for Municipal Facilities						
Year		Population	Jobs	Residential Square Feet	Nonresidential Square Feet	Total Square Feet
Base	2018	66,425	58,660	79,518	42,669	122,187
Year 1	2019	67,558	60,018	80,874	43,657	124,531
Year 2	2020	68,691	61,025	82,230	44,389	126,619
Year 3	2021	69,911	62,109	83,691	45,178	128,869
Year 4	2022	71,131	63,192	85,151	45,966	131,117
Year 5	2023	72,351	64,276	86,612	46,754	133,366
Year 6	2024	73,570	65,360	88,072	47,542	135,614
Year 7	2025	74,790	66,444	89,532	48,331	137,863
Year 8	2026	76,010	67,527	90,993	49,119	140,112
Year 9	2027	77,230	68,611	92,453	49,907	142,360
Year 10	2028	78,450	69,695	93,913	50,696	144,609
Ten-Year Increase		12,025	11,035	14,395	8,027	22,422
Projected Expenditure				\$3,987,432	\$2,223,462	\$6,210,894

Growth-Related Expenditure on Municipal Facilities

\$6,210,894

Maximum Supportable Municipal Facilities Impact Fee

Fee Component	Cost per Person	Cost per Job
Municipal Facilities Space	\$331.60	\$201.49

Residential (per unit)

Development Type	Persons per Housing Unit	Maximum Supportable Fee
Single Family	2.37	\$785
Multi-Family	1.56	\$516

Nonresidential

Type	ITE Code	Unit	Employees*	Maximum Supportable Fee
Retail/Commercial	820	1,000 SF	2.34	\$471
Office/Institutional	710	1,000 SF	2.97	\$598
Industrial	130	1,000 SF	1.16	\$234
Warehousing	150	1,000 SF	0.34	\$69

*Employment densities were calculated using data from the Institute of Transportation Engineers (ITE), Trip Generation Manual, 10th Edition.



Parks and Recreation Impact Fee

■ Consumption-based approach

- » Assumes the City does not purchase additional park land in the short-term
- » Impact fees go to develop existing parks and banked park land

■ Citywide service area

- » Residents within the 201 Service Area population is used as “Park Population”

■ Components

- » Level 1 and 2 park improvements

Level 1 Park Improvement Needs

Level 1 Park Infrastructure Level-of-Service Standards

Type	Level of Service	Demand Unit	Unit Cost / Acre
Level 1 Park Improvements	0.0001 Acres	per person	\$112,500

Growth-Related Need for Level 1 Park Improvements			
Year		Population	Improved Acres
Base	2018	103,224	10.32
Year 1	2019	104,985	10.50
Year 2	2020	106,746	10.67
Year 3	2021	108,642	10.86
Year 4	2022	110,538	11.05
Year 5	2023	112,434	11.24
Year 6	2024	114,329	11.43
Year 7	2025	116,225	11.62
Year 8	2026	118,121	11.81
Year 9	2027	120,016	12.00
Year 10	2028	121,912	12.19
Ten-Year Increase		18,688	1.87
Growth-Related Expenditure on Level 1 Park Improvements			\$210,375

Level 2 Park Improvement Needs

Level 2 Park Infrastructure Level-of-Service Standards

Type	Level of Service	Demand Unit	Unit Cost / Acre
Level 2 Park Improvements	0.0035 Acres	per 1,000 persons	\$192,500

Growth-Related Need for Level 2 Park Improvements			
Year		Population	Improved Acres
Base	2018	103,224	357.54
Year 1	2019	104,985	363.64
Year 2	2020	106,746	369.74
Year 3	2021	108,642	376.31
Year 4	2022	110,538	382.87
Year 5	2023	112,434	389.44
Year 6	2024	114,329	396.00
Year 7	2025	116,225	402.57
Year 8	2026	118,121	409.14
Year 9	2027	120,016	415.70
Year 10	2028	121,912	422.27
Ten-Year Increase		18,688	65
Growth-Related Expenditure Level 2 Park Improvements			\$12,512,500

Maximum Supportable Park Impact Fee

Fee Component	Cost per Person
Level 1 Parkland Improvements	\$11.25
Level 2 Parkland Improvements	\$666.76
COST PER DEMAND UNIT	\$678.01

Type	Persons per Housing Unit	Maximum Supportable Fee	Current Fee	Increase
Single-Family	2.37	\$1,605	\$225	\$1,380
Multi-Family	1.56	\$1,055	\$225	\$830

Maximum Supportable Fee Summary

Residential (Per Unit)

<i>Type</i>	<i>Fire</i>	<i>Police</i>	<i>Parks and Recreation</i>	<i>Municipal Facilities</i>	<i>Maximum Supportable Fee</i>	<i>Current Fee</i>	<i>Difference</i>
Single-Family	\$710	\$305	\$1,605	\$785	\$3,405	\$225	\$3,180
Multi-Family	\$467	\$200	\$1,055	\$516	\$2,238	\$225	\$2,013

Nonresidential (Per 1,000 square feet)

<i>Type</i>	<i>Fire</i>	<i>Police</i>	<i>Parks and Recreation</i>	<i>Municipal Facilities</i>	<i>Maximum Supportable Fee</i>	<i>Current Fee</i>	<i>Difference</i>
Retail/Commercial	\$489	\$206	\$0	\$471	\$1,167	\$0	\$1,167
Office/Institutional	\$191	\$81	\$0	\$598	\$870	\$0	\$870
Industrial	\$66	\$28	\$0	\$234	\$328	\$0	\$328
Warehousing	\$34	\$14	\$0	\$69	\$117	\$0	\$117

Water Plant Investment Fee

- Last updated pre-1990s
- In 2015, Raftelis Financial Consultants proposed 2016 PIF:
 - » \$4,100 per capacity unit (Cash Financed)
 - » System net equity = \$69.9 million
 - » System capacity = 16.3 million gallons per day (16,900 capacity units)
 - » Does not include recovery of proportionate share of City's water rights
- 2019 PIF: \$4,480 (3% escalation)

Fee	Purpose	Cost
Plant Investment Fee	- Recover the cost of constructing the system. - Cost range based on size of service line and meter (3/4" – 6").	\$300 - \$8,500
Tap Fee	- Recover cost of City crews making physical connection to water main line and supplying meter. - Cost range based on size of service line and meter (3/4" – 6").	\$700 – 19,850

Proposed Water Plant Investment Fees

Water Plant Investment Fees

SIZE (inch)	TAP	PIF	TOTAL CONNECTION FEE	PROPOSED
3/4 x 5/8	\$700	\$300	\$1,000	\$5,180
3/4 x 3/4				
1	\$875	\$375	\$1,250	\$6,850
1.5	\$2,050	\$900	\$2,950	\$12,580
2	\$2,900	\$1,250	\$4,150	\$18,520
3	\$6,875	\$2,975	\$9,850	\$33,360
4	\$12,850	\$5,550	\$18,400	\$54,480
6	\$19,850	\$8,500	\$28,400	\$155,632

Comparison of Water-Related Fees

Water Plant Investment Fees

SIZE (inch)	PROPOSED	Ute Water (2019)	Clifton Water (2019)	Denver Water (2019) (1)	Aurora	Greeley	Pueblo (4)	Flagstaff, AZ (5)	Cheyenne, WY
Single Family (1-2 bath, 1/8 ac lot)					\$ 8,773.69				
Single Family (3-4 bath, 1/8 ac lot)					\$ 15,530.69				
Single Family (5+ bath, 1/8 ac lot)					\$ 22,755.69				
Multi-family (per unit)					\$ 9,760.00		\$ 2,880.00		
Single Family (2000 sf)				\$ 4,430.00					
Multi-family (2 DU)				\$ 1,040.00					
Multi-family (8 DU)				\$ 24,560.00					
Multi-family (20 DU)				\$ 47,840.00					
3/4 x 5/8	\$5,180	\$7,000	\$7,000	\$ 10,730.00	\$ 22,195.00	\$ 10,800.00	\$ 5,069.00	\$ 5,728.00	\$ 8,030.00
3/4 x 3/4		\$8,750	\$8,750						
1	\$6,850	\$10,500	\$16,250	\$ 19,170.00	\$ 39,729.00	\$ 18,000.00	\$ 4,909.00	\$ 9,566.00	\$ 19,420.00
1.5	\$12,580	\$15,725	\$18,000	\$ 42,180.00	\$ 87,227.00	\$ 36,000.00	\$ 25,029.00	\$ 19,074.00	\$ 38,730.00
2	\$18,520	\$23,150	\$27,000	\$ 76,690.00	(3)	\$ 57,500.00	\$ 31,725.00	\$ 30,530.00	\$ 61,990.00
3	\$33,360	\$41,700	\$40,500	\$ 126,426.00	(3)	\$ 126,000.00	\$ 60,973.00	\$ 57,279.00	\$ 168,640.00
4	\$54,480	\$73,100	\$60,840	\$ 229,971.00	(3)	\$ 216,600.00	\$ 210,439.00	\$ 95,484.00	\$ 290,760.00
6	\$155,632	\$182,800	\$91,260	\$ 517,374.00		\$ 450,000.00	\$ 434,157.00	\$ 190,910.00	\$ 620,260.00
8			\$136,890	\$ 774,957.00			\$ 1,007,583.00	\$ 305,468.00	
10			\$205,336	\$ 1,200,204.00				\$ 439,157.00	
12				\$ 1,235,855.00					

(1) Denver Water Rates

Single Family Residential

Base Charge

\$ per sf

ADU

Multi-family

First two DU

Next 6 DU

Over 8 DU, \$ per unit

Fees for specific tap sizes are for nonresidential.

(2) Aurora Water Rates

Residential

Outdoor Use Fee (per sf lot size)

Outdoor use fee for common areas in non-fee simple lots will be supplied by an irrigation meter.

Commercial

Fees for specific tap sizes are for nonresidential.

(3) Commercial Water Connection fees for meters 2-inches and greater are based on the estimated daily volume of water and assessed at \$63.82 per gallon/per day for connection and water transmission development fee. Consumption beyond initial allocation may be addressed through monthly bill or payment of additional connection fees.

Outdoor Use Fee (per sf lot size)

--Non-water Conserving

--Water Conserving

(4) Pueblo

Plant investment fee only, water tap fee charged separately

(5) Flagstaff

Water Capacity fee only, separate tap fee

Historical/Projected Water Revenue

City Water Meter Sales

Meter Size	3/4 inch	1 inch	1.5 inch	2 inch	3 inch	4 inch	Total Mtrs	PIF/Tap Revenue	Proposed PIF/Tap	Revenue Difference
2019 Year to Date	16	0	0	0	0	1	17	\$34,400.00	\$137,720.00	\$103,320.00
2018	36	0	1	5	3	0	45	\$89,250.00	\$391,740.00	\$302,490.00
2017	42	1	3	2	0	0	48	\$60,400.00	\$299,190.00	\$238,790.00

2020 Estimated Meter Sales

	3/4 inch	1 inch	1.5 inch	2 inch	3 inch	4 inch	Total Mtrs	
2020	30	0	0	3	0	4	37	\$430,320.00

Fire, Police, Parks and Recreation and Municipal Services Impact Fee Implementation Schedule and Comparison

			Jan 1 2020	Jan 1 2021	Jan 1 2022	Stakeholder Proposed 8/30/2019
			33%	66%	Staff Proposed 100%	
Residential	Land Use Type	Unit	Current Fees			
	Single Family					
	Fire	Dwelling	\$0	\$234	\$469	\$710
	Police	Dwelling	\$0	\$101	\$201	\$305
	Parks and Recreation	Dwelling	\$225	\$680	\$1,136	\$1,605
	Municipal Services	Dwelling	\$0	\$259	\$518	\$785
	Multi-Family					
	Fire	Dwelling	\$0	\$154	\$308	\$467
	Police	Dwelling	\$0	\$66	\$132	\$200
	Parks and Recreation	Dwelling	\$225	\$499	\$773	\$1,055
	Municipal Services	Dwelling	\$0	\$170	\$341	\$516
Commercial & Industrial	Retail/Commercial					
	Fire	1,000 sf	\$0	\$161	\$323	\$489
	Police	1,000 sf	\$0	\$68	\$136	\$206
	Parks and Recreation	1,000 sf	\$0	\$0	\$0	\$0
	Municipal Services	1,000 sf	\$0	\$155	\$311	\$471
	Office/Institutional					
	Fire	1,000 sf	\$0	\$63	\$126	\$191
	Police	1,000 sf	\$0	\$27	\$53	\$81
	Parks and Recreation	1,000 sf	\$0	\$0	\$0	\$0
	Municipal Services	1,000 sf	\$0	\$197	\$395	\$598
	Industrial					
	Fire	1,000 sf	\$0	\$22	\$44	\$66
	Police	1,000 sf	\$0	\$9	\$18	\$28
	Parks and Recreation	1,000 sf	\$0	\$0	\$0	\$0
	Municipal Services	1,000 sf	\$0	\$77	\$154	\$234
	Warehousing					
	Fire	1,000 sf	\$0	\$11	\$22	\$34
	Police	1,000 sf	\$0	\$5	\$9	\$14
	Parks and Recreation	1,000 sf	\$0	\$0	\$0	\$0
	Municipal Services	1,000 sf	\$0	\$23	\$46	\$69

Transportation Impact Fee Implementation Schedule and Comparison Chart

				Jan 1 2020	July 1 2020	Jan 1 2021	Jul 1 2021	Jan 1 2022	July 1 2022	Stakeholder Proposed	TIF Study
				16.7%	33%	50%	67%	83%	Staff Proposed	8/30/2019	100%
Land Use Type				Unit	Current Fees						
Residential	All Multi-Family	Dwelling	\$ 1,769	\$ 2,016	\$ 2,263	\$ 2,511	\$ 2,758	\$ 3,005	\$ 3,252	\$ 2,511	\$ 4,570
	<1,250 sq.ft of living area	Dwelling	\$ 2,554	\$ 2,670	\$ 2,787	\$ 2,903	\$ 3,019	\$ 3,136	\$ 3,252	\$ 2,903	
	1,250 to 1,649 sq.ft of living area	Dwelling	\$ 2,554	\$ 3,033	\$ 3,513	\$ 3,992	\$ 4,472	\$ 4,951	\$ 5,430	\$ 3,992	\$ 6,763
	1,650 to 2,299 sq.ft of living area	Dwelling	\$ 2,554	\$ 3,181	\$ 3,809	\$ 4,436	\$ 5,064	\$ 5,691	\$ 6,318	\$ 4,436	
	2,300 or more of living area	Dwelling	\$ 2,554	\$ 3,552	\$ 4,549	\$ 5,547	\$ 6,544	\$ 7,542	\$ 8,538	\$ 5,546	
Commercial & Industrial	Hotel/Motel	Room	\$ 2,407	\$ 2,703	\$ 2,999	\$ 3,295	\$ 3,591	\$ 3,887	\$ 4,183	\$ 3,295	\$ 4,183
	Shopping Center/Commercial	1,000 sf	\$ 4,189	\$ 4,864	\$ 5,540	\$ 6,215	\$ 6,890	\$ 7,566	\$ 8,240	\$ 6,215	\$ 8,240
	Auto Sales/Service	1,000 sf	\$ 3,780	\$ 4,523	\$ 5,267	\$ 6,010	\$ 6,754	\$ 7,497	\$ 8,240	\$ 6,010	\$ 9,258
	Golf Course	Hole	\$ 5,951	\$ 6,333	\$ 6,714	\$ 7,096	\$ 7,477	\$ 7,859	\$ 8,240	\$ 7,096	\$ 12,850
	Movie Theater	1,000 sf	\$ 10,574	\$ 10,185	\$ 9,796	\$ 9,407	\$ 9,018	\$ 8,629	\$ 8,240	\$ 8,240	\$ 33,028
	Restaurant, Standard	1,000 sf	\$ 5,159	\$ 5,673	\$ 6,186	\$ 6,700	\$ 7,213	\$ 7,727	\$ 8,240	\$ 6,700	\$ 14,975
	Bank, Drive-In	1,000 sf	\$ 6,359	\$ 8,360	\$ 10,362	\$ 12,363	\$ 14,365	\$ 16,366	\$ 18,365	\$ 12,352	\$ 18,365
	Convenience Store w/Gas Sales	1,000 sf	\$ 9,143	\$ 10,680	\$ 12,218	\$ 13,755	\$ 15,292	\$ 16,830	\$ 18,365	\$ 13,754	\$ 26,395
	Restaurant, Drive-Through	1,000 sf	\$ 11,544	\$ 12,681	\$ 13,818	\$ 14,955	\$ 16,092	\$ 17,229	\$ 18,365	\$ 14,955	\$ 33,203
	Office, General	1,000 sf	\$ 3,141	\$ 3,732	\$ 4,323	\$ 4,913	\$ 5,504	\$ 6,095	\$ 6,685	\$ 4,913	\$ 6,685
	Office, Medical	1,000 sf	\$ 8,862	\$ 8,499	\$ 8,136	\$ 7,773	\$ 7,410	\$ 7,047	\$ 6,685	\$ 6,685	\$ 25,665
	Animal Hospital/Vet Clinic	1,000 sf	\$ 8,862	\$ 8,499	\$ 8,136	\$ 7,773	\$ 7,410	\$ 7,047	\$ 6,685	\$ 6,685	\$ 15,858
	Hospital	1,000 sf	\$ 4,112	\$ 4,541	\$ 4,970	\$ 5,399	\$ 5,828	\$ 6,257	\$ 6,685	\$ 5,399	\$ 7,905
	Nursing Home	1,000 sf	\$ 1,149	\$ 1,239	\$ 1,329	\$ 1,419	\$ 1,508	\$ 1,598	\$ 1,688	\$ 1,419	\$ 3,120
	Place of Worship	1,000 sf	\$ 1,967	\$ 1,920	\$ 1,874	\$ 1,827	\$ 1,781	\$ 1,734	\$ 1,688	\$ 1,688	\$ 2,725
	Day Care Center	1,000 sf	\$ 4,086	\$ 3,686	\$ 3,287	\$ 2,887	\$ 2,487	\$ 2,087	\$ 1,688	\$ 1,688	\$ 4,485
	Elementary/Secondary School	1,000 sf	\$ 639	\$ 814	\$ 989	\$ 1,164	\$ 1,338	\$ 1,513	\$ 1,688	\$ 1,164	\$ 1,688
	Public/Institutional	1,000 sf	\$ 639	\$ 826	\$ 998	\$ 1,171	\$ 1,343	\$ 1,516	\$ 1,688	\$ 1,164	\$ 3,813
	Industrial	1,000 sf	\$ 1,864	\$ 1,900	\$ 1,935	\$ 1,971	\$ 2,007	\$ 2,042	\$ 2,078	\$ 1,971	\$ 2,078
	Warehouse	1,000 sf	\$ 1,328	\$ 1,286	\$ 1,244	\$ 1,201	\$ 1,159	\$ 1,117	\$ 1,075	\$ 1,075	\$ 1,248
	Mini-Warehouse	1,000 sf	\$ 460	\$ 563	\$ 665	\$ 768	\$ 870	\$ 973	\$ 1,075	\$ 768	\$ 1,075

Business Stakeholder Group Recommendation for items marked in red is that the 50% formula not be applied and that the new fees be adopted at 100% immediately

City of Grand Junction
Comparison of Staff Proposed to Industry Proposed
September 16, 2019

Residential Single Family (1,650 to 2,299 sq.ft.)									
	Current	Annual Increase (avg)	Bi-Annual Increase (avg)	Staff Proposed at 100%	Total Increase	Industry Proposed at 100%	Total Increase	Industry Less Than Proposed	
Transportation	\$ 2,554		\$ 627	\$ 6,318	\$ 3,764	\$ 4,436	\$ 1,882	\$ (1,882)	-30%
Fire	-	237		710	710	-	-	(710)	-100%
Police	-	102		305	305	-	-	(305)	-100%
Parks	225	460		1,605	1,380	915	690	(690)	-43%
Municipal Services	-	262		785	785	-	-	(785)	-100%
Total	\$ 2,779			\$ 9,723	\$ 6,944	\$ 5,351	\$ 2,572	\$ (4,372)	-45%

Residential Multi-Family									
	Current	Annual Increase (avg)	Bi-Annual Increase (avg)	Staff Proposed at 100%	Total Increase	Industry Proposed at 100%	Total Increase	Industry Less Than Proposed	
Transportation	\$ 1,769		\$ 247	\$ 3,252	\$ 1,483	\$ 2,511	\$ 742	\$ (741)	-23%
Fire	-	156		467	467	-	-	(467)	-100%
Police	-	67		200	200	-	-	(200)	-100%
Parks	225	277		1,055	830	640	415	(415)	-39%
Municipal Services	-	172		516	516	-	-	(516)	-100%
Total	\$ 1,994			\$ 5,490	\$ 3,496	\$ 3,151	\$ 1,157	\$ (2,339)	-43%

Retail Commercial Shopping Center									
	Current	Annual Increase (avg)	Bi-Annual Increase (avg)	Staff Proposed at 100%	Total Increase	Industry Proposed at 100%	Total Increase	Industry Less Than Proposed	
Transportation	\$ 4,189		\$ 675	\$ 8,240	\$ 4,051	\$ 6,215	\$ 2,026	\$ (2,025)	-25%
Fire	-	163		489	489	-	-	(489)	-100%
Police	-	69		206	206	-	-	(206)	-100%
Parks	-	-		-	-	-	-	-	n/a
Municipal Services	-	157		471	471	-	-	(471)	-100%
Total	\$ 4,189			\$ 9,406	\$ 5,217	\$ 6,215	\$ 2,026	\$ (3,191)	-34%



HOUSING AND BUILDING
ASSOCIATION
of
WESTERN COLORADO



August 12, 2019

Mr. Greg Caton, City Manager
250 N. 5th Street
Grand Junction, CO 81501

RE: Current position on Proposed Impact Fees

The stakeholder groups that have participated in the current discussion of Impact fees for Grand Junction which includes the Grand Junction Chamber of Commerce, Western Colorado Contractors Association, Grand Junction Area Realtors Association, Association Members for Growth and Development, and the Homebuilders Association of Western Colorado have appreciated the collaborative nature of our meetings with you and other city staff to discuss and work at refining the development fees that will help the city address the need for building infrastructure capacity while not stymieing growth and economic development.

Recognizing that many residential and commercial projects are competitive in nature this stakeholder group commissioned a comparison of six cities in an attempt to as closely as possible compare current fees. That comparison is attached and we would ask that you share it and this letter with the City Council at your August 19th briefing during the Council Workshop.

In essence, the study concluded that Grand Junction is currently 52% above average on development fees for a single-family residence and 27% higher than the average on a commercial office project when compared to the five other selected cities. It is important to note that this is based on current fees and does not include the city's proposal for increasing the traffic capacity payment fees and park fees along with adding new impact fees for fire, police and facilities. It also does not include the proposal for more off-

site improvement costs being borne by the developer. In other words, we are already on the threshold of being much higher than our comparison cities with **no fee increases**.

The stakeholder group considers it important for policy decision makers to consider the following:


- There are additional revenues via sales, use and property taxes that the city will receive from the economic activity generated by new development that were not considered by the consultant study that recommended the increases in fees and levying of new fees. The National Realtor Association for example, has estimated that every new single-family home adds two jobs and \$80,000 to an area's economy.
- Any increase in fees is ultimately borne by the homeowner or business owner as those costs are passed through to them by the developer which makes housing costs and business expansions more expensive. The Grand Junction Area Realtors Association has estimated that just 37% of Mesa County residents can currently afford a median priced home at the rate of \$250,000.
- Area wages have been increasing for the past two year but are still substantially below those of other areas in Colorado. The most recent comparison from the Mesa County Workforce Center indicated that between third quarter of 2017 and third quarter of 2018 (most recent data available) the average wage increased a modest 4% to \$854 per week. Such wages coupled with the increased fees for residential development will make housing even more unaffordable for the city's residents.
- According to information from Elizabeth Peetz, Government Affairs Director, Colorado Association of Realtors as of May 2019 **32,000 households on the Western Slope** are weighed down by the cost of housing which means they are already paying more that 30% of their income for housing. This includes renters.
- Representatives of the development community have asked that all fees be brought to the table for consideration. However, a proposed increase in water tap fees was only introduced to them in July and were not factored into our other discussions. It is our understanding that the proposal will take current tap fees from \$1,000 to over \$5,000 for the smallest tap fee on nonresidential projects.

As a result of our meetings and the additional information that we have been able to gather along with recognizing the need for increased

infrastructure capacity and an environment that does not stifle growth our organizations are proposing the following:

- Implement 50% of proposed increase in TCP (transportation capacity payment) fees for residential developments and commercial developments that were presented and agreed to during Discussion Meeting #4 on July 29th over a 3-year schedule. At that time once again review the fee to determine if adjustments should be made. This will increase fees to a manageable level acceptable by the development community without halting progress. The review will help allow for adjustments based on current market prices and needs.
- Implement 50% of the proposed fee increase for parks presented at Discussion Meeting #4 on July 29th over the next three years with a review and recommendation back to Council at the end of that period regarding fee adjustments.
- Do not implement any new fees (i.e. fire, police and facilities) at this time.


Thank you for your continued collaboration on this proposal and the consideration of the suggested solution by the collective stakeholders in Grand Junction.



Housing and Building Association of Northwest Colorado



Grand Junction Chamber of Commerce



Grand Junction Area Realtors Assn.



Western Colorado Contractors Association



Associated Members for Growth and Development



GRAND JUNCTION DEVELOPMENT IMPACT FEE COMPARATIVE ANALYSIS

GRAND JUNCTION, COLORADO

PREPARED FOR:

GRAND JUNCTION AREA REALTOR ASSOCIATION

August 6, 2019

Metrostudy | A Hanley Wood company

Denver Colorado Office

9033 East Easter Place, Suite 116

Centennial, CO 80112

www.metrostudy.com

Phone: 720.493.2020 Fax: 720.493.9222

August 6, 2019

Mrs. Diane Schwenke
Grand Junction Area Realtor Association
2743 Crossroads Blvd
Grand Junction, CO 81506

RE: Grand Junction Development Impact Fee Comparative Analysis ("Analysis")

Dear Mrs. Schwenke:

Metrostudy is pleased to present this Analysis of the development impact fees for comparative municipalities to the City of Grand Junction, Colorado. We have provided a detailed analysis of the development impact fees as well as accompanying demographic and housing, and mill levy and tax information on the following pages and Appendix for the Grand Junction Area Realtor Association ("Client"). This Analysis was conducted by Steven Saules, Manager. Metrostudy has been engaged in analyzing residential market conditions with its proprietary lot-by-lot survey nationally since 1975, and locally within the state of Colorado since 2001.

Please contact us at your convenience with any comments or questions regarding this Analysis, or with any other matters relevant to your real estate market research needs.

Respectfully Submitted,

Metrostudy

metrstudy

The following Grand Junction Development Impact Fee Comparative Analysis included herein summarizes the total estimated development impact fees associated with the new construction of two (2) property types ("Property Types") within the City of Grand Junction, Colorado ("City"), as well as within five (5) comparative Colorado municipalities. The Property Types include a 2,000 square foot single-family detached home and a 10,000 square foot single-structure office building. The five municipalities include the Town/City of Fruita, Montrose, Gunnison, Pueblo, and Sterling, Colorado (collectively the "Municipalities"). The development impact fees are collected for capital infrastructure items categorized for; however, not limited to police, fire, school, transportation, parks and recreation, public safety, etc., as well as those development impact fees pertaining to water and sewer plant investment fees exclusive of raw water rights (collectively the "DIFs"). The current Municipality DIFs are summarized in **Table-1** of the Analysis, while the detailed analysis for both Property Types is shown in **Table-2** and in **Table-3** on the following pages.

The current DIFs included in this Analysis are based on estimates and calculations derived from the applicable Municipalities' 2019 or most current fee schedules and Municipality provided data. The DIFs were affirmed through multiple iterations of research and conversations with Municipality staff and associated external entities.

Additionally, Metrostudy has reviewed and provided accompanying demographic and housing, and mill levy and tax information in order to further the Client's understanding of how the Municipalities' DIFs truly compare within the context of additional housing market affordability factors. Certain DIFs shown in the Analysis required different calculations depending on the Municipality.

Finally, the assumptions upon which all DIFs in this Analysis were estimated is shown by Product Type in **Exhibit-A**, while a map of the Municipalities' locations is detailed in **Exhibit-B** of the Appendix. As shown below, the DIFs associated with the construction of a new 2,000 square foot single-family detached home, and a new 10,000 square foot office building in Grand Junction are approximately 52.8 percent and 27.3 percent higher than that of the average of the comparative Municipalities, respectively.

Table-1: Summary of Total Development Impact Fees by Municipality

<i>Total Development Impact Fees (\$)</i>	<i>Fruita</i>	<i>Montrose</i>	<i>Gunnison</i>	<i>Pueblo</i>	<i>Sterling</i>	<i>Average</i>	<i>Grand Junction</i>	<i>Difference (%)</i>
<u>Single-Family Detached</u>								
<i>Metric: \$/unit</i>								
Total (\$)	23,315	11,554	7,500	8,227	5,040	11,127	17,000	52.8%
<u>Office</u>								
<i>Metric: \$/building</i>								
Total (\$)	53,903	14,200	13,500	9,800	7,623	19,805	25,216	27.3%

Source: Municipality/DPFG

Table-2: Single-Family Detached Development Impact Fee Detailed Analysis (\$/unit)

Development Impact Fees*	Fruita**	Montrose***	Gunnison	Pueblo****	Sterling*****	Average	Grand Junction*****	Difference
<u>Demographics and Housing</u>	1	1	1	1	1		1	
Population	13,463	20,328	6,602	111,368	11,271	27,505	59,121	-
Households	5,035	8,300	2,583	45,209	4,867	13,199	24,495	-
Median Household Income (\$)	56,018	44,801	45,219	37,453	39,519	44,602	48,844	-
Average New Home Price (All) (\$)	372,509	299,771	299,000	263,409	251,579	297,254	311,739	-
Annual Income to Home Price	15.0%	14.9%	15.1%	14.2%	15.7%	15.0%	15.7%	4.4%
<u>Annual Taxes</u>	2	2	2	2	2		2	
Mill Levy	82.2370	70.2120	55.1480	88.7630	77.4420	74.7604	69.3920	-
Average New Home Price (All) (\$)	372,509	299,771	299,000	263,409	251,579	297,254	311,739	-
Annual Taxes (\$)	2,206	1,515	1,187	1,683	1,403	1,600	1,558	-
Annual Taxes to Home Price	0.59%	0.51%	0.40%	0.64%	0.56%	0.54%	0.50%	-7.2%
<u>Development Impact Fees (\$)</u>	3,4,5	6,7	8	9,10,11	12		5,13,14	
Chip and Seal	80	-	-	-	-	-	-	-
Drainage	1,706	-	-	-	-	-	-	-
Inspection	-	-	-	-	-	-	-	-
Police	-	1,000	-	-	-	-	-	-
Parks, Open Space and Trails	1,860	1,575	-	-	-	-	-	-
Public Safety Fee	-	-	-	740	-	-	-	-
School	920	679	-	-	-	-	920	-
Transportation, Street, Road	3,200	1,500	-	-	-	-	2,554	-
Water Plant Investment Fees	8,750	2,635	2,500	5,747	2,690	-	8,750	-
Sewer Plant Investment Fees	6,800	4,165	5,000	1,740	2,350	-	4,776	-
Total Per Unit	23,315	11,554	7,500	8,227	5,040	11,127	17,000	52.8%
<u>School District</u>	<i>Mesa County Valley 51</i>	<i>Montrose County RE-1J</i>	<i>Gunnison Watershed RE1J</i>	<i>Pueblo City 60</i>	<i>RE-1 Valley</i>		<i>Mesa County Valley 51</i>	-
Fee	-	-	-	-	-	-	-	-
Source	Diana Sirko 970-254-5100	Laurie Laird 970-252-7902	Leslie Nichols 970-641-7770	Dave Homer 719-549-7113	Jan Delay 970-522-0792	-	Diana Sirko 970-254-5100	-
<u>Fire District</u>	<i>Lower Valley Fire Protection</i>	<i>Montrose Fire Protection</i>	<i>Gunnison Volunteer Fire Dept.</i>	<i>Pueblo Fire Dept.</i>	<i>Sterling Fire Dept.</i>		<i>Grand Junction Fire Dept.</i>	-
Fee	-	-	-	-	-	-	-	-
Source	Frank Cavaliere 970-858-3133	Lindsey Wiley 970-249-9181	Eric Jansen 970-641-8090	James Riddell 719-553-2830	Levon Ritter 970-522-3823	-	Ken Watkins 970-549-5801	-
<u>Police District</u>	<i>Fruita City Police Dept.</i>	<i>Montrose Police Dept.</i>	<i>Gunnison Police Dept.</i>	<i>Pueblo Police Dept.</i>	<i>Sterling Police Dept.</i>		<i>Grand Junction Police Dept.</i>	-
Fee	-	-	-	-	-	-	-	-
Source	Glenda Willis 970-858-3008	Tim Cox 970-252-5200	Keith Robinson 970-641-8200	Troy Davenport 719-553-2420	Tyson Kerr 970-522-3512	-	Doug Shoemaker 970-242-6707	-
Total DIF Per Unit	23,315	11,554	7,500	8,227	5,040	11,127	17,000	52.8%
DIF to Home Price	6.3%	3.9%	2.5%	3.1%	2.0%	3.5%	5.5%	53.6%

Source

- (1) Metrostudy, Property Analysis, Steven Saules - 720-493-2020
- (2) County GIS mapping system and Colorado Department of Local Affairs
- (3) Fruita, Planning, Henry Hemphill - 970-858-0786
- (4) Fruita, Engineering, Sam Atkins - 970-858-8377
- (5) Ute Water Conservancy District, Jim Daugherty - 970-242-7491
- (6) Montrose, Planning, Archie Byers - 970-240-1437
- (7) Montrose, Engineering, Scott Murphy - 970-240-1498
- (8) Gunnison, Building, Eric Jansen - 970-641-8090
- (9) Pueblo, Planning, Alan Lamberg - 719-553-2241
- (10) Pueblo, Land Use, Scott Hobson - 719-553-2244
- (11) Pueblo, Board of Water Works, Rhonda Navarette - 719-584-0270
- (12) Sterling, Public Works, George Good - 970-522-9700
- (13) Grand Junction, Community Development, Lance Gloss - 970-244-1422
- (14) Grand Junction, Residential Sewer, Amy Castaneda - 970-256-4027
- (15) Grand Junction, Commercial Water/Sewer, Debi Overholt - 970-244-1520

Footnotes (residential)

*DIFs may vary by subdivision or subdivision filing within each jurisdiction. Metrostudy has included all known DIFs regardless of their inclusions or exclusions across subdivisions. Metrostudy has only utilized neighborhood specific DIFs when DIFs are not uniform across the municipality. Neighborhood or development agreement specific DIFs, DIF waivers, land dedication requirements, and/or DIF credits may impact actual DIFs within each jurisdiction. DIFs do not include facility fees where developers may be partially reimbursed from builders for initial upfront infrastructure investments. Water and sewer plant investment fees do not include additional acquisition costs for raw water rights. Any applicable landscaping/irrigation costs are based on T-ing off of the main water line. Residential home sales prices based on 7/1/2018 to 6/30/2019 time period. Colorado residential assessment rate of 7.20% and Municipality mill levy rates are based on 2018 figures. DIFs may be collected at time of annexation, platting, planning approvals, building permit issuance, certificate of occupancy, or other.

** (Fruita) Chip and seal DIFs based on actual costs for Brannon Estates Filing 2C with 10 lots. Drainage DIFs (\$17,060 across 10 lots) are shown above; however, were exempted from Brannon Estates due to developer funding of detention ponds. DIFs payable at time of planning approval for issuance of building permit.

*** (Montrose) Transportation DIFs based on building permit fee estimate for Estates of Stone Ridge Filing 2. Park DIFs were exempted from the development due to developer land dedication, which is standard. DIFs payable at time of building permit issuance. Police DIFs were not confirmed with documents but over the phone at approximately \$1,000 per unit/lot.

**** (Pueblo) At subdivision platting there is park dedication requirement of 8% of land (excluding right of way); however, most projects in recent times have dedicated land. City mitigates DIF costs by utilizing a facility fee. DIFs negotiated at annexation and apply only to those properties being annexed into the City. Transportation Department may assess traffic DIFs when a new building triggers new traffic signals, signs and/or pavement markings required by a subdivision improvement agreement (SIA); however, there are not recent examples that the municipality can provide. Public Safety DIFs based on 0.37 cents per square foot of residential structure.

***** (Sterling) Park and/or street site requirements are development specific; requirements are not payments in lieu of DIFs.

***** (Grand Junction) Transportation DIFs may be deferred prior to the issuance of a certificate of occupancy. DIFs payable at time of planning approval for issuance of building permit.

Table-3: Office Development Impact Fee Detailed Analysis (\$/building)

Development Impact Fees*	Fruita**	Montrose***	Gunnison	Pueblo****	Sterling*****	Average	Grand Junction*****	Difference
<u>Demographics</u>	1	1	1	1	1		1	
Population	13,463	20,328	6,602	111,368	11,271	27,505	59,121	-
Households	5,035	8,300	2,583	45,209	4,867	13,199	24,495	-
<u>Mill Levy</u>	2	2	2	2	2		2	
Mill Levy	82.2370	70.2120	55.1480	88.7630	84.6600	-	74.8040	-
Total	82.2370	70.2120	55.1480	88.7630	84.6600	76.2040	74.8040	-1.8%
<u>Development Impact Fees (\$)</u>	3,4,5	6,7	8	9,10,11	12		13,15	
Chip and Seal	-	-	-	-	-	-	-	-
Drainage	17,058	-	-	-	-	-	-	-
Inspection	-	-	-	-	-	-	550	-
Police	-	-	-	-	-	-	-	-
Parks, Open Space and Trails	-	-	-	-	-	-	-	-
Public Safety Fee	-	-	-	1,060	-	-	-	-
School	-	-	-	-	-	-	-	-
Transportation, Street, Road	19,545	-	-	-	-	-	18,640	-
Water Plant Investment Fees	10,500	4,140	4,500	5,830	3,940	-	1,250	-
Sewer Plant Investment Fees	6,800	10,060	9,000	2,910	3,683	-	4,776	-
Total Per Unit	53,903	14,200	13,500	9,800	7,623	19,805	25,216	27.3%
<u>School District</u>	<i>Mesa County Valley 51</i>	<i>Montrose County RE-1J</i>	<i>Gunnison Watershed RE-1J</i>	<i>Pueblo City 60</i>	<i>RE-1 Valley</i>		<i>Mesa County Valley 51</i>	-
Fee	-	-	-	-	-	-	-	-
Source	Diana Sirko 970-254-5100	Laurie Laird 970-252-7902	Leslie Nichols 970-641-7770	Dave Homer 719-549-7113	Jan Delay 970-522-0792	-	Diana Sirko 970-254-5100	-
<u>Fire District</u>	<i>Lower Valley Fire Protection</i>	<i>Montrose Fire Protection</i>	<i>Gunnison Volunteer Fire Dept.</i>	<i>Pueblo Fire Dept.</i>	<i>Sterling Fire Dept.</i>		<i>Grand Junction Fire Dept.</i>	-
Fee	-	-	-	-	-	-	-	-
Source	Frank Cavaliere 970-858-3133	Lindsey Wiley 970-249-9181	Eric Jansen 970-641-8090	James Riddell 719-553-2830	Levon Ritter 970-522-3823	-	Ken Watkins 970-549-5801	-
<u>Police District</u>	<i>Fruita City Police Dept.</i>	<i>Montrose Police Dept.</i>	<i>Gunnison Police Dept.</i>	<i>Pueblo Police Dept.</i>	<i>Sterling Police Dept.</i>		<i>Grand Junction Police Dept.</i>	-
Fee	-	-	-	-	-	-	-	-
Source	Glenda Willis 970-858-3008	Tim Cox 970-252-5200	Keith Robinson 970-641-8200	Troy Davenport 719-553-2420	Tyson Kerr 970-522-3512	-	Doug Shoemaker 970-242-6707	-
Total DIF Per Building	53,903	14,200	13,500	9,800	7,623	19,805	25,216	27.3%

Source

- (1) Metrostudy, Property Analysis, Steven Saules - 720-493-2020
- (2) County GIS mapping system and Colorado Department of Local Affairs
- (3) Fruita, Planning, Henry Hemphill - 970-858-0786
- (4) Fruita, Engineering, Sam Atkins - 970-858-8377
- (5) Ute Water Conservancy District, Jim Daugherty - 970-242-7491
- (6) Montrose, Planning, Archie Byers - 970-240-1437
- (7) Montrose, Engineering, Scott Murphy - 970-240-1498
- (8) Gunnison, Building, Eric Jansen - 970-641-8090
- (9) Pueblo, Planning, Alan Lamberg - 719-553-2241
- (10) Pueblo, Land Use, Scott Hobson - 719-553-2244
- (11) Pueblo, Board of Water Works, Rhonda Navarette - 719-584-0270
- (12) Sterling, Public Works, George Good - 970-522-9700
- (13) Grand Junction, Community Development, Lance Gloss - 970-244-1422
- (14) Grand Junction, Residential Sewer, Amy Castaneda - 970-256-4027
- (15) Grand Junction, Commercial Water/Sewer, Debi Overholt - 970-244-1520

Footnotes (office)

- *DIFs may vary by area or filing within each jurisdiction. Metrostudy has included all known DIFs regardless of their inclusions or exclusions across areas. Metrostudy has only utilized location specific DIFs when DIFs are not uniform across the municipality. Development agreement specific DIFs, DIF waivers, land dedication requirements, and/or DIF credits may impact actual DIFs within each jurisdiction. Does not include facility fees. Water and sewer plant investment fees do not include additional acquisition costs for raw water rights. Any applicable landscaping/irrigation costs are based on T-ing off of the main water line. Colorado mill levy rates are based on 2018 figures. DIFs may be collected at time of annexation, platting, planning approvals, building permit issuance, certificate of occupancy, or other.
- **(Fruita) DIFs payable at time of planning approval for issuance of building permit. The base rate for transportation DIFs for a 10,000 square foot commercial office buildings is \$1,589 per 1,000 square feet multiplied by a 1.23 factor.
- *** (Montrose) Park and/or street site requirements are development specific; requirements are not payments in lieu of DIFs.
- **** (Pueblo) Drainage DIFs have the potential to exist; however, recent projects reviewed by the municipality have mitigated these costs by developer management of drainage slope on site as opposed to entering into discussions of associated DIFs; this form/process is expected to continue. Public Safety DIFs based on 0.106 cents per square foot of commercial structure.
- ***** (Sterling) Park and/or street site requirements are development specific; requirements are not payments in lieu of DIFs.
- ***** (Grand Junction) Commercial DIFs are project specific. Commercial sewer fees were estimated based on 20 employees and 500 square feet of space per employee. Transportation DIFs may be deferred prior to the issuance of a certificate of occupancy and are based on \$1,864 per 1,000 square feet. DIFs payable at time of planning approval for issuance of building permit.

Disclaimer:

The development impact fees shown in this Analysis will vary depending on a multitude of factors, including; however, not limited to development timing, specific municipality and/or subdivision and/or subdivision phase/filing, school/fire/police jurisdictions development impact fee collection procedures, project size and square feet/acreage, number of units or buildings, water and sewer line requirements, landscaped area and/or necessity for additional water lines, impervious area, etc. The development impact fees shown in the Analysis were based on the Municipalities 2019 or most recent fee schedule, which may not be revised after the production of this Analysis. This Analysis did not consider timeline and upcoming changes to the development impact fees shown.

It is understood by the Client that Metrostudy can make no guarantees about the findings and/or recommendations in this Analysis. To protect the Client and to assure that Metrostudy's research results will continue to be accepted as objective and impartial by the business community, Metrostudy's fee for this Study is in no way dependent upon the specific conclusions reached or the nature of the advice given in this Analysis.

Reasonable efforts have been made to ensure that the data contained in this Analysis reflect the most accurate and timely information possible and are believed to be reliable. This Analysis is based on estimates, assumptions, and other information developed by Metrostudy from its independent research effort, general knowledge of the industry and consultations with the Client and its representatives. No responsibility is assumed for inaccuracies in reporting by the Client, its agents and representatives or any other data source used in preparing or presenting this Analysis. This Analysis is based on market-wide information that was current as of the production of the Analysis. While every reasonable effort was made to collect this information and it is deemed reliable, it cannot be guaranteed for accuracy. Metrostudy makes no warranty or representation that any of the estimated values or results in this Study will be achieved, and actual results will vary depending on project and development specific details.


Appendix:

Exhibit A: Development Impact Fee Assumptions

Assumptions	Single-Family Detached	Office
Square Feet	2,000	10,000
Project Acres	0.25	0.50
Project Impervious Percent	50%	90%
Water Tap Size	3/4"	1"
Project Address / Location		
Fruita	1518 Myers Ln, Fruita, CO 81521	1672 Highway 6 50, Fruita, CO 81521
Montrose	3400 Ridgeline Dr, Montrose, CO 81401	1546 E Oak Grove Rd, Montrose, CO 81401
Gunnison	1499 W Gunnison Ave, Gunnison, CO 81230	499 W Georgia Ave, Gunnison, CO 81230
Pueblo	5601 Bellagio Way, Pueblo, CO 81005	718 W 6th St, Pueblo, CO 81003
Sterling	832 Nicole Rd, Sterling, CO 80751	218 N 2nd St, Sterling, CO 80751
Grand Junction	554 Crestwood Ave, Grand Junction, CO 81504	398 I-70BL, Grand Junction, CO 81501

Source: Municipality/Metrostudy

Exhibit B: Development Impact Fee Municipality Map



This Analysis was prepared by Metrostudy, a consulting firm and the nation's leading provider of primary and secondary market information to the housing, retail, and related industries nationwide.



CONTACT INFORMATION

Tom Hayden

Director of Consulting – Western U.S.

Denver Office:

9033 East Easter Place, Suite 116

Centennial, Colorado 80112

(720) 493-2020

thayden@metrostudy.com

www.metrostudy.com

John Covert

Regional Director – Colorado / New Mexico

Denver Office:

9033 East Easter Place, Suite 116


Centennial, Colorado 80112

(720) 493-2020


jcovert@metrostudy.com

www.metrostudy.com

TCP FEE INCREASE PROPOSALS



PERCENTAGE OF INCREASE OF PROPOSED TCP FEES



All fees are for single-family detached units of any size unless																	
Communities	General Government	Police		Parks & Recreation		Schools	Transp.	Storm Drainage		Fire	Trails	Water		Sewer		Fire District	Recreation District
Aurora	\$189	\$94		\$240			\$589	\$1,242	per acre	\$92		\$0	[3]	\$550		No	No
Aurora - 2019#	\$235	\$116		\$1,901			\$612	\$115								No	No
Castle Rock - 2019(Single family housing unit of 2,500 sq ft)	\$355	\$542		\$3,720			\$7,004	\$1,098								No	No
Castle rock (Single-family detached or attached unit of 2,000-2,499 sq ft)	\$325	\$497		\$3,406			\$7,004	\$843		\$1,005						No	No
Fort Collins	\$523	\$220		\$1,743			\$3,112	\$1,548	[4]	\$440		\$730 + \$0.36 per sq ft of lot area	[5]	\$3,537		Yes 10.95 mills	No
Glenwood Springs**				\$5,775		\$2,471				\$1,290		\$5,004	[6]	\$5,380		No	No
Golden ##												\$20,742		\$3,486		No	No
Greeley (Single-family residence)	-	\$135		\$3,131			\$4,194	\$392		\$603	\$434	\$10,800	[1]	\$5,700	[2]		
Littleton - 2019	\$1,904	\$399		-			\$1,049	\$1,170								Yes 9.25 mills	Yes 8.496 mills
Lone Tree - 2018, TischlerBise Proposed Fee*	\$1,152	\$619		\$7,286			-	-								Yes 9.25 mills	Yes 8.496 mills
Longmont (For any residential unit between 1,601-2,400 sq ft)				\$6,962	[10]		\$1,746	\$923								No	No
Montrose %		\$919	[8]	\$1,575		\$679						\$1,882	[9]	\$3,889	[9]	Yes 8.56 mills	Yes 4.5 mills
Parker - 2019 Max Supportable Fee	\$381	\$387		\$5,289			\$3,063	\$293									
Westminster				\$1,993		\$876						\$15,039	[7]	\$5,733	[7]	No	No

Sources: Fees have been gathered from localities' websites and studies

[1], [2], [5] 'Plant Investment Fee' based on 3/4" tap size for residential units

[3] Water transmission development fee for extension of water transmission facilities is included in the water service connection fee; water connection fee = \$6100 for single-family detached units of 1-2 bathrooms, not including half baths

[4] Example fee for a single-family unit with lot soze or 8,600 sq ft plus 6,156 sq ft of common area. This 'Plant Invertment Fee' is based on a base rate of \$9,142 per gross acre

[6] Fee for 1 EQR, or the equivalent of a single-family unit up to 3BR and 2BA in size.

[7] Fees for single-family detached units with < 4 BR; fee includes treatment and transportation costs, but does not include connection charge

[8] Known as the City Operations and Police Services (COPS) Fee - to be used for both general government and police services

[9] Capacity charge, but does not include connection fee

[10] Combination of Recreation Buildings Fee (\$1086.85) and Parks Improvement Fee (\$8573.83)

* The fees listed for the City of Lone Tree


** Impact fees passed by Council

Most recent development fee schedule is from January 1, 2014

% Does not adopt impact fees in according to Colorado statue requirements; so the fees are not technically impact fees

Park Development Fee calculated as the fee-in-lieu option for park development. All fees listed are assessed on

Annual Sales Tax Increase per Annual Housing Unit Increase



CITY OF GRAND JUNCTION

ORDINANCE NO. ____

AN ORDINANCE AMENDING ORDINANCE NO. 3641 CONCERNING GROWTH AND DEVELOPMENT RELATED STREET POLICY

Recitals:

Safe and efficient streets are one of the most important services provided by the City, the City Council finds and determines that it is proper to provide a specific financing mechanism that will continue to allow safe and functional streets and for new growth and development to pay its way to an equitable degree.

The Council further determines that the resources of the City are properly allocated to maintaining and improving, including capital additions to, the existing streets and roads and those annexed over time, as resources permit, together with additional improvements to the system near and around developing areas of the City. The citizens and users of the street system pay for the upkeep and general improvement to the system by the payment of sales and use taxes. Sales and use taxes are not sufficient, however, to pay for all the road needs and there are limited resources available to the City, from other sources, to add to the system and/or to make improvements in the rapidly developing areas of the City.

The Council has found and affirms that an equitable method of imposing a portion of the costs of paying for additional or improved capacity, necessitated because of Growth, and promoting safe and effective access to and from new developments to the public street system is best addressed by requiring developers to pay for and install public right-of-way improvements that are required for such safe and effective access.

BE IT ORDAINED BY THE CITY COUNCIL OF THE CITY OF GRAND JUNCTION THAT ORDINANCE NO. 3641 AMENDED AS SHOWN: (For text, deletions are ~~struckthrough~~ and additions are underlined; for graphics, deletions are crossed through with an X.)

Growth and Development Related Street Policy

~~The City of Grand Junction requires that new development pay a Transportation Capacity Payment to help defray the cost to the City for the impact of development on City streets. The City has experienced steady growth for over a decade and during that time has struggled with how to fairly collect and administer impact fees assessed against development, how to credit some or all of those fees against taxes otherwise paid and what, if any, role the City should have in funding/contributing to the cost of providing additional traffic/street capacity and/or traffic/street capacity in accordance with community expectations.~~

~~The City has determined that there are three key components to a meaningful growth and development related street/traffic policy. They are:~~

- ~~— 1. Collection of a realistic TCP for all new development projects. The TCP shall be annually reviewed and adjusted in accordance with 6.2B2d of the ZDC.~~
- ~~— 2. A clear articulation of what minimum requirements (in addition to the TCP) each development must construct; and~~
- ~~— 3. City funding and/or other means of participation in construction of street improvements.~~

~~Because the City has determined that traffic is a community problem, the TCP shall be uniform throughout the City and subject to criteria stated below; funding may be provided to street improvements anywhere within the City.~~

~~The principles of this policy are:~~

- ~~1. All development projects that create a traffic impact, as defined by the City ZDC, shall pay a TCP as established by and in accordance with the ZDC. The fundamental precept of the City's TCP policy is that new development must pay its fair share for the added traffic that development creates.~~
- ~~2. The TCP fee has been set to ensure that trips from each new development are calculated and that the developer contributes to the value of _____ capacity consumption of City streets in proportion to the traffic that the development is reasonably anticipated to generate. The fee also recognizes as a credit the value of taxes generated from development.~~
- ~~3. TCP funds are intended to be used for improvements to the major roadway system as identified on the most current version of the Grand Valley Circulation Plan functional classification map (Minor Collector or above). Improvements to the local roadway system will continue to be the responsibility of the property owners abutting the local roadway. The TCP fee is not intended to be used for debt service for the Riverside Parkway project.~~
- ~~4. Minimum Street Access Improvements -- The intent of this section is to describe the improvements necessary to connect a proposed development to the existing street system. SUCH IMPROVEMENTS SHALL BE PUBLIC IMPROVEMENTS AND SHALL BE THE MAINTENANCE RESPONSIBILITY OF THE CITY WHETHER SUCH PUBLIC IMPROVEMENTS ARE IDENTIFIED THROUGH A TRAFFIC STUDY OR OTHERWISE MADE A CONDITION OF APPROVAL FOR DEVELOPMENT. Construction of these improvements will be the responsibility of the developer and shall be constructed or guaranteed at the time of development. These improvements are needed to provide safe ingress/egress and shall meet the minimum standards in Section CHAPTERS 5 AND 6 AND THE UNNUMBERED CHAPTER ENTITLED Fire Department Access of the TEDS Manual -- Fire Department Access. These improvements are not intended to include off-site, Half Street or perimeter improvements necessary to increase the capacity or improve the safety of adjacent or perimeter streets.~~
 - ~~• Absent unique needs or characteristics of the development, Minimum Street Access Improvements shall mean construction of full asphalt radii, and necessary drainage improvements in accordance with the City standard detail for each intersection with a perimeter street and/or improvements necessitated if the proposed development creates lots with direct access to the perimeter street(s) as determined by the Director. An owner or developer may appeal a determination of Minimum Street Access Improvements to the Transportation Engineering Design Standards (TEDS) Exception~~

~~Committee. That Committee consists of the PW&U Director, the Fire Chief and the Community Development Director.~~

- ~~• Curb, gutter and sidewalk improvements shall be constructed as part of minimum access improvements when connecting directly to a street with like improvements.~~
- ~~• The City's multi-modal plan, including bike lanes, trails, paths, alternate pedestrian connections and bus stops and transit shall be incorporated into determining what improvements are required associated with a connection to the adjacent street system.~~
- ~~• Right of Way – The development shall dedicate necessary ROW (per Code and TEDS) to provide safe ingress/egress to the proposed development.~~
- ~~• Drainage Structures including Bridges – The development shall construct drainage structures and/or bridges associated the connection of the development to the street system.~~
- ~~• Traffic Studies – Preparation of Traffic Studies shall be the responsibility of new development as currently defined by the Code.~~
- ~~• Utilities – The extension of utilities including water, sewer, storm water improvements gas, electric, cable and telephone, etc will continue to be the responsibility of new development.~~

~~5. In addition to the TCP and Minimum Street Access Improvements, the developer must fully construct (or if current needs do not require construction, then the developer must guarantee for future construction) all internal streets, roads, alleys, and future connections in accordance with the development's approved plan.~~

~~6. The developer is responsible for the cost of the design of all features of the Minimum Street Access Improvements as required by TEDS, the GVCP, and other applicable City code(s), ordinance(s), policy(ies) or resolution(s).~~

~~7. Reimbursable Street Expenses – In the event a development triggers the need for public improvements beyond available City funding from the TCP, the City and the developer may enter into an agreement that would provide for the reimbursement of a portion of the costs of the public improvements.~~

~~Safe and adequate streets are a priority for the City. To help meet that need, a fund will be established to allow the City to fund and/or partner with developers or other governments. City funding or participation in street improvements shall be used for three purposes:~~


~~1. Construction of larger scale improvements along corridors which are deficient in street improvements (i.e., capacity, safety or physical improvements including pavement, curbs, gutters, and sidewalks).~~

~~2. Specific street or intersection improvements either adjacent or off-site from a new development where the existing condition is deficient as defined by City code.~~

~~3. Participation in a larger regional project in cooperation with the participating agencies of the Grand Valley MPO.~~

~~City funding and/or other means of participation in street improvements is conditioned on:~~

- ~~• Construction will improve traffic safety;~~
- ~~• Construction will improve traffic flow;~~
- ~~• Construction will improve pedestrian safety;~~
- ~~• Construction will improve capacity.~~



MINIMUM STREET ACCESS INCLUDES

- ♦ CULVERT/CANAL CROSSING TO ACCOMMODATE DEVELOPMENT NEEDS (TRAFFIC STUDY). IF LESS THAN LENGTH REQUIRED FOR ULTIMATE STREET SECTION, CITY MAY CONTRIBUTE TO COMPLETE THE LENGTH.
- ♦ FIRE ACCESS IMPROVEMENTS BETWEEN COLLECTOR AND STORE ACCESS (MIN. 20' OF PAVEMENT WIDTH, OR GREATER AS REQUIRED BY THE TRAFFIC STUDY. DOES NOT INCLUDE CURB, GUTTER OR SIDEWALK, UNLESS NECESSARY FOR TRANSITION WITH EXISTING).
- ♦ DEDICATION OF R.O.W. PER DEVELOPMENT NEEDS OR PER MAJOR STREET PLAN, WHICH EVER IS GREATER.
- ♦ DRAINAGE IMPROVEMENTS AS NECESSARY.

CITY OF GRAND JUNCTION BUILDS


- ♦ TRAFFIC SIGNAL
- ♦ DECELERATION LANE


DRAWN BY: JAH
 DATE: 6-10-2004
 SCALE: N.T.S.
 APPR. BY: T.M.
 FILE NO. EXAMPLE.DWG

PUBLIC WORKS & UTILITIES
 ENGINEERING DIVISION

EXAMPLE 1

CITY OF
Grand Junction
 COLORADO





This Ordinance shall be effective on January 1, 2021.

Introduced on first reading this _____ day of March 2019.

PASSED and ADOPTED and ordered published in pamphlet form this _____ day of _____ 2019.

President of the Council

Barbara Traylor Smith

Attest:

Wanda Winkelmann, City Clerk

CITY OF GRAND JUNCTION

ORDINANCE NO. 3641

AN ORDINANCE AMENDING ORDINANCE NO. 2750 AS CODIFIED AS SECTION 6.2 OF THE GRAND JUNCTION ZONING AND DEVELOPMENT CODE CONCERNING TRANSPORTATION CAPACITY PAYMENTS INCLUDING CALCULATIONS THEREOF, CREDITS AND APPROVED METHODOLOGIES

Recitals:

The existing City ordinances require that a developer of land adjacent to a right-of-way which is unimproved or does not meet current standards ("under-improved") either improve the abutting half of the right-of-way for the frontage of the development or pay a sum of money determined by an assumption of additional traffic that will be created from the development. Also, current City policy allows the City to require additional improvements to the existing roadway system when it is determined that the proposed development has negative impacts to the capacity and/or safety of the existing system.

While this method assures that a development pays its fair share of the cost of the associated impact to the transportation system, there has been concern raised that this method of addressing traffic impacts is not always fair. This method has the disadvantage of requiring the first development in an area of under-improved public infrastructure to complete these improvements but allows others, who follow later, to develop without similar costs.

Another disadvantage is that a developer of land immediately adjacent to one or more unimproved or under-improved streets may be required to pay for the improvement of all adjacent street improvements, yet another development, due to location or the configuration of the parcels such that it does not abut an unimproved street, may not be required to make the same improvements to the street system, even though each development may add the same amount of traffic.

Because safe and efficient streets are one of the most important services provided by the City, the Council does hereby amend the Code to provide a specific financing mechanism, which will continue to allow safe and functional streets while refining the calculation of payment for and costs attributable to development.

The Council determines that the resources of the City are properly allocated to maintaining and improving, including capital additions to, the existing 370 miles of streets and roads and that, as resources permit, additional improvements to the system should be made near and around developing areas of the City as growth occurs. The citizens and users of the street system pay for the upkeep and general improvement to

the system nearly exclusively by the payment of sales and use taxes. Sales and use taxes are not sufficient, however, to pay for all the road needs and there are limited resources available to the City, from other sources, to add to the system or to make improvements in the rapidly developing areas of the City.

Therefore, the Council finds and affirms that it is in the public interest to continue the practice of collecting Transportation Capacity Payments (TCP) and appropriately increase the amount of that fee to more accurately reflect the cost of improvements that are reasonably attributable to new development, new residents and new business activities (collectively "Growth").

The Council further finds that the TCP shall be set at a level that a substantial portion of the cost to build new transportation facilities caused by Growth is paid for by the Growth that has caused the need.

The Council is well aware that Growth and new development creates additional vehicular traffic that consumes a portion of the existing transportation infrastructure capacity. In support of the TCP methodology, the City has adopted the data, assumptions and conclusions of the Institute of Transportation Engineer's Trip Generation Manual ("ITE") for purposes of projecting the number of trips created by development. The ITE is a valid, nationally recognized basis to estimate traffic generated by a development and shall continue to be used by the City. The most recent version of the ITE is incorporated herein by this reference as if fully set forth.

The Council has found and affirms that a fair method of imposing a portion of the costs of paying for additional or improved capacity, necessitated because of Growth, is a fee based on a formula that considers among other things the number of trips generated by different types of development (based on ITE), the average trip length, and the percentage of new trips as variables. The specific formula for the TCP provided for herein has been studied and found to be valid by the 2002 Transportation Impact Fee Study prepared by Duncan Associates. That study is incorporated herein by this reference as if fully set forth.

Because the traffic impacts of new trips are not always easily ascertained or allocated to a particular intersection or street, and because the City is not so large that there are distinct areas of the City which are wholly unrelated to the others, the Council finds that it is not reasonable to define discrete time and distance limits for the spending of TCP funds in relation to each development. Nevertheless, expenditure and the prioritization of projects for expenditure shall, to the extent reasonable, be as near in time and distance as is possible to the location from which the payment was derived.

The Council has considered, but rejected as impracticable, a proposal whereby the City would be divided into quadrants or other sub-areas, in which quadrant or sub-area funds attributable to a particular subdivision or development must be spent within certain specified time limits. Such a method, while attractive to a developer, ignores the professional judgments which traffic engineers must make and ignores the reality that

sub-funds, which track TCP funds from particular areas or neighborhoods, may never have enough money to pay for needed improvements.

BE IT ORDAINED BY THE CITY COUNCIL OF THE CITY OF GRAND JUNCTION THAT SECTION 6.2 B1& B2 OF THE ZONING AND DEVELOPMENT CODE ARE AMENDED AS SHOWN:

Additions are shown in ALL CAPS, except for the entire section entitled “Growth and Development Related Street Policy” which is new, even though it is not capitalized. Adoption of this ordinance shall constitute a repeal of inconsistent terms and provisions of the existing ordinance and/or the codification including the analytical and other justification and descriptive materials which were adopted by reference in Ordinance No. 2750.6.2B1(f) Dedications required by subparagraph shall be at no cost to the City. Dedications shall not be eligible for, or require a refund or TCP credit.

6.2B1(f) Dedications required by subparagraph 6.2B1c shall be at no cost to the City. Dedications shall not be eligible for or require a refund or TCP credit.

6.2B2 Transportation Capacity Payment (TCP) and Right-of-Way Improvements.

6.2B2 a. The developer shall pay to the City a Transportation Capacity Payment (TCP) and Right-of-Way Improvements as required by the Public Works Director (DIRECTOR.)

a. The developer shall pay to the City a Transportation Capacity Payment (TCP) as required by the Public Works Director (DIRECTOR).

b. THE DIRECTOR MAY REQUIRE THAT THE DEVELOPER PAY FOR AND/OR CONSTRUCT IMPROVEMENTS necessary for the safe ingress and/or egress of traffic to the development. THOSE IMPROVEMENTS ARE DEFINED AS MINIMUM STREET ACCESS IMPROVEMENTS. MINIMUM STREET ACCESS IMPROVEMENTS SHALL BE DEFINED BY THE MOST RECENT VERSION OF THE CITY’S GROWTH AND DEVELOPMENT RELATED STREET POLICY AND/OR TEDS. THE GROWTH AND DEVELOPMENT RELATED STREET POLICY SHALL BE REVIEWED BY CITY STAFF AND ADOPTED ANNUALLY BY COUNCIL RESOLUTION.

c. No PLANNING CLEARANCE FOR A building permit for any use or activity requiring payment of the TCP pursuant to this Ordinance shall be issued until the TCP HAS BEEN PAID AND MINIMUM STREET ACCESS IMPROVEMENTS HAVE BEEN CONSTRUCTED, PAID FOR OR ADEQUATELY SECURED AS DETERMINED BY THE DIRECTOR. ADEQUATE SECURITY SHALL BE THAT ALLOWED OR REQUIRED FOR A DEVELOPMENT IMPROVEMENT AGREEMENT (DIA) UNDER SECTION 2.19 OF THIS CODE.

d. The amount of the TCP shall be as set forth ANNUALLY BY THE CITY COUNCIL in ITS adopted fee RESOLUTION. THE TCP IS MINIMALLY SUBJECT

TO ANNUAL ADJUSTMENT FOR INFLATION BASED ON THE CONSUMER PRICE INDEX FOR ALL URBAN CONSUMERS (CPI-U), WESTERN REGION, SIZE B/C, PUBLISHED MONTHLY BY THE UNITED STATES DEPARTMENT OF LABOR. (THIS INFORMATION CAN BE FOUND AT THE INTERNET SITE OF <http://data.bls.gov/labjava/outside.jsp?survey=cu>)

e. THE TCP shall be used BY THE DIRECTOR TO MAKE capital improvements to the transportation facilities in the City IN ACCORDANCE WITH THE CITY'S GROWTH AND DEVELOPMENT RELATED STREET POLICY, THIS ORDINANCE, AND OTHER APPLICABLE PROVISIONS OF THE ZONING AND DEVELOPMENT CODE.

(1) TO PAY DEBT SERVICE ON ANY PORTION OF ANY CURRENT OR FUTURE GENERAL OBLIGATION BOND OR REVENUE BOND ISSUED AFTER THE EFFECTIVE DATE OF THIS ORDINANCE AND USED TO FINANCE MAJOR ROAD SYSTEM IMPROVEMENTS;

(2) FOR THE RECONSTRUCTION AND REPLACEMENT OF EXISTING ROADS, THE CONSTRUCTION OF NEW MAJOR ROAD SYSTEMS, AND IMPROVEMENTS AND/OR FOR THE PAYMENT OF REIMBURSABLE STREET EXPENSES (AS THAT TERM IS DEFINED FROM TIME TO TIME BY THE CITY'S GROWTH AND DEVELOPMENT RELATED STREET POLICY) THAT ARE INTEGRAL TO AND THAT ADD CAPACITY TO THE STREET SYSTEM;

(3) TRAFFIC CAPACITY IMPROVEMENTS DO NOT INCLUDE ONGOING OPERATIONAL COSTS OR DEBT SERVICE FOR ANY PAST GENERAL OBLIGATION BOND OR REVENUE BOND ISSUED PRIOR TO THE EFFECTIVE DATE OF THIS SECTION OR ANY PORTION OF ANY CURRENT OR FUTURE BOND ISSUED AFTER THE EFFECTIVE DATE OF THIS SECTION AND NOT USED TO FINANCE MAJOR ROAD SYSTEM IMPROVEMENTS.

(4) Capital spending decisions shall be guided by the principles, among others, that TCP funds shall be used to make capacity AND SAFETY improvements but not used to upgrade existing deficiencies except incidentally in the course of making improvements; TCP fund expenditures which provide improvements which are near in time and/or distance TO the development FROM WHICH THE FUNDS ARE COLLECTED are preferred over expenditures for improvements which are more distant in time and/or distance.

(5) No TCP funds shall be used for maintenance.

(6) TCP funds will be ACCOUNTED FOR SEPARATELY BUT may be commingled with other funds of the City.

(7) The DIRECTOR shall determine when and where TCP funds shall be spent.

(i) AS PART OF THE TWO-YEAR BUDGET PROCESS

(ii) AS REQUIRED TO KEEP PACE WITH DEVELOPMENT

(8) The TCP shall not be payable if THE DIRECTOR IS SHOWN by clear and convincing evidence, that at least one of the following applies:

(i) alteration or expansion of an existing structure will not create additional trips;

(ii) the construction of an accessory structure will not create additional trips produced by the principal building or use of the land. A garage is an example of an accessory structure which does not create additional trips;

(iii) the replacement of a destroyed or partially destroyed structure with a new building or structure of the same size and use that does not create additional trips;

(iv) a structure is constructed in a development for which a TCP fee has been paid within the prior EIGHTY FOUR (84) months or the structure is in a development with respect to which the developer constructed Street Access Improvements and the City accepted such improvements and the warranties have been satisfied.

f. IF THE TYPE OF IMPACT-GENERATING DEVELOPMENT FOR WHICH A BUILDING PERMIT IS REQUESTED IS FOR A CHANGE OF LAND USE OR FOR THE EXPANSION, REDEVELOPMENT OR MODIFICATION OF AN EXISTING DEVELOPMENT, THE FEE SHALL BE BASED ON THE NET INCREASE IN THE FEE FOR THE NEW LAND USE TYPE AS COMPARED TO THE PREVIOUS LAND USE TYPE.

g. IN THE EVENT THAT THE PROPOSED CHANGE OF LAND USE, REDEVELOPMENT OR MODIFICATION RESULTS IN A NET DECREASE IN THE FEE FOR THE NEW USE OR DEVELOPMENT AS COMPARED TO THE PREVIOUS USE OR DEVELOPMENT, THE DEVELOPER MAY APPLY FOR A REFUND OF FEES PREVIOUSLY PAID WITH THE CONSENT OF THE PREVIOUS PERSON HAVING MADE THE PAYMENT AND OR CONSTRUCTED THE IMPROVEMENTS.

h. FOR FEES EXPRESSED PER 1,000 SQUARE FEET, THE SQUARE FOOTAGE SHALL BE DETERMINED ACCORDING TO GROSS FLOOR AREA, MEASURED FROM THE OUTSIDE SURFACE OF EXTERIOR WALLS AND EXCLUDING UNFINISHED BASEMENTS AND ENCLOSED PARKING AREAS.

THE FEES SHALL BE PRORATED AND ASSESSED BASED ON ACTUAL FLOOR AREA, NOT ON THE FLOOR AREA ROUNDED TO THE NEAREST 1,000 SQUARE FEET.

- i. Any claim for credit shall be made not later than the time of application or request for a planning clearance. Any claim not so made shall be deemed waived. Credits shall not be transferable from one project or development to another nor otherwise assignable or transferable.

2.5 MINIMUM STREET ACCESS IMPROVEMENTS INCLUDE street and road improvements required to PROVIDE FOR THE SAFE ingress and egress needs of the development AS DETERMINED BY THE DIRECTOR.

- a. Quality of service FOR ANY NEW DEVELOPMENT AND/OR FOR TRAFFIC CAPACITY IMPROVEMENTS shall be DETERMINED BY THE DIRECTOR. THE DIRECTOR SHALL DETERMINE THE ACCEPTABLE QUALITY OF SERVICE TAKING INTO CONSIDERATION EXISTING TRAFFIC, STREETS, AND PROPOSED DEVELOPMENT.

- b. REQUIRED RIGHT-OF-WAY DEDICATIONS SHALL BE AT NO COST TO THE CITY.

2.6 Definitions. The following terms and words shall have the meanings set forth for this section.

- a. Average trip length: The average length of a vehicle trip as determined by the limits of the City, the distance between principle trip generators and as modeled by the CITY'S, THE COUNTY'S, THE STATE'S OR THE MPO'S COMPUTER program(S). IN THE EVENT THAT THE MODELS ARE INCONSISTENT, THE MOST ADVANTAGEOUS TO THE CITY SHALL BE USED.
- b. "Convenience store," "hotel/motel," "retail," and other terms contained and with the meaning set forth in the Trip Generation Manual.
- c. Lane-mile: Means one paved lane of a right-of-way mile in length fourteen (14) feet in width, including curb and gutter, sidewalk, storm sewers, traffic control devices, earthwork, engineering, and construction management including inspections. The value of right-of-way is not included.
- d. Percentage of new trips: Based on THE MOST CURRENT VERSION of ITE Transportation and Land Development Manual, and of the ITE Trip Generation Manual.
- e. Unimproved/under-improved floor area: Has the meaning as defined in the adopted building codes.

2.7 CALCULATION OF FEE.

- a. ANY PERSON WHO APPLIES FOR A BUILDING PERMIT FOR AN IMPACT-GENERATING DEVELOPMENT SHALL PAY A TRANSPORTATION IMPACT FEE IN ACCORDANCE WITH THE MOST RECENT FEE SCHEDULE PRIOR TO ISSUANCE OF A BUILDING PERMIT. IF ANY CREDIT IS DUE PURSUANT TO SECTION i ABOVE, THE AMOUNT OF SUCH CREDIT SHALL BE DEDUCTED FROM THE AMOUNT OF THE FEE TO BE PAID.

Land Use Type	ITE Code	Unit	Fee	Factor
Residential				
Single Family	210	Dwelling	\$1,500	1.00
Multi-Family	220	Dwelling	\$1,039	0.69
Mobile Home/RV Park	240	Pad	\$ 754	0.50
Hotel/Motel	310/320	Room	\$1,414	0.94
Retail/Commercial				
Shopping Center (0-99KSF)	820	1000 SF	\$2,461	1.64
Shopping Center (100-249KSF)	820	1000 SF	\$2,311	1.54
Shopping Center (250-499KSF)	820	1000 SF	\$2,241	1.49
Shopping Center (500+KSF)	820	1000 SF	\$2,068	1.38
Auto Sales/Service	841	1000 SF	\$2,223	1.48
Bank	911	1000 SF	\$3,738	2.49
Convenience Store w/Gas Sales	851	1000 SF	\$5,373	3.58
Golf Course	430	Hole	\$3,497	2.33
Health Club	493	1000 SF	\$2,003	1.34
Movie Theater	443	1000 SF	\$6,216	4.14
Restaurant, Sit Down	831	1000 SF	\$3,024	2.02
Restaurant, Fast Food	834	1000 SF	\$6,773	4.52
Office/Institutional				
Office, General (0-99KSF)	710	1000 SF	\$1,845	1.23
Office, General >100KSF	710	1000 SF	\$1,571	1.05
Office, Medical	720	1000 SF	\$5,206	3.47
Hospital	610	1000 SF	\$2,418	1.61
Nursing Home	620	1000 SF	\$ 677	0.45
Church	560	1000 SF	\$1,152	0.77
Day Care Center	565	1000 SF	\$2,404	1.60
Elementary/Sec. School	520/522/530	1000 SF	\$ 376	0.25
Industrial				
Industrial Park	130	1000 SF	\$1,091	0.73
Warehouse	150	1000 SF	\$ 777	0.52
Mini-Warehouse	151	1000 SF	\$ 272	0.18

- b. IF THE TYPE OF IMPACT-GENERATING DEVELOPMENT FOR WHICH A BUILDING PERMIT IS REQUESTED IS NOT SPECIFIED ON THE FEE SCHEDULE, THEN THE DIRECTOR SHALL DETERMINE THE FEE ON THE BASIS OF THE FEE APPLICABLE TO THE MOST NEARLY COMPARABLE LAND USE ON THE FEE SCHEDULE. THE DIRECTOR SHALL DETERMINE

COMPARABLE LAND USE BY TRIP GENERATION RATES CONTAINED IN THE MOST CURRENT EDITION OF ITC *TRIP GENERATION MANUAL*.

c. IN MANY INSTANCES, A BUILDING MAY INCLUDE SECONDARY OR ACCESSORY USES TO THE PRINCIPAL USE. FOR EXAMPLE, IN ADDITION TO THE PRODUCTION OF GOODS, MANUFACTURING FACILITIES USUALLY ALSO HAS OFFICE, WAREHOUSE, RESEARCH AND OTHER ASSOCIATED FUNCTIONS. THE TCP FEE SHALL GENERALLY BE ASSESSED BASED ON THE PRINCIPAL USE. IF THE APPLICANT CAN SHOW THE DIRECTOR IN WRITING BY CLEAR AND CONVINCING EVIDENCE THAT A SECONDARY LAND USE ACCOUNTS FOR OVER 25% OF THE GROSS FLOOR AREA OF THE BUILDING AND THAT THE SECONDARY USE IS NOT ASSUMED IN THE TRIP GENERATION FOR THE PRINCIPAL USE, THEN THE TCP MAY BE CALCULATED ON THE SEPARATE USES.

d. TCP FEE CALCULATION STUDY -- AT THE ELECTION OF THE APPLICANT OR UPON THE REQUEST OF THE DIRECTOR, FOR ANY PROPOSED DEVELOPMENT ACTIVITY, FOR A USE THAT IS NOT ON THE FEE SCHEDULE OR FOR WHICH NO COMPARABLE USE CAN BE DETERMINED AND AGREED BY THE APPLICANT AND THE DIRECTOR OR FOR ANY PROPOSED DEVELOPMENT FOR WHICH THE DIRECTOR CONCLUDES THE NATURE, TIMING OR LOCATION OF THE PROPOSED DEVELOPMENT MAKES IT LIKELY TO GENERATE IMPACTS COSTING SUBSTANTIALLY MORE TO MITIGATE THAN THE AMOUNT OF THE FEE THAT WOULD BE GENERATED BY THE USE OF THE FEE SCHEDULE, A TCP FEE CALCULATION STUDY MAY BE PERFORMED.

e. THE COST AND RESPONSIBILITY FOR PREPARATION OF A FEE CALCULATION STUDY SHALL BE DETERMINED IN ADVANCE BY THE APPLICANT AND THE DIRECTOR.

f. THE DIRECTOR MAY CHARGE A REVIEW FEE AND/OR COLLECT THE COST FOR RENDERING A DECISION ON SUCH STUDY. THE DIRECTOR'S DECISION ON A FEE OR A FEE CALCULATION STUDY MAY BE APPEALED TO THE ZONING BOARD OF APPEALS IN ACCORDANCE WITH 2.18B OF THIS CODE.

g. THE TCP FEE CALCULATION STUDY SHALL BE BASED ON THE SAME FORMULA, QUALITY OF SERVICE STANDARDS AND UNIT COSTS USED IN THE IMPACT FEE STUDY. THE FEE STUDY REPORT SHALL DOCUMENT THE METHODOLOGIES AND ALL ASSUMPTIONS.

h. THE TCP FEE CALCULATION STUDY SHALL BE CALCULATED ACCORDING TO THE FOLLOWING FORMULA.

$$\text{FEE} = \text{VMT} \times \text{NET COST/VMT} \times \text{RF}$$

WHERE:

$$\begin{aligned} \text{VMT} &= \text{TRIPS} \times \% \text{ NEW} \times \text{LENGTH} \div 2 \\ \text{TRIPS} &= \text{DAILY TRIP ENDS GENERATED BY THE DEVELOPMENT DURING THE WORK WEEK} \\ \% \text{ NEW} &= \text{PERCENT OF TRIPS THAT ARE PRIMARY, AS OPPOSED TO PASSBY OR DIVERTED-LINK TRIPS} \\ \text{LENGTH} &= \text{AVERAGE LENGTH OF A TRIP ON THE MAJOR ROAD SYSTEM} \\ \div 2 &= \text{AVOIDS DOUBLE-COUNTING TRIPS FOR ORIGIN AND DESTINATION} \\ \text{NET COST/VMT} &= \text{COST/VMT} - \text{CREDIT/VMT} \\ \text{COST/VMT} &= \text{COST/VMC} \times \text{VMC/VMT} \\ \text{COST/VMC} &= \text{AVERAGE COST TO CREATE A NEW VMC BASED ON HISTORICAL OR PLANNED PROJECTS ($306 EXCLUDING MAJOR STRUCTURES)} \\ \text{VMC/VMT} &= \text{THE SYSTEM-WIDE RATIO OF CAPACITY TO DEMAND IN THE MAJOR ROAD SYSTEM (1.0 ASSUMED)} \\ \text{CREDIT/VMT} &= \text{CREDIT PER VMT, BASED ON REVENUES TO BE GENERATED BY NEW DEVELOPMENT ($82)} \\ \text{RF} &= \text{REDUCTION FACTOR ADOPTED BY POLICY AT 52.6\%} \end{aligned}$$

i. A TCP FEE CALCULATION STUDY SUBMITTED FOR THE PURPOSE OF CALCULATING A TRANSPORTATION IMPACT FEE MAY BE BASED ON DATA, INFORMATION AND ASSUMPTIONS THAT ARE FROM:

- (1) AN ACCEPTED STANDARD SOURCE OF TRANSPORTATION ENGINEERING OR PLANNING DATA; OR
- (2) A LOCAL STUDY ON TRIP CHARACTERISTICS PERFORMED BY A QUALIFIED TRANSPORTATION PLANNER OR ENGINEER PURSUANT TO AN ACCEPTED METHODOLOGY OF TRANSPORTATION PLANNING OR ENGINEERING THAT HAS BEEN APPROVED BY THE DIRECTOR.

Growth and Development Related Street Policy

The City of Grand Junction requires that new development pay a Transportation Capacity Payment to help defray the cost to the City for the impact of development on City streets. The City has experienced steady growth for over a decade and during that time has struggled with how to fairly collect and administer impact fees assessed against development, how to credit some or all of those fees against taxes otherwise paid and what, if any, role the City should have in funding/contributing to the cost of providing additional traffic/street capacity and/or traffic/street capacity in accordance with community expectations.

The City has determined that there are three key components to a meaningful growth and development related street/traffic policy. They are:

1. Collection of a realistic TCP for all new development projects. The TCP shall be annually reviewed and adjusted in accordance with 6.2B2d of the ZDC.
2. A clear articulation of what minimum requirements (in addition to the TCP) each development must construct; and
3. City funding and/or other means of participation in construction of street improvements.

Because the City has determined that traffic is a community problem, the TCP shall be uniform throughout the City and subject to criteria stated below; funding may be provided to street improvements anywhere within the City.

The principles of this policy are:

1. All development projects that create a traffic impact, as defined by the City ZDC, shall pay a TCP as established by and in accordance with the ZDC. The fundamental precept of the City's TCP policy is that new development must pay its fair share for the added traffic that development creates.
2. The TCP fee has been set to ensure that trips from each new development are calculated and that the developer contributes to the value of capacity consumption of City streets in proportion to the traffic that the development is reasonably anticipated to generate. The fee also recognizes as a credit the value of taxes generated from development.
3. TCP funds are intended to be used for improvements to the major roadway system as identified on the most current version of the Grand Valley Circulation Plan functional classification map (Minor Collector or above). Improvements to the local

roadway system will continue to be the responsibility of the property owners abutting the local roadway. The TCP fee is not intended to be used for debt service for the Riverside Parkway project.

4. Minimum Street Access Improvements -- The intent of this section is to describe the improvements necessary to connect a proposed development to the existing street system. SUCH IMPROVEMENTS SHALL BE PUBLIC IMPROVEMENTS AND SHALL BE THE MAINTENANCE RESPONSIBILITY OF THE CITY WHETHER SUCH PUBLIC IMPROVEMENTS ARE IDENTIFIED THROUGH A TRAFFIC STUDY OR OTHERWISE MADE A CONDITION OF APPROVAL FOR DEVELOPMENT. Construction of these improvements will be the responsibility of the developer and shall be constructed or guaranteed at the time of development. These improvements are needed to provide safe ingress/egress and shall meet the minimum standards in ~~Section~~ CHAPTERS 5 AND 6 AND THE UNNUMBERED CHAPTER ENTITLED Fire Department Access of the TEDS Manual – Fire Department Access. These improvements are not intended to include off-site, Half Street or perimeter improvements necessary to increase the capacity or improve the safety of adjacent or perimeter streets.

- Absent unique needs or characteristics of the development, Minimum Street Access Improvements shall mean construction of full asphalt radii, and necessary drainage improvements in accordance with the City standard detail for each intersection with a perimeter street and/or improvements necessitated if the proposed development creates lots with direct access to the perimeter street(s) as determined by the Director. An owner or developer may appeal a determination of Minimum Street Access Improvements to the Transportation Engineering Design Standards (TEDS) Exception Committee. That Committee consists of the PW&U Director, the Fire Chief and the Community Development Director.
- Curb, gutter and sidewalk improvements shall be constructed as part of minimum access improvements when connecting directly to a street with like improvements.
- The City's multi-modal plan, including bike lanes, trails, paths, alternate pedestrian connections and bus stops and transit shall be incorporated into determining what improvements are required associated with a connection to the adjacent street system.
- Right of Way - The development shall dedicate necessary ROW (per Code and TEDS) to provide safe ingress/egress to the proposed development.
- Drainage Structures including Bridges - The development shall construct drainage structures and/or bridges associated the connection of the development to the street system.

- Traffic Studies - Preparation of Traffic Studies shall be the responsibility of new development as currently defined by the Code.
- Utilities – The extension of utilities including water, sewer, storm water improvements gas, electric, cable and telephone, etc will continue to be the responsibility of new development.

5. In addition to the TCP and Minimum Street Access Improvements, the developer must fully construct (or if current needs do not require construction, then the developer must guarantee for future construction) all internal streets, roads, alleys, and future connections in accordance with the development's approved plan.

6. The developer is responsible for the cost of the design of all features of the Minimum Street Access Improvements as required by TEDS, the GVCP, and other applicable City code(s), ordinance(s), policy(ies) or resolution(s).

7. Reimbursable Street Expenses – In the event a development triggers the need for public improvements beyond available City funding from the TCP, the City and the developer may enter into an agreement that would provide for the reimbursement of a portion of the costs of the public improvements.

Safe and adequate streets are a priority for the City. To help meet that need, a fund will be established to allow the City to fund and/or partner with developers or other governments. City funding or participation in street improvements shall be used for three purposes:

1. Construction of larger scale improvements along corridors which are deficient in street improvements (i.e., capacity, safety or physical improvements including pavement, curbs, gutters, and sidewalks).

2. Specific street or intersection improvements either adjacent or off-site from a new development where the existing condition is deficient as defined by City code.

3. Participation in a larger regional project in cooperation with the participating agencies of the Grand Valley MPO.

City funding and/or other means of participation in street improvements is conditioned on:

- Construction will improve traffic safety;
- Construction will improve traffic flow;
- Construction will improve pedestrian safety;
- Construction will improve capacity.


Introduced on First Reading this 19th day of May 2004.

PASSED and ADOPTED on second reading this 2nd day of June 2004.

/s/: Bruce Hill
President of the Council

Attest:

/s/: Stephanie Tuin
City Clerk



MINIMUM STREET ACCESS INCLUDES

- ♦ CULVERT/CANAL CROSSING TO ACCOMMODATE DEVELOPMENT NEEDS (TRAFFIC STUDY). IF LESS THAN LENGTH REQUIRED FOR ULTIMATE STREET SECTION, CITY MAY CONTRIBUTE TO COMPLETE THE LENGTH.
- ♦ FIRE ACCESS IMPROVEMENTS BETWEEN COLLECTOR AND STORE ACCESS (MIN. 20' OF PAVEMENT WIDTH, OR GREATER AS REQUIRED BY THE TRAFFIC STUDY. DOES NOT INCLUDE CURB, GUTTER OR SIDEWALK, UNLESS NECESSARY FOR TRANSITION WITH EXISTING).
- ♦ DEDICATION OF R.O.W. PER DEVELOPMENT NEEDS OR PER MAJOR STREET PLAN, WHICH EVER IS GREATER.
- ♦ DRAINAGE IMPROVEMENTS AS NECESSARY.

CITY OF GRAND JUNCTION BUILDS


- ♦ TRAFFIC SIGNAL
- ♦ DECELERATION LANE


DRAWN BY: JAH
 DATE: 5-10-2004
 SCALE: N.T.S.
 APPR. BY: T.M.
 FILE NO. EXAMPLE.DWG

PUBLIC WORKS & UTILITIES
 ENGINEERING DIVISION

EXAMPLE 1

CITY OF
Grand Junction
 COLORADO





MINIMUM STREET ACCESS INCLUDES

- ◆ CONNECTION OF CURBS, GUTTERS AND SIDEWALKS TO EXISTING IMPROVEMENTS.
- ◆ DRAINAGE IMPROVEMENTS AS NECESSARY.

CITY OF GRAND JUNCTION BUILDS

- ◆ DECELERATION LANE

DRAWN BY: JAH
 DATE: 5-10-2004
 SCALE: N.T.S.
 APPR. BY: T.M.
 FILE NO. EXAMPLE.DWG

PUBLIC WORKS & UTILITIES
 ENGINEERING DIVISION
 EXAMPLE 3

CITY OF
Grand Junction
 COLORADO

CITY OF GRAND JUNCTION

ORDINANCE NO. ____

AN ORDINANCE AMENDING SECTION 21.06 OF THE GRAND JUNCTION ZONING AND DEVELOPMENT CODE CONCERNING THE UPDATING OF AND ADOPTION OF NEW DEVELOPMENT IMPACT FEES.

Recitals:

The City Council having duly considered the policy and pragmatic implications of updating and enacting land development fees, which are also known as impact fees, ("Fees") finds that Fees are a necessary component of funding the capital costs of infrastructure required to maintain the current level of service for city residents, and further finds that development should pay its proportionate share of the capital costs of fire, police, municipal facilities, parks and recreation and transportation infrastructure.

The City recently completed two Fee studies and pursuant to State law regarding the purpose and methodology related to calculation and imposition of Fees, the fee studies were presented to City Council. The Fee studies found that development created a demand on capital facilities and that the City's current fees do not support the Council policy that development should pay a proportionate share of the capital costs of fire, police, municipal facilities, parks and recreational and transportation infrastructure and that and that updating and adopting new Fees as described in the Fee Studies would be reasonably related to the overall cost of the services or improvements to be provided by the City.

The City Council further finds and determines that resources of the City are properly allocated to maintaining and improving streets and that further resources are needed to defray the capital facilities costs related to new development.

Therefore, the City Council finds and affirms that it is in the public interest to continue the practice of collecting transportation and parks and recreation impact fees and there is a need to increase the amount of those Fees to more accurately reflect the cost of improvements that are reasonably attributable to new development, new residents and new business activities.

The Council further finds and affirms that it is in the public interest to collect impact fees for the fire, police and municipal facilities to reflect the cost of capital improvements that are reasonably attributable to new development, new residents and new business activity.

NOW, THEREFORE, BE IT ORDAINED BY THE CITY COUNCIL OF THE CITY OF GRAND JUNCTION THAT SECTION 21.06. OF THE ZONING AND DEVELOPMENT CODE IS AMENDED AS SHOWN: (Deletions ~~struckthrough~~; additions underlined.)

ADD ALL OF THE FOLLOWING:

21.06.110 Development Impact Fees

- (a) Title. This section shall be known and may be cited as the "Grand Junction, Colorado Impact Fee Ordinance" or "Impact Fee Ordinance."
- (b) Authority. The City has the authority to adopt this Chapter pursuant to Article XX, § 6 of the Colorado State Constitution, the City's home rule charter, the City's general police powers, and other laws of the State of Colorado.
- (c) Application. This shall apply to all development within the territorial limits of the City, except development exempted pursuant to §21.06.110(f)(2), *Exemptions*.
- (d) Purpose.
 - (1) The intent of this Chapter is to ensure that new development pays a proportionate share of the cost of city parks and recreation, fire, police, municipal government and transportation capital facilities.
 - (2) It is the intent of this Chapter that the impact fees imposed on new development are no greater than necessary to defray the impacts directly related to proposed new development.
 - (3) Nothing in this Chapter shall restrict the City from requiring an applicant for a development permit to construct reasonable capital facility improvements designed and intended to serve the needs of the applicant's project, whether or not such capital facility improvements are of a type for which credits are available under §21.06.110(g), *Credits*.
- (e) Definitions.

For the purposes of this section, the following terms shall have the following meanings:

 - 1) *Planning Clearance.* A planning clearance issued by the Director permitting the construction of a building or structure within the City of Grand Junction.
 - 2) *Capital facilities.* Any improvement or facility that: a. Is directly related to any service that the City is authorized to provide; b. Has an estimated useful life of five years or longer; and c. Is required by the Charter, ordinances or policy of the City pursuant to a resolution or ordinance.
 - 3) *Commencement of impact-generating development.* Commencement of impact-generating development occurs upon either:

- a. Planning Clearance for residential uses intended for fee simple ownership such as single family homes, townhomes or condominiums, or
 - b. The submittal of a complete application for the development of a non-residential development or multi-family for rent development for which construction commences on or before two years from the date of complete application submittal
- 4) Development. Any construction or expansion of a building, structure, or use, any change in use of a building or structure, or any change in the use of land, which creates additional demand for parks and recreation, fire, police and municipal government capital facilities.
- 5) Development permit. Any final approval of an application for a rezoning, an approved Planned Development Ordinance, conditional use permit, subdivision, development or site plan, planning clearance, planning clearance or similar application for new construction.
- 6) Fee payer. A person commencing impact-generating development who is obligated to pay an impact fee in accordance with the terms of this section.
- 7) Fee schedule or impact fee schedule. The impact fees for Police, Fire, Municipal Facilities, Parks and Recreation and Transportation established by this section. The impact fee schedule is set forth in the Fee Schedule to this section and is incorporated herein by reference.
- 8) Impact fee study. The study entitled City of Grand Junction, Colorado 2019 Impact Fee Study, prepared by TischlerBise dated August 8, 2019 or the study entitled Transportation Impact Fee Study by Duncan Associates dated November 2019 with Minor Revisions February 28, 2019.
- 9) Independent fee calculation study. A study prepared by a fee payer, calculating the cost of parks and recreation capital facilities, fire capital facilities, police capital facilities and municipal government capital facilities required to serve the fee payer's proposed development, that is performed on an average cost (not marginal cost) methodology, uses the level of service standards, service units and unit construction costs stated in the impact fee study, and is performed in compliance with any criteria for such studies established by this section.
- 10) Level of service (LOS). A measure of the relationship between service capacity and service demand for capital facilities.
- 11) Floor area. The total finished square footage of all levels included within the outside walls of a building or portion thereof, but excluding courts, garages having no habitable area, uninhabitable areas that are located above the highest habitable level, or uninhabitable areas that are located below the first floor level.
- 12) Successor-in-interest. A person, as defined by this section, who is conveyed a fee simple interest in land for which an impact fee is paid or a credit is approved pursuant to the terms of this section.

For the purposes of this section, site-related improvements such as minimum street improvements and safety improvements shall not constitute transportation capital facilities.

(f) Development impact fees to be imposed.

(1) Fee obligation, payment and deposit.

- i. Obligation to pay and time of payment. Commencing January 1, 2020, any person who causes the commencement of impact-generating development, except those exempted pursuant to §21.06.110(f)(2), Exemptions, shall be obligated to pay impact fees before ... and pursuant to the terms of this section. The obligation to pay the impact fees shall run with the land. The amount of the impact fees shall be determined in accordance with §21.06.110(f)(3), Calculation of amount of impact fees and the Fee Schedule in effect at the time of issuance of a planning clearance and paid to the Director at the time of issuance of a planning clearance. If any credits are due pursuant to §21.06.110(h), Credits, those shall be determined prior to the issuance of a planning clearance and payment of the impact fees.
- ii. Fees promptly deposited into accounts. All monies paid by a fee payer pursuant to this section shall be identified as impact fees and shall be promptly deposited in the appropriate impact fee trust accounts established and described in §21.06.110(h), Impact fee trust accounts.
- iii. Extension of previously issued development permit. If the fee payer is applying for an extension of a development permit issued prior to January 1, 2020, the impact fees required to be paid shall be the net increase between the impact fees applicable at the time of the current permit extension application and any impact fees previously paid pursuant to this section, and shall include any impact fees established subsequent to such prior payment.
- iv. Fee based on development permitted. If the planning clearance is for less floor area than the entire development approved pursuant to the development permit, the fee shall be computed separately for the floor area of development covered by the planning clearance, and with reference to the use categories applicable to such development covered by the planning clearance.
- v. Permit for change in use, expansion, redevelopment, modification. If the fee payer is applying for a planning clearance to allow for a change of use or for the expansion, redevelopment, or modification of an existing development, the impact fees required to be paid shall be based on the net increase in the impact fees for the new use as compared to the

previous use and actual fee paid for the previous use, and shall include any impact fees established subsequent to such prior payment.

- vi. Prior conditions and/or agreements. Any person who prior to January 1, 2020 has agreed in writing with the City, as a condition of permit approval to pay an impact fee shall be responsible for the payment of the impact fees under the terms of such agreement, and the payment of the impact fees may be offset against any impact fees due pursuant to the terms of this section.

(2) Exemptions. The following types of development shall be exempted from payment of the impact fees. Any claim for exemption shall be made no later than the time when the applicant applies for the first planning clearance. Any claim for exemption not made at or before that time shall be waived. The Director shall determine the validity of any claim for exemption pursuant to the standards set forth below.

- i. Replacing existing residential unit with new unit. Reconstruction, expansion, alteration or replacement of a previously existing residential unit that does not create any additional residential units.
- ii. New impact-generating development creates no greater demand than previous development. New impact-generating development that the fee payer can demonstrate will create no greater demand over and above that produced by the existing use or development.
- iii. Building after fire or catastrophe. Rebuilding the same amount of floor space of a structure that was destroyed by fire or other catastrophe.
- iv. Accessory structures. Construction of unoccupied accessory structures related to a residential unit.
- v. Previous payment of same amount of impact fees. Impact-generating development for which an impact fee was previously paid in an amount that equals or exceeds the impact fee that would be required by this section.
- vi. Government. Development by the federal government, the state, school district, or the city.
- vii. Complete development application approved prior to effective date of section. For development for which a complete application for a planning

clearance was approved prior to January 1, 2020 and for non-residential and multi-family development. For which a complete application was submitted prior to January 1, 2020 so long as construction commences by January 1, 2022. For the purposes of this section, a development application shall not be considered complete unless and until (a) all the required information and submittal materials required by all relevant city ordinances, resolutions, rules and regulations are submitted and received by the Director, and (b) the Director has determined the application is complete. The decision of the Director with respect to completeness is final.

- viii. Small additions and renovations for residential uses. Construction of an addition to an existing dwelling unit of 500 square feet or less, or expansion of finished space for an existing dwelling unit of 500 square feet or less. This exemption shall only be used one time for each dwelling unit and does not apply to accessory dwelling units.

(3) Calculation of amount of impact fees.

- i. Except for those electing to pay impact fees pursuant to §21.06.110(f)(3)(ii), Independent fee calculation study, the impact fees applicable to the impact-generating development shall be as determined by the Fee Schedule, which is hereby adopted and incorporated herein. The Impact Fee Schedule is based on the impact fee study. It applies to classes of land uses within the City, differentiates between types of land uses, and is intended to defray the projected impacts caused by proposed new development on city capital facilities. The determination of the land use category(ies) in the Impact Fee Schedule that is applicable to impact-generating development shall be made by the Director with reference to the Impact Fee Study and the methodologies therein; the then-current edition of the ITE Trip Generation Manual, published by the Institute of Traffic Engineers; the City zoning code; the then-current land use approvals for the development; and any additional criteria set forth in duly administrative rules.

- 1. Annual adjustment of impact fees to reflect effects of inflation. The Impact Fee Schedule, shall be adjusted annually. On January 1, 2023, and on January 1 of each subsequent year each impact fee amount set forth in Fee Schedule shall be adjusted for inflation.

- a. For transportation impact fees, the fees shall be adjusted for inflation based on latest 10-year average of the Colorado Department of Transportation Construction Cost Index, published quarterly by CDOT.
 - b. For Fire, Police, Parks and Municipal Facilities, the fees shall be adjusted for inflation based on the most recent Construction Cost Index published by Engineering News Record.
 - c. Adjusted Fees/the adjusted Impact Fee Schedule shall become effective immediately upon calculation and certification by the City Manager and shall not require additional action by the City Council to be effective.
 2. Impact-generating development not listed in the Impact Fee Schedule. If the proposed impact-generating development is of a type not listed in the Impact Fee Schedule, then the impact fees applicable to the most nearly comparable type of land use. . The determination of the most nearly comparable type of land use shall be made by the Director with reference to the impact fee study and City code.
 3. Mix of uses. If the proposed impact-generating development includes a mix of those uses listed in the Impact Fee Schedule, then the impact fees shall be determined by adding the impact fees that would be payable for each use as if it was a freestanding use pursuant to the Impact Fee Schedule.
- ii. Independent fee calculation study. In lieu of calculating the amount(s) of impact fees by reference to the Impact Fee Schedule, a fee payer may request that the amount of the required impact fee be determined by reference to an independent fee calculation study.
1. Preparation of independent fee calculation study. If a fee payer requests the use of an independent fee calculation study, the fee payer shall be responsible for retaining a qualified professional (as determined by the Director) to prepare the independent fee calculation study that complies with the requirements of this section, at the fee payer's expense.
 2. General parameters for independent fee calculation study. Each independent fee calculation study shall be based on the same

LOS standards and unit costs for the capital facilities used in the impact fee study, and shall document the relevant methodologies and assumptions used.

3. Procedure.

- a. An independent fee calculation study shall be initiated by submitting f an application to the Director together with an application fee to defray the costs associated with the review of the independent fee calculation study.
- b. The Director shall determine if the application is complete. If it is determined the application is not complete, a written statement outlining the deficiencies shall be sent by mail to the person submitting the application. The Director shall take no further action on the application until it is complete.
- c. When it is determined the application is complete, the application shall be reviewed by the Director and a written decision rendered on whether the impact fees should be modified, and if so, what the amount should be, based on the standards in §21.06.110(g)(1), *Standards*.

- 4. Standards. If, on the basis of generally recognized principles of impact analysis the Director determines the data, demand information and assumptions used by the applicant to calculate the impact fees in the Independent Fee Calculation Study more accurately measures the proposed impact-generating development's impact on the appropriate capital facilities, the impact fees determined in the Independent Fee Calculation Study shall be deemed the impact fees due and owing for the proposed development. The fee adjustment shall be set forth in a fee agreement. If the Independent Fee Calculation Study fails to satisfy these requirements, the impact fees applied shall be the impact fees established in the Impact Fee Schedule.

(g) Credits.

(1) Standards.

- i. General. Any person causing the commencement of impact-generating development may apply for credit against impact fees otherwise due, up to but not exceeding the full obligation of impact fees proposed to be paid

pursuant to the provisions of this section, for any contributions or construction (as determined as appropriate by the Director) accepted in writing by the City for capital facilities. Credits against impact fees shall be provided only for that impact fee for which the fee should be collected.

ii. Valuation of credits.

1. Construction. Credit for construction of capital facilities shall be valued by the City based on complete engineering drawings, specifications, and construction costs estimates submitted by the fee payer to the City. The Director shall determine the amount of credit, if any, due based on the information submitted, or, if he/she determines the information is inaccurate or unreliable, then on alternative engineering or construction costs acceptable to the Director.
2. Contributions. Contributions for capital facilities shall be based on the value of the contribution or payment at the time it is made to the City.

iii. When credits become effective.

1. Construction. Credits for construction of capital facilities shall become effective after the credit is approved pursuant to this section, a credit agreement is entered into and (a) all required construction has been completed and has been accepted by the City (b) suitable maintenance and financial warranty has been received and approved by the City, and (c) all design, construction, inspection, testing, financial warranty, and acceptance procedures have been completed in compliance with all applicable city requirements. Approved credits for the construction of capital facilities may become effective at an earlier date if the fee payer posts security in the form of an irrevocable letter of credit or escrow agreement and the amount and terms of such security are accepted by the City Manager. At a minimum, such security must be in the amount of the approved construction credit plus 20 percent, or an amount determined to be adequate to allow the city to construct the capital facilities for which the credit was given, whichever is higher.
2. Contribution. Credits for contributions for capital facilities shall become effective after the credit is approved in writing pursuant to

this section, a credit agreement is entered into and the contribution is actually made to the City in a form acceptable to the City.

- iv. *Transferability of credits.* Credits for contributions, construction or dedication of land shall be transferable within the same development and for the same capital facility for which the credit is provided, but shall not be transferable outside the development. Credit may be transferred pursuant to these terms and conditions by a written instrument, to which the City is a signatory that clearly identifies which credits issued under this section are to be transferred. The instrument shall be signed by both the transferor and transferee, and the document shall be delivered to the Director for registration of the change in ownership. If there are outstanding obligations under a credit agreement, the City may require that the transferor or transferee, or both (as appropriate) enter into an amendment to the credit agreement to assure the performance of such obligations.
- v. *Total amount of credit.* The total amount of the credit shall not exceed the amount of the impact fees due for the specific facility fee (eg. Fire, Police, Parks).
- vi. *Capital contribution front-ending agreement.* The City may enter into a capital contribution front-ending agreement with any person who proposes to construct capital facilities to the extent the fair market value of the construction of these capital facilities exceed the obligation to pay impact fees for which a credit is provided pursuant to this section. The capital contribution front-ending agreement shall provide proportionate and fair share reimbursement linked to the impact-generating development's use of the capital facilities constructed.

(2) *Procedure.*

- i. *Submission of application.* In order to obtain a credit against impact fees otherwise due, the fee payer shall submit an offer for contribution or construction. The offer shall be submitted to the Director, and must specifically request a credit against impact fees.
- ii. *Contribution Offer contents.* The offer for contribution credit shall include the following:

1. Construction. If the proposed credit involves construction of capital facilities:
 - a. The proposed plan of the specific construction certified by a duly qualified and licensed Colorado engineer.
 - b. The projected costs for the suggested improvement, which shall be based on local information for similar improvements, along with the construction timetable for the completion thereof. Such estimated costs may include the costs of construction or reconstruction, the costs of all labor and materials, the costs of all lands, property, rights, easements and franchises acquired, financing charges, interest prior to and during construction and for one year after completion of construction, costs of plans and specifications, surveys of estimates of costs and of revenues, costs of professional services, and all other expenses necessary or incident to determining the feasibility or practicability of such construction or reconstruction;
 - c. A statement under oath of the facts that qualify the fee payer to receive a contribution credit.
 2. Contribution. If the proposed offer involves a credit for any contribution for capital facilities, the following documentation shall be provided:
 - a. A copy of the planning clearance for which the contribution was established;
 - b. If payment has been made, proof of payment; or
 - c. If payment has not been made, the proposed method of payment.
 - iii. Determination of completeness. The Director shall determine if the application is complete. If it is determined that the proposed application is not complete, the Director shall send a written statement to the applicant outlining the deficiencies. No further action shall be taken on the application until all deficiencies have been corrected.
 - iv. Decision. The Director shall determine if the offer for credit is complete, the offer shall be reviewed and approved if it complies with the standards in §21.06.110(g)(1) Standards.
- (3) Credit agreement. If the offer for credit is approved by the Director, a credit agreement shall be prepared and signed by the applicant and the City Manager. The credit agreement shall provide for the construction or contribution of capital facilities, the time by which it shall be dedicated, completed, or paid, , and the

value (in dollars) of the credit against the impact fees the fee payer shall receive for the construction or contribution.

- (4) Accounting of credits. Each time a request to use approved credits is presented to the City, the Director shall reduce the amount of the impact fees, and shall note in the City's records and the credit agreement the amount of credit remaining, if any.

(h) Impact fee trust accounts.

(1) Establishment of trust accounts.

- i. Establishment of trust accounts. For the purpose of ensuring impact fees collected pursuant to this section are designated for the mitigation of capital facility impacts reasonably attributable to new impact-generating development that paid the impact fees.
- ii. Establishment of accounts. Impact fees shall be deposited into four (4) accounts: parks and recreation, capital facilities, fire capital facilities, police capital facilities, and municipal government capital facilities accounts.

(2) Deposit and management of accounts.

- i. Managed in conformance with CRS 29-1-801 et. seq. The impact fee accounts shall be maintained as interest bearing and shall be managed in conformance with CRS 29-1-801 et. seq.
- ii. Immediate deposit of impact fees in appropriate account. All impact fees collected by the City pursuant to the Chapter shall be promptly deposited into the appropriate account.
- iii. Interest earned on trust account monies. Any Impact Fees not immediately necessary for expenditure shall be deposited in interest-bearing accounts. Interest earned on monies in the accounts shall be considered part of such account, and shall be subject to the same restrictions on use applicable to the impact fees deposited in such account.
- iv. Income derived retained in accounts until spent. All income derived from the deposits shall be retained in the accounts until spent pursuant to the requirements of this section.
- v. Expenditure of impact fees. Monies in each account shall be considered to be spent in the order collected, on a first-in/first-out basis.

(i) Expenditure of impact fees.

- (1) Capital facilities impact fees. The monies collected from each capital facilities impact fee shall be used only to acquire or construct capital facilities within the city.
- (2) No monies spent for routine maintenance, rehabilitation or replacement of capital facilities. No monies shall be spent for periodic or routine maintenance.

rehabilitation, or replacement of any city parks and recreation, fire, police or municipal government capital facilities.

- (3) No monies spent to remedy deficiencies existing on effective date of section. No monies shall be spent to remedy existing deficiencies in parks and recreation capital facilities, fire capital facilities, police capital facilities, or municipal government capital facilities.

(4) Transportation impact fee monies may be used to pay debt service on any portion of any current or future general obligation bond or revenue bond issued after July 6, 2004, and used to finance major road system improvements.

- (4) Transportation impact fee monies may be spent for the reconstruction and replacement of existing roads, the construction of new major road systems and improvements and/or for the payment of reimbursable street expenses.

- (5) (6) Annual impact fee budget. At least once during each fiscal year of the City, the City Manager shall present to the City Council a proposed impact fee capital facilities budget for parks and recreation, fire, police, municipal facilities and transportation. The impact fee capital facilities budget shall recommend the City Council appropriate monies from each impact fee account to specific city parks and recreation capital facilities, fire capital facilities, police capital facilities, and municipal government capital facilities. Any monies, including any accrued interest, not budgeted and appropriated to specific capital facility projects and not expended shall be retained in the same impact fee account until budgeted, appropriated and expended according to the City Charter and ordinances.

(j) Refund of impact fees paid.

- (1) Refund of impact fees not spent or encumbered in ten years. A fee payer or the fee payer's successor-in-interest may request a refund of any impact fees not been spent or encumbered within ten years from the date the fee was paid, along with interest actually earned on the fees. Impact fees shall be deemed to be spent on the basis of the first fee collected shall be the first fee spent.

- (2) Procedure for refund. The refund shall be administered by the Director, and shall be undertaken through the following process:

- i. Submission of refund application. A refund application shall be submitted within one year following the end of the 10th year from the date on which the planning clearance was issued. The refund application shall include the following information:

1. A copy of the dated receipt issued for payment of the impact fee;
2. A copy of the planning clearance; and

- ii. Determination of completeness. The Director shall determine if the refund application is complete. If the application is not complete, the Director shall mail the applicant a written statement outlining the deficiencies. The Director shall take no further action on the refund application until it is complete.
- iii. Decision on refund application. When the refund application is complete, it shall be reviewed and approved if the Director determines a fee has been paid which has not been spent within the 10-year period. The refund shall include the fee paid plus interest actually earned on the impact fee.

(3) Limitations.

- i. Expiration of planning clearance without possibility of extension. If a fee payer has paid an impact fee required by this section and obtained a planning clearance, and the planning clearance for which the impact fee was paid later expires without the possibility of further extension, then the fee payer or the fee payer's successor-in-interest shall be entitled to a refund of the impact fee paid, without interest. In order to be eligible to receive a refund of impact fees pursuant to this subsection, the fee payer or the fee payer's successor-in-interest shall be required to submit an application for such refund to the Director within 30 days after the expiration of the planning clearance for which the fee was paid. If a successor-in-interest claims a refund of impact fee, the City may require written documentation that such rights have been conveyed to the claimant. If there is uncertainty as to the person to whom the refund is to be paid, or if there are conflicting demands for such refund, the City Attorney may interplead such funds.
- ii. No refund if project demolished, destroyed, altered, reconstructed or reconfigured. After an impact fee has been paid pursuant to this section, no refund of any part of such fee shall be made if the development for which the impact fee was paid is later demolished, destroyed, or is altered, reconstructed, reconfigured, or changed in use so as to reduce the size or intensity of the development or the number of units in the development.

(k) Low-Moderate Income Housing.

In order to promote the provision of low-moderate income housing in the City, the City Council may agree in writing to pay some or all of the impact fees imposed on a proposed low income housing development by this section from other unrestricted funds of the City. Payment of impact fees on behalf of a fee payer shall be at the discretion of the City Council and may be made pursuant to goals and objectives adopted by the City Council to promote affordable housing.

(l) Administration, Appeals and Updates of determination or decision of Director to City Manager.

(1) Review every seven years. The impact fees described in this section and the administrative procedures of this section shall be reviewed at least once every seven years by the City Manager to ensure that (a) the demand and cost assumptions underlying the impact fees are still valid, (b) the resulting impact fees do not exceed the actual costs of constructing capital facilities that are of the type for which the impact fees are paid and that are required to serve new impact-generating development, (c) the monies collected or to be collected in each impact fee accounts have been and are expected to be spent for capital facilities for which the impact fees were paid, and (d) the capital facilities for which the impact fees are to be used will benefit the new development paying the impact fees.

(2) Appeal.

- i. Any determination or decision made by the Director under this section may be appealed to the City Manager by filing with the City Manager within 30 days of the determination or decision for which the appeal is being filed: (1) a written notice of appeal on a form provided by the city manager, (2) a written explanation of why the appellant feels the determination or decision is in error, and (3) an appeal fee established by the city.
- ii. City manager review. The City Manager shall fix a time and place for hearing the appeal, and shall mail notice of the hearing to the appellant at the address given in the notice of appeal. The hearing shall be conducted at the time and place stated in the notice given by the City Manager. At the hearing, the City Manager shall consider the appeal and either affirm or modify the decision or determination of the Director based on the relevant standards and requirements of this section. The decision of the City Manager shall be final.

(3) Administrative rules. The City Manager and Director, and their respective designees may from time to time establish written administrative rules, not inconsistent with the provisions of this section, to facilitate the implementation of this section. Without limiting the foregoing, the Director is authorized to establish written administrative rules, not inconsistent with the provisions of this section, for use in the determination of the land use category(ies) in the impact fee schedule that is applicable to impact-generating development. All administrative rules adopted pursuant hereto shall be published in written form and copies thereof

maintained in the offices of the community development department and City Clerk. Fee payers shall be advised of any administrative rules adopted pursuant hereto and a copy of such rules shall be made available without charge to such fee payers and other persons requesting a copy thereof.

DRAFT

FEE SCHEDULE

FIRE, POLICE, PARKS AND RECREATION, AND MUNICIPAL FACILITIES IMPACT FEE SCHEDULE

			Jan 1 2020	Jan 1 2021	Jan 1 2022
Land Use Type	Unit	Current Fees	33%	66%	100%
Residential	Single Family				
	Fire	Dwelling	\$0	\$234	\$710
	Police	Dwelling	\$0	\$101	\$305
	Parks and Recreation	Dwelling	\$225	\$680	\$1,605
	Municipal Services	Dwelling	\$0	\$259	\$785
	Multi-Family				
	Fire	Dwelling	\$0	\$154	\$467
	Police	Dwelling	\$0	\$66	\$200
	Parks and Recreation	Dwelling	\$225	\$499	\$1,055
	Municipal Services	Dwelling	\$0	\$170	\$516
Commercial & Industrial	Retail/Commercial				
	Fire	1,000 sf	\$0	\$161	\$489
	Police	1,000 sf	\$0	\$68	\$206
	Parks and Recreation	1,000 sf	\$0	\$0	\$0
	Municipal Services	1,000 sf	\$0	\$155	\$471
	Office/Institutional				
	Fire	1,000 sf	\$0	\$63	\$191
	Police	1,000 sf	\$0	\$27	\$81
	Parks and Recreation	1,000 sf	\$0	\$0	\$0
	Municipal Services	1,000 sf	\$0	\$197	\$598
	Industrial				
	Fire	1,000 sf	\$0	\$22	\$66
	Police	1,000 sf	\$0	\$9	\$28
	Parks and Recreation	1,000 sf	\$0	\$0	\$0
	Municipal Services	1,000 sf	\$0	\$77	\$234
	Warehousing				
	Fire	1,000 sf	\$0	\$11	\$34
	Police	1,000 sf	\$0	\$5	\$14
	Parks and Recreation	1,000 sf	\$0	\$0	\$0
	Municipal Services	1,000 sf	\$0	\$23	\$69

All fees to be adjusted annually commencing January 1, 2023 in accordance with this chapter.

FEE SCHEDULE
TRANSPORATION IMPACT FEE SCHEDULE

Land Use Type	Unit	Jan 1 2020	July 1 2020	Jan 1 2021	July 1 2021	Jan 1 2022	July 1, 2022
		16.7%	33%	50%	67%	83%	100%
All Multi-Family	Dwelling	\$ 1,893	\$ 2,016	\$ 2,140	\$ 2,263	\$ 2,387	\$ 3,252
<1,250 sq.ft of living area	Dwelling	\$ 2,612	\$ 2,670	\$ 2,729	\$ 2,787	\$ 2,845	\$ 3,252
1,250 to 1,649 sq.ft of living area	Dwelling	\$ 2,794	\$ 3,033	\$ 3,273	\$ 3,513	\$ 3,753	\$ 5,430
1,650 to 2,299 sq.ft of living area	Dwelling	\$ 2,868	\$ 3,181	\$ 3,495	\$ 3,809	\$ 4,123	\$ 6,318
2,300 or more of living area	Dwelling	\$ 3,053	\$ 3,552	\$ 4,050	\$ 4,549	\$ 5,048	\$ 8,538
Mobile Home/RV Park	Pad	\$ 1,476	\$ 1,667	\$ 1,859	\$ 2,050	\$ 2,242	\$ 3,583
Hotel/Motel	Room	\$ 2,555	\$ 2,703	\$ 2,851	\$ 2,999	\$ 3,147	\$ 4,183
Retail/Commercial/Restaurant	1,000 sf	\$ 4,527	\$ 4,864	\$ 5,202	\$ 5,540	\$ 5,877	\$ 8,240
Convenience Commercial (gas/drive thru)s	1,000 sf	\$ 7,360	\$ 8,360	\$ 9,361	\$ 10,362	\$ 11,363	\$ 18,365
Office	1,000 sf	\$ 3,436	\$ 3,732	\$ 4,027	\$ 4,323	\$ 4,618	\$ 6,685
Institutional/Public	1,000 sf	\$ 1,194	\$ 1,239	\$ 1,284	\$ 1,329	\$ 1,374	\$ 1,688
Industrial	1,000 sf	\$ 1,882	\$ 1,900	\$ 1,918	\$ 1,935	\$ 1,953	\$ 2,078
Warehouse	1,000 sf	\$ 1,286	\$ 1,244	\$ 1,201	\$ 1,159	\$ 1,117	\$ 1,075

All fees to be adjusted annually commencing January 1, 2023 in accordance with this chapter.

Delete Strikethrough Text, Add Underlined Text [Parks and Open Space]

21.06.020 Public and private parks and open spaces.

(a) ~~Public Parks and Open Space Fee Required.~~

~~(1) For all new residential development requiring rezoning, subdivision and/or planned development approval or site plan review, the owner shall pay into the City escrow fund for parks and open space acquisition and development that amount determined by the City to be necessary or required to defray the cost of and provide parks and open space.~~

~~(2) The dedication of land and/or the payment of the cash equivalent will enable the City to provide parks in the proper location and of the proper size to serve the citizens of the City. This regulation is also adopted to help discourage the proliferation of small parcels, tracts and out lots that are ostensibly created as open space and/or parks but are not sized, maintained or otherwise functional sites.~~

~~(3) For subdivisions, the open space fee is required and payable at the time of platting, when applicable. For all other reviews, the open space fee is required to be paid before the issuance of a planning clearance. For the purposes of this section only, "development" shall mean construction of one or more dwelling unit.~~

~~(4) Private open space and/or recreational area in any development, or outdoor living area required in a multifamily development, shall not be a substitute for the required open space fee, park impact fee or land dedication.~~

~~(5) The parks impact fee shall be as adopted by City Council by resolution.~~

~~(6) The parks impact fee shall not be waived or deferred for any development. The open space fee/dedication is discretionary, as provided for herein.~~

(a) **Open Space Dedication.**

(1) The owner of any residential development of 10 or more lots or dwelling units shall dedicate 10 percent of the gross acreage of the property or the equivalent of 10 percent of the value of the property. The decision as to whether to accept money or land as required by this section shall be made by the Director. Subdivisions with less than 10 lots or residential dwelling units are not required to dedicate 10 percent of the gross acreage of the property or the equivalent of 10 percent of the value of the property unless the developer or owner owns land adjacent to the proposed subdivision, in which case the Planning Commission shall determine the open space requirement.

(2) For any residential development required to provide open space, the owner shall hire an MAI appraiser to appraise the property. For purposes of this requirement, the property

shall be considered the total acreage notwithstanding the fact that the owner may develop or propose to develop the property in filings or phases.

(3) The appraiser's report shall be submitted to the City for purposes of determining fair market value and otherwise determining compliance with this section. The owner shall pay all costs of the appraisal. The owner waives any privilege and/or protection that may exist or be asserted to exist over the details of the appraisal. The appraisal is and shall be considered by the City as an open record under the Colorado Open Records Act.

(4) The required dedication and/or payment shall be subject to and made in accordance with this code. The City Council may accept the dedication of land in lieu of payment so long as the fair market value of the land dedicated to the City is not less than 10 percent of the value of the property.

(5) As part of any project approval, the owner shall dedicate, at no cost to the City, public trails, rights-of-way and waterfront greenbelts/access as designed on and as needed to implement adopted plans of the City. If such dedication is claimed to exceed constitutional standards, the owner shall so inform the City Attorney who, if he agrees, shall ask the City Council to pay a fair share of the value of such dedication or waive all or part of such required dedication.

(6) For creation of a homeowners' association, each subdivision of five or more lots shall record covenants which shall contain provisions for assessments, liens and enforcement of maintenance of all private open space areas and provisions for enforcement by and reimbursement to the City should the homeowners' association fail to maintain the areas properly and the City elects to do so.

(7) For subdivisions, the land dedication or open space fee is required and payable at the time of platting, when applicable. [moved from section 21.06.020(a)(3)]

(8) Private open space and/or recreational area in any development, or outdoor living area required in a multifamily development, shall not be a substitute for the required ~~open space fee, park impact fee or~~ land dedication. [moved from section 21.06.020(a)(4)]

Delete Strikethrough Text, Add Underlined Text [Transportation Impact Payments/Infrastructure Standards]

21.06.010 Infrastructure standards.

(a) General.

(1) Public Improvements. The improvements described in this section must be built by the applicant and constructed in accordance with adopted standards, unless otherwise indicated. ~~The applicant/developer shall either complete construction of all such improvements (in this section "infrastructure") prior to final City approval (such as a subdivision plat) or shall execute a development improvements agreement. [redundant to below]~~ No improvements shall be made until the following required plans, profiles and specifications have been submitted to, and approved by, the City:

- (i) Roads, streets and alleys;
- (ii) Street lights and street signs for all street intersections;
- (iii) Sanitary sewer pipes and facilities;
- (iv) Fire hydrants and water distribution system and storage;
- (v) Storm drainage system;
- (vi) Irrigation system;
- (vii) Right-of-way landscaping;
- (viii) Other improvements and/or facilities as may be required by changing technology and the approval process;
- (ix) Permanent survey reference monuments and monument boxes (see § 38-51-101 C.R.S.).

(2) Guarantee of Public Improvements. No development shall be approved until the City has accepted constructed infrastructure or the developer has executed a development improvements agreement along with adequate security (see GJMC 21.02.070(m)).

(3) No planning clearance for any use or activity shall be issued until minimum street access improvements have been constructed, paid for or adequately secured. [moved from iii, below]

(4) City Participation. The City may elect to require the developer to coordinate construction with the City as required in this chapter. ~~If the developer, in order to provide~~

~~safe access and circulation, must build or improve an arterial or collector street, the City may choose to participate in paying for a portion of the costs of paving these streets, including engineering, site preparation, base and pavement mat.~~

(b) **Streets, Alleys, Trails and Easements.**

(1) **Design Standards.**

(i) Streets, alleys, sidewalks, trails and bike paths shall be designed and constructed in accordance with applicable City standards, ~~including Street and alley layouts shall conform to adopted street plans and other policies, as well as TEDS (GJMC Title 29).~~

(ii) No owner or developer shall propose a site design or plan which could result in the applicant controlling access to a street, alley or right-of-way.

(ii) Easements shall be provided as required for improvements and utilities. Alleys may be used for placement of utilities and infrastructure. ~~may be used.~~

(iv) If needed to provide safe and adequate access and circulation for residents, visitors, users and occupants, the applicant shall provide off-site infrastructure.

(v) Each project with one or more buildings (except detached dwellings) shall provide paved pedestrian walkway/sidewalk connections to nearby rights-of-way. Said connections shall be separate from parking and driveway areas.

~~(vi) Dedications required by subsection (b)(1)(iii) of this section shall be at no cost to the City. Dedications shall not be eligible for or require a refund or TCP credit.~~

(2) **Transportation Capacity Payment (TCP) and Right-of-Way Right of Way Dedication**

(i) A developer shall dedicate to the City such rights-of-way (e.g., streets, sidewalks, trails, bicycle paths and easements) needed to serve the project in accordance with: ~~(A) the adopted Functional Classification Map and Grand Junction Circulation Plan, as amended. from time to time. [moved from iii, above]~~

(ii) Required right-of-way dedications shall be at no cost to the City. ~~[moved from B. below].~~ Such dedications shall not be eligible for transportation impact fee credit.

(3) **Required Improvements.**

(i) The developer shall ~~pay to the City a transportation capacity payment (TCP) and construct right-of-way improvements considered~~ minimum street improvements, local streets, alleys, sidewalks, trails and bike paths ~~as minimum street access~~

~~improvements as well as improvements necessary for the safe ingress and/or egress of traffic to the development, as required by the Code. Director. The type of improvements and required design (eg. Cross sections) shall be those provided in TEDS.~~

~~(a) (ii) The Director may require that the developer pay for and/or construct improvements necessary for the safe ingress and/or egress of traffic to the development. Those improvements are defined as minimum street access improvements. Minimum street improvements shall be those required for the safe ingress and egress of traffic to and from the development and include the design and construction of all streets internal to and fronting a development that are designed as Local or Unclassified in the Grand Junction Circulation Plan, defined by the most recent version of the City's growth and development related street policy and/or TEDS (GJMC Title 29). The growth and development related street policy shall be reviewed by City staff and adopted periodically by Council resolution.~~

~~(b) Any unbuilt street that is designated in the Grand Junction Circulation Plan as a Collector or Arterial and is internal to the development shall be constructed to a Local street standard by the developer.~~

~~a. The City may require the developer based on the City's Circulation Plan and input from the Public Works Director to design and construct the street to a Collector or Arterial standard, thereby requiring the oversizing of streets.~~

~~b. When oversizing is required, the developer may be eligible for a city cost-share agreement in the differential amount between the required Local street improvement and the required Collector or Arterial street improvement~~

~~(c) All streets connecting the existing street network to the development shall be at least 20 feet wide, or as required by the development's traffic demands and the Fire Code, and designed structurally to meet fire equipment load requirements.~~

~~(ii) Commencing January 1, 2021, The developer shall construct improvements necessary for the safe ingress and/or egress of traffic to the development, [moved from above] as required by the Director.~~

~~(d) To achieve safe ingress and/or egress, if turn lanes to and from the development are warranted based on a Traffic Impact Study, the developer will be responsible for the construction of said lanes.~~

~~(e) Where a safety improvement is for the benefit of a development but will benefit other future developments, the developer may request the City to provide a reimbursement agreement for a period of 10 years to recapture a~~

portion of the improvement costs. Based on a proportionate usage of the improvement as determined by an approved traffic study.

~~(ii) The Director may require that the developer pay for and/or construct improvements necessary for the safe ingress and/or egress of traffic to the development. Those improvements are defined as minimum street access improvements. Minimum street access improvements shall be defined by the most recent version of the City's growth and development related street policy and/or TEDS (GJMC Title 29). The growth and development related street policy shall be reviewed by City staff and adopted periodically by Council resolution.~~

~~(iii) No planning clearance for a planning clearance for any use or activity requiring payment of the TCP shall be issued until the TCP has been paid and minimum street access improvements have been constructed, paid for or adequately secured, as determined by the Director. Adequate security shall be that allowed or required for a development improvement agreement (DIA) under GJMC 21.02.070(m).~~

~~(iv) The amount of the TCP shall be as set forth annually by the City Council in its adopted fee resolution. The TCP is minimally subject to annual adjustment for inflation based on the Colorado Department of Transportation's (CDOT) Construction Cost Index, published quarterly by the CDOT (this information can be found at the Internet site of <http://www.coloradodot.info/business/eema/construction-cost-index>).~~

~~(v) The TCP shall be used by the Director to make capital improvements to the transportation facilities in the City in accordance with the City's growth and development related street policy, this section, and other applicable provisions of the Zoning and Development Code.~~

~~(A) To pay debt service on any portion of any current or future general obligation bond or revenue bond issued after July 6, 2004, and used to finance major road system improvements.~~

~~(B) For the reconstruction and replacement of existing roads, the construction of new major road systems and improvements and/or for the payment of reimbursable street expenses (as that term is defined from time to time by the City's growth and development related street policy) that are integral to and that add capacity to the street system.~~

~~(C) Traffic capacity improvements do not include ongoing operational costs or debt service for any past general obligation bond or revenue bond issued prior to July 6, 2004, or any portion of any current or future bond issued after July 6, 2004, and not used to finance major road system improvements.~~

~~(D) Capital spending decisions shall be guided by the principles, among others, that TCP funds shall be used to make capacity and safety improvements but not used to upgrade existing deficiencies except incidentally in the course of making improvements; TCP fund expenditures which provide improvements which are near in time and/or distance to the development from which the funds are collected are preferred over expenditures for improvements which are more distant in time and/or distance.~~

~~(E) No TCP funds shall be used for maintenance.~~

~~(F) TCP funds will be accounted for separately but may be commingled with other funds of the City.~~

~~(G) The Director shall determine when and where TCP funds shall be spent:~~

~~a. As part of the two-year budget process.~~

~~b. As required to keep pace with development.~~

~~(H) The TCP shall not be payable if the Director is shown by clear and convincing evidence that at least one of the following applies:~~

~~a. Alteration or expansion of an existing structure will not create additional trips;~~

~~b. The construction of an accessory structure will not create additional trips produced by the principal building or use of the land. A garage is an example of an accessory structure which does not create additional trips;~~

~~c. The replacement of a destroyed or partially destroyed structure with a new building or structure of the same size and use that does not create additional trips;~~

~~d. A structure is constructed in a development for which a TCP fee has been paid within the prior 84 months or the structure is in a development with respect to which the developer constructed street access improvements and the City accepted such improvements and the warranties have been satisfied.~~

~~(vi) If the type of impact-generating development for which a planning clearance is requested is for the expansion, redevelopment or modification of an existing development, the fee shall be based on the net increase in the fee for the new land use type as compared to the previous land use type.~~

~~(vii) — In the event that the proposed expansion, redevelopment or modification results in a net decrease in the fee for the new use or development as compared to the previous use or development, the developer may apply for a refund of fees previously paid with the consent of the previous person having made the payment and/or constructed the improvements.~~

~~(viii) — A request for a change of use permit that does not propose the expansion of an existing structure shall not require the payment of the TCP. If, however, a request for a change of use permit does propose the expansion of an existing structure, the TCP shall only be applied to the expansion and not the existing structure.~~

~~(ix) — For fees expressed per 1,000 square feet, the square footage shall be determined according to gross floor area, measured from the outside surface of exterior walls and excluding unfinished basements and enclosed parking areas. The fees shall be prorated and assessed based on actual floor area, not on the floor area rounded to the nearest 1,000 square feet.~~

~~(x) — Any claim for credit shall be made not later than the time of application or request for a planning clearance. Any claim not so made shall be deemed waived. Credits shall not be transferable from one project or development to another nor otherwise assignable or transferable.~~

~~(xi) — Minimum street access improvements include street and road improvements required to provide for the safe ingress and egress needs of the development as determined by the Director.~~

~~(A) — Quality of service for any new development and/or for traffic capacity improvements shall be determined by the Director. The Director shall determine the acceptable quality of service taking into consideration existing traffic, streets and proposed development.~~

~~(B) — Required right-of-way dedications shall be at no cost to the City.~~

~~(xii) — Definitions. The following terms and words shall have the meanings set forth for this section:~~

~~(A) — “Average trip length” means the average length of a vehicle trip as determined by the limits of the City, the distance between principal trip generators and as modeled by the City’s, the County’s, the State’s or MPO’s computer program. In the event that the models are inconsistent, the most advantageous to the City shall be used.~~

~~(B) —“Convenience store,” “hotel/motel,” “retail,” and other terms contained in and with the meaning set forth in the Trip Generation Manual.~~

~~(C) —“Lane-mile” means one paved lane of a right-of-way one mile in length and 14 feet in width, including curb and gutter, sidewalk, storm sewers, traffic control devices, earthwork, engineering, and construction management including inspections. The value of right-of-way is not included.~~

~~(D) —“Percentage of new trips” is based on the most current version of the ITE Transportation and Land Development Manual, and the ITE Trip Generation Manual.~~

~~(E) —“Unimproved/under-improved floor area” has the meaning as defined in the adopted building codes.~~

~~(xiii) —Calculation of Fee.~~

~~(A) —Any person who applies for a planning clearance for an impact-generating development shall pay a transportation impact fee in accordance with the most recent fee schedule prior to issuance of a planning clearance. If any credit is due pursuant to subsection (b)(2)(x) of this section, the amount of such credit shall be deducted from the amount of the fee to be paid.~~

~~(B) —If the type of impact-generating development for which a planning clearance is requested is not specified on the fee schedule, then the Director shall determine the fee on the basis of the fee applicable to the most nearly comparable land use on the fee schedule. The Director shall determine comparable land use by the trip generation rates contained in the most current edition of the ITE Trip Generation Manual.~~

~~(C) —In many instances, a building may include secondary or accessory uses to the principal use. For example, in addition to the production of goods, manufacturing facilities usually also have office, warehouse, research and other associated functions. The TCP fee shall generally be assessed based on the principal use. If the applicant can show the Director in writing by clear and convincing evidence that a secondary land use accounts for over 25 percent of the gross floor area of the building and that the secondary use is not assumed in the trip generation for the principal use, then the TCP may be calculated on the separate uses.~~

~~(D) —TCP Fee Calculation Study. At the election of the applicant or upon the request of the Director, for any proposed development activity, for a use that is not on the fee schedule or for which no comparable use can be determined and~~

agreed to by the applicant and the Director or for any proposed development for which the Director concludes the nature, timing or location of the proposed development makes it likely to generate impacts costing substantially more to mitigate than the amount of the fee that would be generated by the use of the fee schedule, a TCP fee calculation study may be performed.

(E) The cost and responsibility for preparation of a fee calculation study shall be determined in advance by the applicant and the Director.

(F) The Director may charge a review fee and/or collect the cost for rendering a decision on such study. The Director's decision on a fee or a fee calculation study may be appealed to the Zoning Board of Appeals in accordance with GJMC 21.02.210(b).

(G) The TCP fee calculation study shall be based on the same formula, quality of service standards and unit costs used in the impact fee study. The fee study report shall document the methodologies and all assumptions.

(H) The TCP fee calculation study shall be calculated according to the following formula:

FEE	=	VMT x NET COST/VMT x RF
VMT	=	TRIPS x % NEW x LENGTH ÷ 2
TRIPS	=	DAILY TRIP ENDS GENERATED BY THE DEVELOPMENT DURING THE WORK WEEK
% NEW	=	PERCENT OF TRIPS THAT ARE PRIMARY, AS OPPOSED TO PASSBY OR DIVERTED-LINK TRIPS
LENGTH	=	AVERAGE LENGTH OF A TRIP ON THE MAJOR ROAD SYSTEM
÷ 2	=	AVOIDS DOUBLE-COUNTING TRIPS FOR ORIGIN AND DESTINATION
NET COST/VMT	=	COST/VMT — CREDIT/VMT
COST/VMT	=	COST/VMC x VMC/VMT
COST/VMC	=	AVERAGE COST TO CREATE A NEW VMC BASED ON HISTORICAL OR PLANNED PROJECTS (FEES SET BY CITY COUNCIL)
VMC/VMT	=	THE SYSTEM-WIDE RATIO OF CAPACITY TO DEMAND IN THE MAJOR ROAD SYSTEM (1.0 ASSUMED)
CREDIT/VMT	=	CREDIT PER VMT, BASED ON REVENUES TO BE GENERATED BY NEW DEVELOPMENT (FEES SET BY CITY COUNCIL)

RF	=	REDUCTION FACTOR ADOPTED BY POLICY (FACTOR SET BY CITY COUNCIL)
----	---	---

~~(f) — A TCP fee calculation study submitted for the purpose of calculating a transportation impact fee may be based on data information and assumptions that are from:~~

~~a. — An accepted standard source of transportation engineering or planning data; or~~

~~b. — A local study on trip characteristics performed by a qualified transportation planner or engineer pursuant to an accepted methodology of transportation planning or engineering that has been approved by the Director.~~

(3) Existing Streets

(i) Existing Local Residential Streets.

(a) General. Many areas of the City were developed in the unincorporated areas of Mesa County without modern urban street and drainage facilities. In many such neighborhoods and areas, the existing local ~~residential~~ streets do not have curbs, gutters or sidewalks. ~~Where structures houses are already built on most or all of such lots, the character of the neighborhood is well established.~~ Given that there are no serious safety or drainage problems associated with these local ~~residential~~ streets, there is no current reason to improve these streets or to install curbs, gutters and/or sidewalks. When an owner in one of these ~~well-established~~ neighborhoods or chooses to subdivide a lot or parcel or an owner in a commercial or industrial area chooses to develop a lot or parcel, unless such improvements are extended off site to connect to a larger system, the new “short runs” of curbing, gutters and/or sidewalks are of little value as drainage facilities or pedestrian ways until some future development or improvement district extends them to other connecting facilities.

~~The Public Works and Planning Director shall determine the acceptable minimum improvements. (G) — If all of the criteria have been met, Instead of constructing requiring these “short run” improvements, the Public Works and Planning owner may apply to the Director to defer full and permanent improvements (“permanent improvements”) by 1. Signing an agreement to form an may, determine the in his or her discretion a signed agreement from the owner an improvement district for the construction of certain required curb(s), gutter(s), and sidewalk(s) and street improvement(s) (“Temporary Improvements”) in lieu of construction at the time of~~

approval of the development application and 2. Constructing, as required by the City, certain temporary curb(s), gutters(s), sidewalk(s), and street improvement(s) required by the City as a condition of approval of the development application. Temporary improvements shall be constructed with the same materials and to the same standards as required of permanent improvements. The agreement to form an improvement district shall be in a form approved by the City Attorney. The agreement shall run with the land and shall be recorded with the Mesa County Clerk and Recorder.

The Director may defer residential street improvements if all of the following criteria are met:

- (A) The development is for three or less residential lots;
- (B) The zoning or existing uses in the block or neighborhood are residential. The Director shall determine the boundaries of the block or neighborhood, based on topography, traffic patterns, and the character of the neighborhood;
- (C) The existing local residential street that provides access to the lots or development meets minimum safety and drainage standards, and has a design use of less than 1,000 average daily traffic ("ADT") based on an assumed typical 10 trips per day per residence and the volume is expected to be less than 1,000 ADT when the neighborhood or block is fully developed;
- (D) At least 80 percent of the lots and tracts in the neighborhood or block are already built upon, so that the street and drainage character is well established;
- (E) If an existing safety hazard or drainage problem, including pedestrian or bicycle traffic, exists and it can be improved or remedied without the street improvements being built; and
- (F) There is at least 250 feet from any point on the development to the nearest existing street improvements (on the same side of the street) that substantially comply with the City standard for similar street improvements.
- ~~(G) If all of the criteria have been met, instead of requiring these "short run" improvements, the Public Works and Planning Director may in his or her discretion accept a signed agreement from the owner to form an improvement district for the construction of curbs, gutters, and sidewalks in lieu of construction. The agreement shall be in a form approved by the City Attorney. The agreement shall run with the land and shall be recorded with the Mesa County Clerk and Recorder.~~ [incorporated into above]

~~(ii) Existing Local Nonresidential Streets. Many commercial and industrial areas of the City were developed in the unincorporated areas of Mesa County without modern urban street and drainage facilities. In many of these areas the existing local nonresidential streets do not have curbs, gutters or sidewalks. Given that there are no serious safety or drainage problems associated with these local nonresidential streets, there is no current reason to improve these streets or to install curbs, gutters and/or sidewalks. When an owner in a commercial or industrial area chooses to develop a lot or parcel, the new "short runs" of curbing, gutters and/or sidewalks are of little value as drainage facilities or pedestrian ways unless the improvements are extended off site to connect to a larger system or until some future development or improvement district extends them to other connecting facilities.~~

~~The Public Works and Planning Director shall determine the acceptable minimum improvements. In order to promote development of infill properties The Director may defer nonresidential street improvements if all of the following criteria have been met:~~

- ~~(A) The development is for a single commercial or industrial lot or parcel that does not create a new lot or parcel;~~
- ~~(B) The proposed development or use of the lot or parcel must be consistent with the allowed uses and requirements of the current zone district;~~
- ~~(C) The lot or parcel size is two acres or less;~~
- ~~(D) The lot or parcel does not have more than 500 feet of frontage on the local nonresidential street;~~
- ~~(E) If an existing safety hazard or drainage problem, including pedestrian or bicycle traffic, exists and it can be improved or remedied without the local nonresidential street improvements being built; and~~
- ~~(F) There is at least 250 feet from any point on the development to the nearest existing street improvements (on the same side of the street) that substantially comply with the City standard for similar local nonresidential street improvements.~~

~~(G) If all of the criteria have been met, instead of requiring these "short run" improvements, the Public Works and Planning Director may in his or her discretion accept a signed agreement from the owner to form an improvement district for the construction of curbs, gutters and sidewalks in lieu of construction. The agreement shall be in a form approved by the City Attorney. The agreement shall run with the land and shall be recorded with the Mesa County Clerk and Recorder.~~

(4) Public Right-of-Way and Private Parking Lot Use.

(i) No structure, fence, sign, parking lot, detention/retention pond, or other temporary or permanent object or structure shall be constructed, maintained, or erected in any portion of any public right-of-way first obtaining a revocable permit has been issued by the City. The City Engineer or other City official may allow traffic control devices, street signs, public notices, utility poles, lines and street banners consistent with this Code. ~~(see this chapter).~~

(ii) No person shall use, store, display or sell any goods, merchandise or any structure without having first obtained a revocable permit, except that this provision shall not be enforced in a manner which limits unreasonably any person's freedom of speech or assembly.

(iii) No commercial vehicle which exceeds one and one-half tons rated carrying capacity shall be parked in a public right-of-way which abuts any residential zone.

(iv) Parking of an RV or any vehicle for more than 72 hours shall not be allowed in a public right-of-way or on any vacant lot.*

~~***Code reviser's note — Ordinance 4833, which amends this subsection (b)(4)(iv), provides, "Sunset Clause. Within sixty days of the third anniversary of the adoption of this ordinance the City Council shall consider the effectiveness of the ordinance at achieving its stated purposes. Without further action by the City Council, the terms and provisions of this ordinance shall expire on the third anniversary of the effective date hereof without subsequent action by the City Council."**~~ [effective date is May 19, 2019]

(6) Street Naming and Addressing System. A street naming system shall be maintained to facilitate the provisions of necessary public services (police, fire, mail), reduce public costs for administration, and provide more efficient movement of traffic. For consistency, this system shall be adhered to on all newly platted, dedicated, or named streets and roads. The Director shall check all new street names for compliance to this system and issue all street addresses. Existing streets and roads not conforming to this system shall be made conforming as the opportunity occurs.



Grand Junction City Council

Regular Session

Item #3.a.

Meeting Date: October 2, 2019

Presented By: Trent Prall, Public Works Director

Department: Public Works - Engineering

Submitted By: Kirsten Armbruster - Project Engineer

Information

SUBJECT:

Change Order for 2019 Monument Road Bicycle Path (Lunch Loop Connector) Trail

RECOMMENDATION:

Staff recommends the City Purchasing Division execute a Construction Contract Change Order with Sorter Construction, Inc of Grand Junction, CO for the 2019 Monument Road Bicycle Path Trail increasing the total amount of the contract to \$2,185,236.19.

EXECUTIVE SUMMARY:

The project to construct a new concrete multi-use path between the existing trail at D Road to the Lunch Loops (Tabeguache) Trailhead along Monument Road, as well as improvements to the trailhead area has encountered a number of challenges primarily associated with extremely wet conditions that have increased costs. Construction began in the middle of May and is proposed for completion in December.

BACKGROUND OR DETAILED INFORMATION:

The Lunch Loop Trail (also referred to as the Monument Road Trail) is a proposed 1.5 mile trail that connects the No Thoroughfare Trail to the Lunch Loop Trailhead. This link will connect users from the Riverfront Trail system to one of the most popular trail systems in Mesa County. The proposed shared use path will extend from D Road and Monument Road, where the No Thoroughfare trail ends, south to the Lunch Loop trailhead. Once complete, the paved trail will help promote walkability and bikeability and connect people of all ages and abilities to trail recreation.

Sorter Construction started construction in May and has encountered a number of challenges. While soils were anticipated to be wet through some portions of the project, much more material was required to provide a stable foundation for the trail. Pumping of subsurface water was also required in order to place the concrete box crossings across No Thoroughfare Wash. Based on pre-bid geotechnical investigations, piles for the bridge abutments were anticipated to extend to between 40 feet and 50 feet in depth. Actual depths reached over 70 feet increasing costs. Casting of the concrete headwalls and retaining walls at the concrete boxes in the wet areas has increased concrete quantities over and above the contract quantities.

The City's Purchasing policy provides for the City Manager up to \$200,000 in authority for change orders. Change Orders approved to date total \$122,943 with an anticipated \$77,057 for extra pile length being approved by the City Manager within the City's policy.

The proposed \$138,873.44 change order is for additional material to stabilize approximately 1450 feet of trail along No Thoroughfare Wash as well as additional concrete required for the culvert retaining walls in the wet areas.

The total amount of the contract will be increased to \$2,185,236.19.

FISCAL IMPACT:

\$2,512,000 Project Budget
\$50,370 Additional revenue from Frog Pond LLC
\$2,562,370 Total Project Budget

\$1,846,362.75 Construction Contract
\$200,000.00 Change Orders approved up to City Manager's Authority
\$138,873.44 This change order
\$2,185,236.19 Proposed Revised Contract

\$326,763.81 Amount remaining in Budget

Remaining budget will be rescoped for additional trailhead improvements to be constructed in 2020.

SUGGESTED MOTION:


I move to authorize the City Purchasing Division to execute a Change Order with Sorter Construction, Inc of Grand Junction, CO for the 2019 Monument Road Bicycle Path Trail in the amount of \$138,873.44.

Attachments


1. 2019 MRT Vicinity Map

2019 Monument Road Bicycle Path Trail

IFB-4618-19-DH



Vicinity Map



Proposed Trail Alignment



Grand Junction City Council

Regular Session

Item #3.b.

Meeting Date: October 2, 2019

Presented By: Kristen Ashbeck, Principal Planner/CDBG Admin

Department: Community Development

Submitted By: Kristen Ashbeck, Principal Planner/CDBG Admin

Information

SUBJECT:

2019 Community Development Block Grant Subrecipient Agreements between the Western Slope Center for Children and HomewardBound of the Grand Valley and the City of Grand Junction

RECOMMENDATION:

Staff recommends approval.

EXECUTIVE SUMMARY:

The Subrecipient Contract formalizes the City's award of CDBG funds to various agencies allocated from the City's 2019 CDBG Program Year as approved by City Council at its June 5, 2019 meeting. The allocation includes the following grants: 1) \$31,500 to the Western Slope Center for Children for improvements to its main program office; 2) \$22,300 to HomewardBound of the Grand Valley for improvements to services provided at the homeless shelter; and 3) \$26,000 to HomewardBound of the Grand Valley to make improvements to exterior client space and air circulation systems at the homeless shelter. The contracts outline the duties and responsibilities of the agencies and ensures that the subrecipients comply with all Federal rules and regulations governing use of the funds.

BACKGROUND OR DETAILED INFORMATION:

CDBG funds are a Department of Housing and Urban Development (HUD) entitlement grant to the City of Grand Junction which became eligible for the funding in 1996. The City has received \$461,255 for the 2019 Program Year and Council approved an amendment to 2018 Action Plan to utilize \$100,000 remaining funds to be allocated

with the 2019 funds for a total allocation of \$561,255. The final funding decision of 17 projects was made by the City Council at its hearing on June 5, 2019. The City's 2019 Program Year began on September 1, 2019 therefore, contracts between the City and the agencies may now be executed.

Western Slope Center for Children Program Office Improvements

WSCC is a nationally accredited child advocacy center with the mission to minimize the pain and trauma for children and their families who are victims of abuse, primarily sexual abuse. WSCC recently acquired a building in order to expand their services located at 2350 G Road. The agency has been remodeling and upgrading the building to better serve clients and meet accreditation requirements. CDBG funds will be used to move and soundproof the direct victim service rooms.

HomewardBound Homeless Shelter Service Improvements

HomewardBound provides overnight emergency shelter for adults and families experiencing homelessness (approximately 1,300 persons). CDBG funds would be used to upgrade the services provided through the purchase of a commercial oven, additional lockers, bunk beds and food for meals served.

HomewardBound Homeless Shelter Exterior Client Space Improvements

HomewardBound is changing check-in procedures for guests to streamline intake and improve safety at the homeless shelter. CDBG funds will be used to provide infrared heaters, lighting and a magnetic gate opener in the exterior client space, provide air curtains at entries to improve health conditions in the shelter and repair the parking lot.

The agencies listed above are considered "subrecipients" to the City. The City will "pass through" a portion of its 2019 Program Year CDBG funds to the agencies but the City remains responsible for the use of these funds. The contracts outline the duties and responsibilities of the agencies and ensures that the subrecipients comply with all Federal rules and regulations governing the use of the funds. The contracts must be approved before the subrecipients may obligate or spend any of the Federal funds. The Subrecipient Agreement with each agency contains the specifics of the projects and how the money will be used by the subrecipients.

FISCAL IMPACT:

Previously approved 2019 CDBG Program Year Budget:

2019 CDBG Allocation:	\$461,255
Remainder Previous Years:	\$100,000
Total Funding Allocated:	\$561,255

Total allocation includes \$25,000 for program administrative costs.

The City will "pass through" a total of \$79,800 of its 2019 Program Year CDBG funds to the agencies listed above.

SUGGESTED MOTION:

I move to authorize the City Manager to sign the Subrecipient Contracts between the City of Grand Junction and the Western Slope Center for Children and HomewardBound of the Grand Valley for funding through the City's 2019 Community Development Block Grant Program Year.

Attachments

1. 2019 CDBG Subrecipient Agreements

**2019 SUBRECIPIENT CONTRACT FOR
CITY OF GRAND JUNCTION
COMMUNITY DEVELOPMENT BLOCK GRANT FUNDS
EXHIBIT A
SCOPE OF SERVICES**

Date Approved: _____

Amount of Grant: \$31,500

Subrecipient: Western Slope Center for Children

Completion Date: August 31, 2020

1. The City agrees to pay the Subrecipient, subject to the subrecipient agreement, this Exhibit and attachment to it, \$31,500 from its 2019 Program Year CDBG Entitlement Funds to make improvements to its main program office located at 2350 G Road, Grand Junction, Colorado ("Property"). Subrecipient is an accredited child advocacy center that provides services to minimize the pain and trauma for children and their families who are victims of abuse, mainly sexual abuse.
2. The Subrecipient certifies that it will meet the CDBG National Objective of low/moderate income benefit (570.202(c)). It shall meet this objective by completing the above-referenced improvements to its main program office.
3. CDBG funds will be used for building modifications to move and soundproof the direct victim service rooms to include: new drywall and sound board added to walls, installation of new doors and doubling the ceiling tiles. The Property is currently owned and operated by Subrecipient which will continue to operate the facility. It is understood that the Amount of the Grant of City CDBG funds shall be used only for the improvements described in this agreement. Costs associated with any other elements of the project shall be paid for by other funding sources obtained by the Subrecipient.
4. This project shall commence upon the full and proper execution of the 2019 Subrecipient Agreement and the completion of all necessary and appropriate state and local licensing, environmental permit review, approval and compliance. The project shall be completed on or before the Completion Date.
5. The total budget for the project is estimated to be \$70,000 as follows:

CDBG: \$31,500
WSCC Building Acquisition, In-Kind and Ongoing Building Upgrades: \$38,500
6. This project will better serve an estimated 400 Subrecipient clients with improved soundproofing for confidentiality and privacy in its victim assistance rooms.
7. The City shall monitor and evaluate the progress and performance of the Subrecipient to assure that the terms of this agreement are met in accordance with City and other applicable monitoring and evaluating criteria and standards. The Subrecipient shall cooperate with the City relating to monitoring, evaluation and inspection and compliance.

_____ Subrecipient

_____ City of Grand Junction

8. The Subrecipient shall provide quarterly financial and performance reports to the City. Reports shall describe the progress of the project, what activities have occurred, what activities are still planned, financial status, compliance with National Objectives and other information as may be required by the City. A final report shall also be submitted when the project is completed.
9. During a period of five (5) years following the Completion Date the use of the Properties improved may not change unless: A) the City determines the new use meets one of the National Objectives of the CDBG Program, and B) the Subrecipient provides affected citizens with reasonable notice and an opportunity to comment on any proposed changes. If the Subrecipient decides, after consultation with affected citizens that it is appropriate to change the use of the Properties to a use which the City determines does not qualify in meeting a CDBG National Objective, the Subrecipient must reimburse the City a prorated share of the Amount of the Grant the City makes to the project. At the end of the five-year period following the project closeout date and thereafter, no City restrictions under this agreement on use of the Properties shall be in effect.
10. The Subrecipient understands that the funds described in the Agreement are received by the City from the U.S. Department of Housing and Urban Development under the Community Development Block Grant Program. The Subrecipient shall meet all City and federal requirements for receiving Community Development Block Grant funds, whether or not such requirements are specifically listed in this Agreement. The Subrecipient shall provide the City with documentation establishing that all local and federal CDBG requirements have been met.
11. A blanket fidelity bond equal to cash advances as referenced in Paragraph V. (E) will not be required as long as no cash advances are made and payment is on a reimbursement basis.
12. A formal project notice will be sent to the Subrecipient once all funds are expended and a final report is received.

_____ Subrecipient
_____ City of Grand Junction

Attachment 1 – Performance Measures

1. Output Measures

A. Total Number of unduplicated clients anticipated to be served by the project during the 12 mo. FY contract: 400

B. Number of unduplicated LMI City residents to be served with grant funds during the 12 mo. FY contract: 180

C. Of the City residents to be served: i) how many will have new or continued access to the service/benefit____; ii) how many will have improved access to the service or benefit: 180? And iii) how many will receive the service or benefit that is improved/no longer substandard____?

2.) Schedule of Performance

Estimate the number of unduplicated City resident to be served per calendar quarter of the 12 mo. FY contract Q1: 45 Q2: 45 Q3: 45 Q4: 45

3) Payment Schedule

During the 12 month FY contract funds will be drawn Q1____Q2: 50% Q3: 50% Q4__

4) Outcome Measures

Activity (select one) __ Senior Service _X_ Youth Service ____ Homeless Service
____ Disabled Service ____ LMI Service ____ Fair Housing Service

Primary Objective (select one) _X_ Create a suitable living environment ____ Provide decent, affordable housing ____ Create economic opportunity (ies)

Primary Outcome Measurement (select one) _X_ Availability/Accessibility ____ Affordability
____ Sustainability

Summarize the means by which outcomes will be tracked, measured and reported.

The types of households or persons served are of special need (presumed benefit) as abuse victims.

The Center's Family Support Advocates track each case from intake and initial forensic interview through to case completion in the criminal justice system. Gathered data provides information for two completely different purposes, each being uniquely accessible: 1) Case-specific and confidential data, restricted to use by WSCC; and 2) Data required by various funding sources – e.g. medical services information the number of mental health counseling sessions, and information regarding Center services and contacts with a victim.

_____ Subrecipient

_____ City of Grand Junction

The Center uses data to track various victim demographics, case status and outcomes; provides for specific agency use of the data (e.g. Grand Junction Police Department); and reports numbers to appropriate local, state and national databases. The Center utilizes an online system (NCAtrak) to track the objective and outcomes for the specific goals as mentioned above.

The Center also uses an Outcome Measurement System (OMS) to get feedback on services provided at and through the Center. This system is a web-based format that includes multiple ways and opportunities for participants to take the surveys. Families that visit the Center are asked to complete an Initial Caregiver Survey during their initial visit or within a few days after their initial visit. Families are then asked to complete a follow-up survey within 60 days of initial visit.

_____ Subrecipient

_____ City of Grand Junction

**2019 SUBRECIPIENT CONTRACT FOR
CITY OF GRAND JUNCTION
COMMUNITY DEVELOPMENT BLOCK GRANT FUNDS
EXHIBIT A
SCOPE OF SERVICES**

Date Approved:

Amount of Grant: \$22,300

Subrecipient: HomewardBound of the Grand Valley

Completion Date: August 31, 2020

1. The City agrees to pay the Subrecipient, subject to the subrecipient agreement, this Exhibit and attachment to it, \$22,300 from its 2019 Program Year CDBG Entitlement Funds to improve services to homeless persons in Grand Junction, Colorado ("Property").
2. The Subrecipient certifies that it will meet the CDBG National Objective of low/moderate income benefit 570.201(c). It shall meet this objective by providing the above-referenced services for the homeless population in Grand Junction, Colorado.
3. This project consists of improving meal services and overnight accommodations for homeless individuals and families including commercial-grade appliances, installation of lockers, and new bunkbeds. It is understood that \$22,300 of City CDBG funds shall be used only for the services described in this agreement. Costs associated with any other elements of the project or above and beyond this amount shall be paid for by other funding sources obtained by the Subrecipient.
4. This project shall commence upon the full and proper execution of the 2019 Subrecipient Agreement and the completion of all necessary and appropriate state and local licensing, environmental permit review, approval and compliance. The project shall be completed on or before the Completion Date.
5. The total budget for the project is estimated to be \$22,300.
6. This project will provide improved services for an estimated total of 1,322 clients.
7. The City shall monitor and evaluate the progress and performance of the Subrecipient to assure that the terms of this agreement are met in accordance with City and other applicable monitoring and evaluating criteria and standards. The Subrecipient shall cooperate with the City relating to monitoring, evaluation and inspection and compliance.

_____ Subrecipient

_____ City of Grand Junction

8. The Subrecipient shall provide quarterly financial and performance reports to the City. Reports shall describe the progress of the project, what activities have occurred, what activities are still planned, financial status, compliance with National Objectives and other information as may be required by the City. A final report shall also be submitted when the project is completed.
9. During a period of five (5) years following the Completion Date the use of the Properties improved may not change unless: A) the City determines the new use meets one of the National Objectives of the CDBG Program, and B) the Subrecipient provides affected citizens with reasonable notice and an opportunity to comment on any proposed changes. If the Subrecipient decides, after consultation with affected citizens that it is appropriate to change the use of the Properties to a use which the City determines does not qualify in meeting a CDBG National Objective, the Subrecipient must reimburse the City a prorated share of the Amount of the Grant the City makes to the project. At the end of the five-year period following the project closeout date and thereafter, no City restrictions under this agreement on use of the Properties shall be in effect.
10. The Subrecipient understands that the funds described in the Agreement are received by the City from the U.S. Department of Housing and Urban Development under the Community Development Block Grant Program. The Subrecipient shall meet all City and federal requirements for receiving Community Development Block Grant funds, whether or not such requirements are specifically listed in this Agreement. The Subrecipient shall provide the City with documentation establishing that all local and federal CDBG requirements have been met.
11. A blanket fidelity bond equal to cash advances as referenced in Paragraph V. (E) will not be required as long as no cash advances are made and payment is on a reimbursement basis.
12. A formal project notice will be sent to the Subrecipient once all funds are expended and a final report is received.

_____ Subrecipient

_____ City of Grand Junction

Attachment 1 – Performance Measures

1. Output Measures

- A. Total Number of unduplicated clients anticipated to be served during the contract: 1,322
- B. Number of unduplicated LMI City residents to be served during the contract: 1,322
- C. Of the City residents to be served, how many will: i) have new or continued access to the service/benefit: ____ 16; ii) have improved access to the service or benefit ____ ; and iii) receive the service or benefit that is improved/no longer substandard: 1,322.

2.) Schedule of Performance

Estimate the number of unduplicated City residents to be served per quarter of the contract:
Q1: 330 Q2: 331 Q3: 330 Q4: 331

3) Payment Schedule

During the contract, funds will be drawn Q1 50% Q2 50% Q3 ____ Q4 ____

4) Outcome Measures

Activity (select one) ____ Senior Service ____ Youth Service X Homeless Service
____ Disabled Service ____ LMI Service ____ Fair Housing Service ____ Housing ____ Other
(insert specify)

Primary Objective (select one) X Create a suitable living environment ____ Provide decent, affordable housing ____ Create economic opportunity(ies)

Primary Outcome Measurement (select one) ____ Availability/Accessibility ____ Affordability
X Sustainability

Summarize the Means by which Outcomes will be Tracked, Measured and Reported

All guests checking in to the shelter for the first time must complete the Homeless Management Information System Intake Packet, which includes a request for income information. HMIS data is updated every six months. The income information recorded is based on self-reporting. If a person is requesting emergency shelter, it is generally accepted that they are homeless and eligible for services.

____ Subrecipient

____ City of Grand Junction

**2019 SUBRECIPIENT CONTRACT FOR
CITY OF GRAND JUNCTION
COMMUNITY DEVELOPMENT BLOCK GRANT FUNDS
EXHIBIT A
SCOPE OF SERVICES**

Date Approved: _____

Amount of Grant: \$26,000

Subrecipient: HomewardBound of the Grand Valley

Completion Date: August 31, 2020

1. The City agrees to pay the Subrecipient, subject to the subrecipient agreement, this Exhibit and attachment to it, \$26,000 from its 2019 Program Year CDBG Entitlement Funds for improvements to exterior and interior client spaces at the community homeless shelter located at 2853 North Avenue, Grand Junction, Colorado ("Property"). Subrecipient provides a variety of services to homeless individuals and families.
2. The Subrecipient certifies that it will meet the CDBG National Objective of low/moderate income benefit (570.202(c)). It shall meet this objective by completing the above-referenced facility improvements for homeless persons in Grand Junction, Colorado.
3. CDBG funds will be used to improve exterior client spaces and improve interior air circulation for health/sanitation concerns at the community homeless shelter located at 2853 North Avenue to include: install infrared heaters, lighting and a magnetic gate opener to improve the outdoor waiting/check-in area and install improved climate control systems for health and sanitation concerns inside the shelter. The Property is currently owned and operated by Subrecipient which will continue to operate the facility. It is understood that the Amount of the Grant of City CDBG funds shall be used only for the improvements described in this agreement. Costs associated with any other elements of the project shall be paid for by other funding sources obtained by the Subrecipient.
4. This project shall commence upon the full and proper execution of the 2019 Subrecipient Agreement and the completion of all necessary and appropriate state and local licensing, environmental permit review, approval and compliance. The project shall be completed on or before the Completion Date.
5. The total budget for the project is estimated to be \$26,000.
6. This project will improve the safety and efficiency and extend the useful life of this facility for the 1,322 clients provided services in the building.
7. The City shall monitor and evaluate the progress and performance of the Subrecipient to assure that the terms of this agreement are met in accordance with City and other applicable monitoring and evaluating criteria and standards. The Subrecipient shall cooperate with the City relating to monitoring, evaluation and inspection and compliance.

_____ Subrecipient

_____ City of Grand Junction

8. The Subrecipient shall provide quarterly financial and performance reports to the City. Reports shall describe the progress of the project, what activities have occurred, what activities are still planned, financial status, compliance with National Objectives and other information as may be required by the City. A final report shall also be submitted when the project is completed.
9. During a period of five (5) years following the Completion Date the use of the Properties improved may not change unless: A) the City determines the new use meets one of the National Objectives of the CDBG Program, and B) the Subrecipient provides affected citizens with reasonable notice and an opportunity to comment on any proposed changes. If the Subrecipient decides, after consultation with affected citizens that it is appropriate to change the use of the Properties to a use which the City determines does not qualify in meeting a CDBG National Objective, the Subrecipient must reimburse the City a prorated share of the Amount of the Grant the City makes to the project. At the end of the five-year period following the project closeout date and thereafter, no City restrictions under this agreement on use of the Properties shall be in effect.
10. The Subrecipient understands that the funds described in the Agreement are received by the City from the U.S. Department of Housing and Urban Development under the Community Development Block Grant Program. The Subrecipient shall meet all City and federal requirements for receiving Community Development Block Grant funds, whether or not such requirements are specifically listed in this Agreement. The Subrecipient shall provide the City with documentation establishing that all local and federal CDBG requirements have been met.
11. A blanket fidelity bond equal to cash advances as referenced in Paragraph V. (E) will not be required as long as no cash advances are made and payment is on a reimbursement basis.
12. A formal project notice will be sent to the Subrecipient once all funds are expended and a final report is received.

_____ Subrecipient

_____ City of Grand Junction

Attachment 1 – Performance Measures

1. Output Measures

A. Total Number of unduplicated clients anticipated to be served by the project during the 12 mo.
FY contract: 1,322

B. Number of unduplicated LMI City residents to be served with grant funds during the 12 mo.
FY contract: 1,322

C. Of the City residents to be served: i) how many will have new or continued access to the service/benefit____; ii) how many will have improved access to the service or benefit: 1,322
And iii) how many will receive the service or benefit that is improved/no longer substandard:
____?

2. Schedule of Performance

Estimate the number of unduplicated City resident to be served per calendar quarter of the 12
month FY contract Q1:330 Q2: 331 Q3: 330 Q4: 331

3. Payment Schedule

During the 12 month FY contract funds will be drawn Q1____ Q2: 50% Q3: 50% Q4____

4. Outcome Measures

Activity (select one) ____ Senior Service ____ Youth Service ☒ Homeless Service
____ Disabled Service ____ LMI Service ____ Fair Housing Service

Primary Objective (select one) ☒ Create a suitable living environment ____ Provide decent,
affordable housing ____ Create economic opportunity (ies)

Primary Outcome Measurement (select one) ____ Availability/Accessibility ____ Affordability
☒ Sustainability

Summarize the Means by which Outcomes will be Tracked, Measured and Reported

All guests checking in to the shelter for the first time must complete the Homeless Management Information System Intake Packet, which includes a request for income information. HMIS data is updated every six months. The income information recorded is based on self-reporting. If a person is requesting emergency shelter, it is generally accepted that they are homeless and eligible for services.

____ Subrecipient

____ City of Grand Junction



Grand Junction City Council

Regular Session

Item #4.a.

Meeting Date: October 2, 2019

Presented By: Greg Caton, City Manager

Department: City Manager's Office

Submitted By: Greg LeBlanc

Information

SUBJECT:

Resolution Adopting the Strategic Plan

RECOMMENDATION:

Staff recommends adoption of the resolution.

EXECUTIVE SUMMARY:

The purpose of this item is to adopt the Strategic Plan.

BACKGROUND OR DETAILED INFORMATION:

The Strategic Plan is a tool used by elected officials and city staff to both guide policy creation and focus efforts during the next two years. The overall purpose of the Strategic Plan is to direct decision-making and budgeting by the City of Grand Junction and to provide guidance to staff. The plan also communicates the City's priorities as set by City Council.

This plan is organized around a framework of four strategic directives. A strategic directive is a high-level priority that is articulated in a way that effectively describes a community priority. Each strategic directive is accompanied by a number of key initiatives. These key initiatives are more specific actions, programs, and ideas designed to aid in achieving the goals set by the strategic directives. These directives include:

- Public Safety
- Planning & Infrastructure

- Diversification of our Economic Base
- Community Building & Engagement

This draft update to the plan added Community Building & Engagement to the list of directives based on the input provided by Council. Council also indicated that the other three directions should remain as they are core to the City's mission.

Four guiding principles accompany the strategic directives. Since they do not represent specific directives or action steps, they are intended to guide the way in which specific strategic directives and initiatives are implemented. These principles include:

- Fiscal Responsibility
- Partnerships & Intergovernmental Relationships
- Communication & Engagement
- Leadership

The previous plan included two guiding principles. Through the strategic planning session, Council indicated that leadership should be added as a guiding principle and that Communication & Engagement should be removed from the list of directives and revised as a guiding principle.

The attached Strategic Plan draft is the final draft for content. Upon approval of the substantive content in the Plan, a final product will be produced with refreshed images.

FISCAL IMPACT:

N/A

SUGGESTED MOTION:

I move to adopt Resolution No. 62-19, a resolution adopting the 2019 Strategic Plan.

Attachments

1. RES-2019STRATPLAN
2. Council Draft_Grand Junction 2019 Strategic Plan Draft

RESOLUTION NO. ____-19

A RESOLUTION ADOPTING THE 2019 STRATEGIC PLAN

Recitals:

In 2017 the City Council adopted a Strategic Plan, a plan that carefully and diligently considered and formulated a direction for the City to continue to grow and prosper. That plan was successfully implemented and served the City well. In 2019, following the seating of three new Councilmembers, the City Council reviewed, revised and renewed the Plan for 2019 and beyond.

The 2019 Plan continues, with some refinement, the four strategic directives of the prior plan and with its adoption and implementation will carry on the successes that resulted from the prior plan. By and with this resolution the City Council adopts, approves and endorses the 2019 Strategic Plan ("Strategic Plan.")

The strategic directives of the Strategic Plan, which are the cornerstones for developing and implementing high level and high priority policy for the City are, **Diversification of the City's economic base**, as well as a continuing emphasis on **Planning and Infrastructure, Public Safety and Community Building and Engagement**.

In addition to the strategic directives the Strategic Plan include four guiding principles, which provide overarching direction for implementation of the Plan. Those guiding principles are **Partnership and Intergovernmental Relationships, Fiscal Responsibility, Communication and Leadership**. The guiding principles do not provide specific mandates or actions but instead are intended to guide the way in which the specific strategic directives and initiatives are implemented

The four strategic directives, together with the four guiding principles are realized by a number of key initiatives. Those initiatives describe more specific actions, programs and ideas designed to bring about the accomplishment of the strategic directives.

The City Council and City staff will use the Strategic Plan to both guide policy creation and focus efforts during the next two years. The overall purpose of the Strategic Plan is to inform and direct decision-making and budgeting by and for the City.

The Strategic Plan communicates the City's priorities and focus; each strategic directive is designed to highlight the priorities, whether as a strength or weakness, of the City and provide an administrative structure for the Council and staff to attend to those priorities in a defined, deliberate structure. While specific actions are not outlined in the Strategic Plan, City staff will implement, track and regularly report on the progress of the implementation of the Plan.

NOW, THEREFORE, BE IT HEREBY RESOLVED BY THE CITY COUNCIL OF THE CITY OF GRAND JUNCTION THAT:

The 2019 Strategic Plan is hereby approved and adopted as generally and specifically provided therein and in accordance with this resolution.

PASSED AND APPROVED this 2nd day of October 2019.

J. Merrick Taggart
President of the Council

ATTEST:

Wanda Winkelmann
City Clerk

GRAND JUNCTION STRATEGIC PLAN



PC: James Alsop



PC: Visit Grand Junction

September 2019

Introduction

The central purpose of this undertaking was to provide the City of Grand Junction with a tool that can be used during the next two years by elected officials and city staff to guide goal setting and strategy. This plan incorporates the priorities identified as most important by City Council. To truly be effective, this plan must become part of how elected officials and city staff operate and think about programs and services. The test of this plan's usefulness will be defined by how effective it is in guiding decisions and how it aids in measuring success.

In the process of examining this strategic plan, the reader will encounter various terms and phrases associated with key elements of the plan. It is important that we place an understanding of the strategic plan within the context of what these elements are intended to contribute.

Guiding Principles

Four guiding principles have been added to the plan. They do not represent specific directives or action steps but are intended instead to guide the way in which specific strategic directives and initiatives are implemented.

Strategic Directives

This plan contains four strategic directives. A strategic directive is a high-level priority that is articulated in a way that effectively describes a community priority and is not intended to describe specific initiatives, ideas, programs, or services. It merely summarizes what we believe is most important.

Key Initiatives

Each strategic directive is accompanied by a number of key initiatives which assist in bringing the directive to the level of application. In other words, key initiatives are more specific actions, programs, and ideas designed to bring about the realization of the strategic directives. We consider the directive to be the destination and the initiatives represent the path that will enable us to arrive at our destination.

What Does Success Look Like?

This section of each strategic directive is designed to describe some of the key indicators we will look to in evaluating the success of that directive. Specific actions are not outlined in this document, and city staff have internal mechanisms that will be used to implement this plan.

Guiding Principles

Partnerships & Intergovernmental Relationships

While some cities may be able to “go it alone” and find success, the City of Grand Junction must effectively partner with both public and private agencies. As a regional hub with urban challenges unique to a community of our size and composition, it will take collective action to succeed in advancing our most important initiatives. Partnerships may include, but are not limited to, organizations or agencies in these areas: government, education, economic development, transportation, and business development.

We view partnership in its broadest sense and not merely through the lens of delivering municipal services. Partnership with a common purpose is the key to success with public and private collaboration. Whether evaluating opportunities for shared services, partnering for economic development, or creating a shared vision for the future of our community, we recognize that our residents will be best served as we work together with other organizations to find solutions. We take every opportunity to celebrate past successful partnerships to build momentum for future collaboration.

Fiscal Responsibility

The foundation of effective local governance is trust. To continue to build the trust placed in us by our citizens, we must be responsible stewards of the resources entrusted to our care. In a world of scarce resources, we must be effective in prioritizing our spending to focus on the things that citizens have identified as most important.

As we establish plans and priorities, we do so with an eye to the future. It is not enough to merely find a way to fund a new project or amenity. We must also ensure that we are planning for long-term ongoing operations and maintenance with each item that we prioritize.

Communication

We want to be a part of a community where residents are well informed about matters of local government and their involvement is encouraged. Expectations have changed over the years, and we as a City must adapt to share helpful information with our residents and stakeholders through channels that meet them where they are.

Communication is a two-way street. It is not enough for us to proclaim what we are doing and expect citizens to listen and follow along. We need to create channels for citizens to approach the city and communicate their priorities. This builds trust and ensures we continue to focus limited resources on our community’s highest priorities.

Leadership

Grand Junction was founded by innovative leaders, ready to lead the way to a new future. Our city continues in that tradition of leadership today. We are not content to wait around for the future, but rather desire to actively shape it. Our City holds a key position in the region. We must be a driving force in issues of regional importance and play a leading role in the growth occurring on the Western Slope. We will do this by setting an example of how local government should operate – in our conduct, in our words, and in our ideas. The status quo will not satisfy us, nor will it work, as we continue to push ourselves outside of our comfort zone to be innovative leaders.

Strategic Directives

1. Public Safety

Grand Junction is geographically isolated from other population centers which creates unique public safety needs, especially for a community of our size. We are a stand-alone regional hub with urban challenges not found in other communities on the Western Slope. It is critical that we ensure our public safety efforts meet current needs as well as anticipate and adapt to future public safety challenges and opportunities.

This will require us to develop a framework to evaluate effective levels of service. To do this, we will consider modeling communities that share similar challenges. Because of our unique needs, we will also analyze best practices from other agencies and assess current workloads to develop an effective staffing model. In the spirit of partnership with surrounding communities, we should also evaluate regionalization opportunities. This will include a review of our current mutual aid agreements.

Lastly, we must establish clear policy direction for new funding. With the passage of a First Responder Sales Tax (Measure 2B) to fund the expansion of our police and fire emergency services, we must continue to ensure that policies and funding mechanisms align with our public safety model and service delivery standards. Over the coming years, we will move steadily to fill open positions at a pace that allows us to make best use of the resources while maintaining a high level of professionalism in our public safety departments.



Strategic Directives

1. Public Safety

KEY INITIATIVES:

- Establish community policing efforts as the heart of our service delivery function with an emphasis on proactive policing efforts
- Promote safety in our public spaces by working with community partners to address vagrancy, homelessness, and vandalism
- Plan for, build, and staff essential public safety infrastructure
- Active enforcement of city codes to improve the physical appearance of our community
- Community risk reduction through prevention and education efforts

SUCCESS METRICS:

- Consistent staffing levels appropriate for community needs through enhanced recruiting and retention efforts
- Response Times – meeting or exceeding national standards
- Feeling of safety – satisfaction survey results for both perceptions of safety and aesthetics
- Continue implementation of community education efforts addressing vagrancy




Strategic Directives

2. Planning & Infrastructure

To fully understand the values, vision and needs of the community, the City must seek robust input from the community and distill that input into a plan. This effort is being undertaken in the Comprehensive Plan 2020: One Grand Junction, a plan that will provide guidance to the City in all that we do for the next 10+ years. Further, to support future growth in our city, we must make plans to expand infrastructure in areas where that growth is most likely to occur. In order to ensure that we are making the right infrastructure investments, the Comprehensive plan adopted in 2009, will be reviewed and updated.

A core function of the City is to maintain and expand infrastructure as needed for future growth. The City will allocate fiscal resources consistent with the Comprehensive Plan and will ensure existing infrastructure is adequately maintained. The City will continue to evaluate the current state of its infrastructure, and actively work with funding partners to implement maintenance plans and construction of core infrastructure.

Infrastructure is defined as the fundamental facilities and systems serving the city such as water and sewer lines, roads, and sidewalks. Given the potential for significant growth in the community, we must also focus on planning for future infrastructure needs that can support quality of life, economic growth, and core municipal service delivery. Many people that have moved to this area have done so and chosen to stay because of the unique quality of life we enjoy. Careful planning will ensure that our lifestyle will be both preserved and enhanced. Building and maintaining infrastructure can be a key ingredient to both attracting businesses as well as attracting and retaining workforce talent.



PC: GJVCB

Strategic Directives

2. Planning & Infrastructure

KEY INITIATIVES:

- Secure funding sources for maintenance of existing infrastructure, and building of essential new infrastructure
- Incorporate sustainable practices into City operations and encourage citizens to embrace sustainability practices
- Evaluate, construct and maintain a transportation system that supports citizen needs, including multi-modal transportation (cyclists, pedestrians, etc.)
- Develop, adopt, and implement community plans (parks, circulation, transportation, Comprehensive)
- Establish sustainable annexation criteria for new developments outside of the city and revise approach for annexing areas that are not quickly urbanizing
- Establish indices to monitor the condition of infrastructure assets (pavement condition, etc.) and build plans for maintenance of these assets

SUCCESS METRICS:

- Adoption of Comprehensive Plan 2020
- Completion and adoption of community plans
- Funding levels for needed infrastructure projects
- Substantial progress on riverfront developments in two years
- Infrastructure condition indices
- Become an AARP Age-Friendly Community




PC: Sharon Jungert

Strategic Directives

3. Diversification of our Economic Base

Throughout our history, we have experienced boom and bust cycles. In preceding decades, the boom and bust has tied to the fluctuations of volatile energy prices. Population in the Grand Valley has now grown to the point where greater economic diversity is not only possible, but imperative. We have begun to take proactive steps to diversify our economic base to moderate the peaks and valleys in economic activity that we have experienced in the past. We must continue those efforts. Because economic development is driven by factors well beyond the core services and functions of the city, we have made the choice to collaborate with other organizations and outsource the majority of our economic development activities. However, due to the importance of economic development to our community, ongoing support and monitoring of these activities is critical.



PC: Allison Blevins

Strategic Directives

3. Diversification of our Economic Base

KEY INITIATIVES:

- Develop catalytic development projects such as Riverfront at Las Colonias and Riverfront at Dos Rios
- Build City Place Brand
- Continue partnerships with Economic Development partners and encourage regular reporting
- Continue to support the economic development efforts of Visit Grand Junction
- Expand student employment opportunities from Colorado Mesa University (CMU)
- Partner with Economic Development organizations to develop and implement plans of action
- Continue progress on a Foreign Trade Zone

SUCCESS METRICS:

- Job growth and employment rates
- Wage growth to close the gap with the state average
- Development, expansion, and retention of business
- Increased sales tax revenue
- Increased number of visitors as evidenced by lodging tax revenue
- Square feet developed in catalytic development projects
- Industry specific job growth - number of new business licenses and/or positions in manufacturing, tech, and other select industries
- Occupancy rate of commercial developments



PC: GJVCB

Strategic Directives

4. Community Building & Engagement

Bring People Together through Great Public Spaces – There is perhaps no greater way to build a community than by bringing people together for shared experiences. While the city is not the primary source of these experiences, we play a significant role in creating spaces where these experiences happen. Public parks, art exhibits, sporting competitions, and other public community events bring together individuals from every age, ethnicity, income level and background. Such activities build pride in our community, encourage volunteerism, and create a feeling of connectedness. We will invest in the resources that provide space for these shared experiences for our residents: establishing arts and culture, improving and building public parks, and hosting quality events for the public to enjoy.

Visibility & Engagement – To honor the trust placed in us by our citizens, we must continue to expand transparent sharing of information. We will communicate and celebrate our significant achievements and also share how we are actively learning from our mistakes. We will strive to ensure the accuracy of any information produced and distributed by the City. Lastly, communication is a two-way street. We need to create more opportunities for engagement with citizens. Rather than wait at City Hall to hear from our residents, we will look at ways to diversify our public outreach and expand our channels of two-way communication and engagement with members of our community.



PC: Allison Blevins

Strategic Directives


4. Community Building & Engagement

KEY INITIATIVES:

- Plan & develop public spaces and places to serve broad, yet diverse uses
- Increase community engagement in public processes by diversifying methods of public outreach
- Engage in public relations and place-branding campaign, involving the community in the process
- Increase use of and diversify citizen engagement platforms (social media, email, public meetings, etc.)
- Plan specific events with cross-generational appeal
- Rebuild the city's neighborhood program
- Partner in the success of the Downtown Creative District
- Support recruitment of sporting events through Greater Grand Junction Sports Commission

SUCCESS METRICS:

- Attendance levels for City-sponsored community events
- Participation levels in comprehensive planning process
- Social media engagement metrics
- Community satisfaction from citizen surveys
- Usage rates of parks and other public open space
- Enhancement of existing and creation of new public spaces



PC: Callie Berkson



Grand Junction City Council

Regular Session

Item #4.b.

Meeting Date: October 2, 2019

Presented By: Ken Sherbenou, Parks and Recreation Director

Department: Parks and Recreation

Submitted By: Ken Sherbenou, Parks and Recreation Director

Information

SUBJECT:

Resolution Authorizing the City Manager to Submit a Grant Request to Great Outdoors Colorado (GOCO) for a Local Park and Outdoor Recreation Grant for Land Acquisition of Approximately 21 Acres along Monument Road on Behalf of the Mesa County Land Conservancy, Inc. with the Trade Name of Colorado West Land Trust

RECOMMENDATION:

Staff recommends adoption of the resolution.

EXECUTIVE SUMMARY:

The City of Grand Junction and the Colorado West Land Trust (CWLT, formerly the Mesa County Land Conservancy) have a long history of collaboration that has and continues to improve the trail system, especially in the Lunch Loop Trail area. Most recently, a \$1.5M Great Outdoors Colorado (GOCO) Connect Grant was earned in 2018 to connect the trail system to downtown Grand Junction on 10' bike path mostly separated from traffic. This connection is on the north side of Lunch Loop and connects to Downtown, and construction is nearing completion. In this Local Park and Outdoor Recreation (LPOR) grant request, the City and the CWLT propose to improve the connection on the south end, to connect the trail to the many nearby neighborhoods.

Per the constitutional amendment that created GOCO, a non-profit must partner with an eligible entity, such as a local government to pursue a GOCO grant. This project does not compete with any other City of Grand Junction request. This resolution will provide authorization for a \$156,920 grant request to GOCO for acquisition of approximately twenty-one acres of land included within the parcel at 2312 Monument

Road Trail. The total budget is \$287,920 and the CWLT has requested a \$30,000 contribution. This matching contribution is in the 2020 proposed budget that is balanced and will be presented to Council soon. Along with a match of \$101,000 for the CWLT, this makes the match 46%, which is competitive.

BACKGROUND OR DETAILED INFORMATION:

The Colorado West Land Trust is a private, non-profit land conservation Corporation that has requested sponsorship from the City of Grand Junction for acquisition of approximately twenty-one acres of land included with the parcel at 2312 Monument Road Trail. The owner plans to subdivide the parcel in the near future creating a parcel along Monument Road.

The construction of the Lunch Loop Connector Trail, connecting the Riverfront to the Lunch Loop Trailhead along the Monument Corridor is expected to be completed by the end of 2019. Since 2014, when the Colorado West Land Trust and the City of Grand Junction participated in a visioning for the Monument Corridor, the Land Trust, the City of Grand Junction, Mesa County, and the BLM staff members have worked to determine the best possible trail alignment to connect the Lunch Loop Trailhead to the S. Camp paved trail. The ultimate goal has been to connect the Riverfront Trail along the Monument Corridor to the S. Camp paved trail in order to complete a 10-mile bike/pedestrian loop that connects some of our areas finest outdoor assets to neighborhoods and the downtown.

The trail alignment selected lies along No Thoroughfare Wash on the south side of Monument Road and requires the acquisition of approximately 20 acres as well as the acquisition of trail-width (20 feet) rights of way from three other landowners. Colorado West Land Trust has negotiated a fair market value with the owner of the 20 acres, requiring a minor subdivision of the property at 2312 Monument Road. CWLT will work with the landowner to direct the minor subdivision. This request is for authorizing the City's grant application to GOCO to purchase the 20 acres, with CWLT as the partner applicant. The grant is due on October 24th, and, if awarded, will issue funds in March of 2020. Once the purchase is complete, CWLT will place a conservation easement on the property, and transfer to the City of Grand Junction for public open space.

The construction of the Lunch Loop Connector Trail, connecting the Riverfront to the Lunch Loop Trailhead along the Monument Corridor is expected to be completed by the end of 2019. Since 2014, when the Colorado West Land Trust and the City of Grand Junction participated in a visioning for the Monument Corridor, the Land Trust, the City of Grand Junction, Mesa County, and the BLM staff members have worked to determine the best possible trail alignment to connect the Lunch Loop Trailhead to the S. Camp paved trail. The ultimate goal has been to connect the Riverfront Trail along the Monument Corridor to the S. Camp paved trail in order to complete a 10-mile bike/pedestrian loop that connects some of our areas finest outdoor assets to

neighborhoods and the downtown.

The trail alignment selected lies along No Thoroughfare Wash on the south side of Monument Road and requires the acquisition of approximately 20 acres as well as the acquisition of trail-width (20 feet) rights of way from three other landowners. Colorado West Land Trust has negotiated a fair market value with the owner of the 20 acres, requiring a minor subdivision of the property at 2312 Monument Road. CWLT will work with the landowner to direct the minor subdivision. This request is for authorizing the City's grant application to GOCO to purchase the 20 acres, with CWLT as the partner applicant. The grant is due on October 24th, and, if awarded, will issue funds in March of 2020. Once the purchase is complete, CWLT will place a conservation easement on the property, and transfer to the City of Grand Junction for public open space.

FISCAL IMPACT:

Total project cost is \$287,920 with a GOCO Grant request of \$159,920. The City's cash match is \$30,000 and is derived from the Conservation Trust Funds and is planned in the 2020 CIP Budget.

SUGGESTED MOTION:

I move to adopt Resolution No. 63-19, a resolution supporting the application for a Local Park and Outdoor Recreation Grant from the State Board of the Great Outdoors Colorado Trust Fund for land acquisition of approximately 21 acres of land included within the parcel at 2312 Monument Road for the ongoing development of the Monument Road Trail.

Attachments

1. Resolution - Mesa Land Conservancy - 090619
2. Mesa Land Conservancy Inc. IGA - 090619 Lunch Loop Acquisition Oct 2019

CITY OF GRAND JUNCTIN, COLORADO

RESOLUTION NO. __-19

**A RESOLUTION SUPPORTING THE APPLICATION FOR A LOCAL PARK AND
OUTDOOR REREATION GRANT FROM THE STATE BOARD OF THE GREAT
OUTDOORS COLORADO TRUST FUND FOR LAND ACQUISITION OF
APPROXIMATELY 21 ACRES OF LAND INCLUDED WITHIN THE PARCEL AT 2312
MONUMENT ROAD FOR THE ONGOING DEVELOPMENT OF THE MONUMENT
ROAD TRAIL**

Recitals:

Mesa County Land Conservancy, Inc., with the trade name of Colorado West Land Trust, a private, non-profit land conservation corporation ("Trust"), requested sponsorship from the City of Grand Junction for acquisition of approximately twenty-one acres of land included within the parcel at 2312 Monument Road in the City of Grand Junction for the purpose of ongoing trail development of the Monument Road Trail ("Project").

The Project plan depends in significant part on receipt of funding in an amount up to \$156,920 from The Great Outdoors Colorado ("GOCO") grant. The Trust is an ineligible recipient of the grant and desires the City to be the conduit through which the Trust, and ultimately the City, will benefit from the Grant. In order for the grant application to be made, the City must agree to serve as the applicant and grantee of the grant. The intent of the Trust is to place a conservation easement on the property and eventually deed it to the City as open space.

After due consideration, the City Council of the City of Grand Junction supports the Project and desires the City to assist the Trust's efforts to submit a GOCO grant application to obtain the necessary funding for the Project, and if the grant is awarded, to enter into such further agreements as are necessary and proper to obtain and pass through the grant funds to the Trust and complete the Project.

**NOW, THEREFORE, BE IT HEREBY RESOLVED BY THE CITY COUNCIL OF THE
CITY OF GRAND JUNCTION THAT:**

- 1: The City Council of the City of Grand Junction strongly supports the application to GOCO to obtain funds needed to complete the Project. The City Manager is authorized and directed to work with the Trust to review, finalize and timely submit such GOCO grant application.
- 2: If the grant is awarded, the City Council of the City of Grand Junction strongly supports the completion of the Project, and authorizes the City Manager to sign an appropriate grant agreement on behalf of the City as grantee of the GOCO grant.

3: If the grant is awarded, the City Council of the City of Grand Junction further authorizes the City Manager to negotiate and sign an intergovernmental agreement between the City and the Trust regarding the GOCO grant. Such agreement shall provide for, but may not be limited to—

- a. Pass through to the Trust of GOCO grant funds received by the City for the Project;
- b. The Trust's assumption of the City's obligations under the GOCO grant agreement,
- c. Confirmation that the Trust has raised and set aside sufficient funds to satisfy GOCO's matching funds requirement(s) for the Project; and,
- d. The Trust's payment of acquisition costs as they come due.

6: This Resolution shall be in full force and effect from and after its passage and adoption.

Passed and adopted this ____ day of _____, 2019.

Mayor, Grand Junction City Council

ATTEST:

Wanda Winkelmann
City Clerk

INTERGOVERNMENTAL AGREEMENT

THIS INTERGOVERNMENTAL AGREEMENT (“Agreement”), is made and entered into this _____ day of October, 2019, by and between THE CITY OF GRAND JUNCTION, a Colorado home rule municipality, hereinafter called “City,” and MESA COUNTY LAND CONSERVANCY, INC., trade name of Colorado West Land Trust, a nonprofit corporation, hereinafter called “Trust;” collectively the “Parties.”

R E C I T A L S

A. The real property known as 2312 Monument Road situated in Mesa County, Colorado, is owned by 2312 Monument Road LLC. Owner plans to subdivide the parcel in the near future, creating a parcel of approximately twenty-one acres along Monument Road that will become the real property known as the “Property” for purposes of this agreement.

B. Trust requests sponsorship from the City on application for a Local Park and Outdoor Recreation Grant from the State Board of the Great Outdoors Trust Fund for land acquisition of Property for ongoing trail development. The intent of Trust is to place a conservation easement on the Property and eventually deed all rights to such Property to City to be used as open space.

C. Pursuant to City Council Resolution No. _____ entitled “A Resolution Supporting The Application For a Local Park and Outdoor Recreation Grant From The State Board of the Great Outdoors Colorado Trust Fund For Land Acquisition of Approximately 21 Acres of Land Included Within The Parcel at 2312 Monument Road For the Ongoing Development of the Monument Road Trail,” the City applied for a grant in an amount up to \$156,920 (the “Grant”) from The State Board of the Great Outdoors Colorado Trust Fund (“GOCO”) for the purchase of the Property for trail development (the “Project”); and

D. The Trust is an ineligible recipient of the Grant and the Parties desire the City to be the conduit through which the Trust, and ultimately the City, will receive the benefit of the Grant; and

E. In order to obtain and pass through the grant funds to the Trust and complete the Project, the City must complete and sign a grant agreement with GOCO in substantially the form attached to this Agreement as Exhibit “A” (the “Grant Agreement”); and

F. The City and the Trust desire to enter into this Agreement to set forth their agreement concerning the terms and conditions of the City's execution of the Grant Agreement and pass-through of the Grant funds to the Trust and to clarify the parties' rights and obligations regarding the Project and the Grant Agreement; and

G. An intergovernmental agreement is authorized pursuant to Section 18, Article XIV of the Colorado Constitution, Section 29-1-203, C.R.S., Section 22-32-110(1)(f), C.R.S., and other applicable laws.

NOW, THEREFORE, in consideration of the mutual covenants and conditions contained herein and other valuable consideration the sufficiency of which is acknowledged, the Parties agree as follows:

1. The Trust hereby covenants and agrees to assume all of the City's obligations under the Grant Agreement, including, but not limited to, contribution of the matching cash and/or in-kind contributions up to \$101,000 for the Project as reflected in the Project budget and as required by GOCO policy, and shall provide such evidence of the same as GOCO may require.

2. In furtherance of this Agreement, the Trust shall cause the land acquisition to be limited to the Property as described in the Project Application submitted to GOCO in connection with the Grant (herein "Improvements"). After acquisition of the Property and completion of the Project, Trust agrees to transfer all legal rights in Property by deed to City. The City does not and shall not be required to assume any obligation to the Trust to construct, operate, or maintain the Improvements encompassed within the Project or contemplated by the Grant. The Trust and the City further agree that the City will provide up to \$30,000 under the Grant and/or the Grant Agreement with respect to construction of the Project. The Trust shall be responsible for paying all Project construction costs as they come due. City hereby covenants and agrees to submit to GOCO reimbursement requests or progress reports, together with any supporting documentation, prepared or provided by the Trust for funds expended on the Project and to remit to the Trust the Grant proceeds, including any Grant progress payments it receives prior to completion of the Project, upon receipt thereof from GOCO pursuant to the Grant Agreement until the full amount of the Grant has been received and remitted to the Trust. In the event the Grant Agreement sets forth a different method for distribution of Grant funds, the parties agree to abide by the terms of the Grant Agreement.

3. The City shall use its best efforts to fulfill all of the conditions precedent to obtaining the Grant, including execution and delivery of the Grant Agreement. The Trust will cooperate with the City and provide all documents necessary for the City to fulfill the conditions precedent, if any.

4. Subject to annual appropriation, the Trust will, at its own expense, operate, repair and maintain the Project Improvements to the same standards observed by the Trust in maintenance and operation of other Trust outdoor facilities for the useful life of the Improvements. Upon transfer of Property from Trust to City by deed, the City will assume, at its own expense, operate, repair and maintain the Project to the same standards observed by the City in maintenance and operation of other City outdoor facilities for the useful life of the Improvements.

5. The City will assist with the administration of the Grant, including but not limited to preparing and submitting any and all reports required by the Grant Agreement.

6. The Trust agrees to involve a representative from the City's Parks and Recreation Department in the decision-making process involving alterations, if any, to the Project that materially affect the City's obligations under the Grant Agreement.

7. This Agreement shall not terminate until the Grant Agreement is fully performed and satisfied as required by the Grant Agreement. Upon termination, the Improvements shall be and remain the property of the Trust.

8. Should either party fail to substantially perform its obligations hereunder, the other party may give written notice of the exact nature of the default. The party in default shall correct the default or provide written schedule of when and how the default will be corrected within fifteen (15) days from receiving such notice. Failure to perform shall entitle the non-defaulting party to pursue any other remedy in law or equity to enforce the terms hereof.

9. Nothing contained herein shall be construed as a limitation upon the Trust's right to make additions to the Property or any portion thereof, so long as such is done as required by the Grant Agreement and the changes do not materially interfere with the public's right to use the Improvements as specified in Paragraph 5 above.

10. This Agreement shall be binding upon and inure to the benefit of the successors in interest of the respective parties.

11. The City's rights and obligations hereunder may not be assigned without the District's written consent, and any attempt to do so will be deemed a default by the City for failure to substantially perform a material covenant and obligation hereunder.

12. The Trust's rights and obligations hereunder may not be assigned without the City's written consent, and any attempt to do so will be deemed a default by the Trust for failure to substantially perform a material covenant and obligation hereunder.

13. General Provisions.

a. Entire Agreement – Merger- Modifications – No Waiver. This Agreement contains the entire understanding of the Parties and is intended as a complete and final expression of their agreement and of the terms thereof. All prior statements and representations, including those which may have been negligently made, and all prior understandings and agreements are merged herein. The Parties specifically waive any claims they may have for negligent misrepresentations in the formation of this Agreement. This Agreement shall not be modified except by a writing signed by the Parties hereto or their duly authorized representatives. No waiver by either Party of any default shall be deemed a waiver of any subsequent default.

b. Time of the Essence. Time is of the essence of this Agreement, and in the event of the failure of either Party to perform any term or condition hereof, including but not limited to terms pertaining to delivery and payment, such party shall be in default and the other party shall be entitled to all remedies provided by law and the terms of this Agreement.

c. Governing Law. This Agreement shall be governed by and construed in accordance with the laws of the City of Grand Junction, State of Colorado. Venue for all actions connected herewith shall be in Mesa County, State of Colorado.

d. Invalidity. If any clause or provision of this Agreement be determined to be illegal, invalid or unenforceable under present or future laws, then it is the intention of the parties that the other terms and provisions of this Agreement shall not be affected thereby.

e. Captions. Article titles and paragraph titles or captions contained in this Agreement are inserted only as a matter of convenience and for reference and in no way define, limit, extend or describe the scope of this Agreement or the intent of any provisions thereof.

f. Pronouns. All pronouns and any variations thereof shall be deemed to refer to the masculine, feminine or neuter, singular or plural, as the identity of the person, persons, entity or entities may require.

g. Attorney's fees. If, on account of any breach or default by a Party hereto under the terms and conditions hereof, any judicial proceeding shall be commenced to enforce any provision(s) of this Agreement, the substantially prevailing party shall (in addition to other relief granted) be awarded all reasonable attorneys' fees and costs resulting from such litigation to the extent permitted by law.

h. No Third Party Beneficiaries. This Agreement does not create any rights in any individual or entity not a party to this Agreement.

i. TABOR. No provision of this Agreement shall be construed or interpreted: 1) to directly or indirectly obligate either Party to make any payment in any year in excess of amounts appropriated for such year; 2) as creating a debt or multiple fiscal year direct or indirect debt or other financial obligation whatsoever within the meaning of Article X, Section 6 or Article X, Section 20 of the Colorado Constitution (TABOR) or any other constitutional or statutory limitation or provision; or 3) as a donation or grant by any Party in aid of any person, company or corporation under applicable Colorado law.

CITY OF GRAND JUNCTION

MESA COUNTY LAND CONSERVANCY,
INC. also known as COLORADO WST LAND
TRUST

By _____
Greg Caton
City Manager

By _____
Robert J. Bleiberg
Registered Agent

ATTEST:

ATTEST:

Wanda Winkelmann
City Clerk



Grand Junction City Council

Regular Session

Item #4.c.

Meeting Date: October 2, 2019

Presented By: Wanda Winkelmann, City Clerk

Department: City Clerk

Submitted By: Wanda Winkelmann

Information

SUBJECT:

A Resolution Assigning City Councilmembers to Various Boards, Commissions, and Authorities

RECOMMENDATION:

Staff recommends adoption of the resolution.

EXECUTIVE SUMMARY:

The purpose of this item is to appoint City Councilmembers to various boards, committees, commissions, authorities, and organizations.

BACKGROUND OR DETAILED INFORMATION:

The City Council assigns its members to serve on a variety of Council appointed boards, committees, commissions, and authorities as well as a number of outside organizations.

A vacancy on the Riverview Technology Corporation (RTC) occurred as a result of District C Councilmember Bennett Boeschstein's term expiration. Councilmember Phyllis Norris will serve on the RTC effective October 2, 2019.

FISCAL IMPACT:

N/A

SUGGESTED MOTION:

I move to adopt Resolution No. 64-19, a resolution appointing and assigning City

Councilmembers to represent the City on various boards, committees, commissions, authorities, and organizations.

Attachments

1. Resolution - Council Assignments

CITY OF GRAND JUNCTION, COLORADO

RESOLUTION NO. XX-19

**A RESOLUTION APPOINTING AND ASSIGNING
CITY COUNCILMEMBERS TO REPRESENT THE CITY
ON VARIOUS BOARDS, COMMITTEES, COMMISSIONS, AUTHORITIES, AND
ORGANIZATIONS**

Recitals:

Through various boards, committees, commissions and organizations the citizens of the City have a longstanding tradition of service to the community. The City Council by and through its creation of many of those boards and its participation there on and there with is no exception. The City is regularly and genuinely benefitted by the service performed by its boards, committees, commissions and organizations.

In order to continue that service, the City Council annually or at convenient intervals designates certain Council members to serve on various boards, committees and commissions.

A vacancy on the Riverview Technology Corporation (RTC) occurred as a result of District C Councilmember Bennett Boeschstein's term expiration. Councilmember Phyllis Norris will serve on the RTC effective October 2, 2019.

**NOW, THEREFORE, BE IT RESOLVED BY THE CITY COUNCIL OF THE CITY OF
GRAND JUNCTION COLORADO THAT:**

Until further action by the City Council, the appointments and assignments of the members of the City Council are as attached.

PASSED AND ADOPTED THIS ____ day of October, 2019.

Mayor and President of the City Council

ATTEST:

City Clerk

CITY COUNCIL FORMAL ASSIGNMENT WORKSHEET 2019/2020

External Agencies

Board/Organization	Meeting Day/Time/Place	2018/2019 Assignments/Number of Years Served	2019/2020 Assignments
Avalon Theatre Committee*	Third Thursday at 8:00 a.m.	Bennett Boeschstein - 6 years	NA
Associated Governments of Northwest Colorado (AGNC)	3rd Wednesday of each month @ 9:00 am different municipalities	Duncan McArthur – 2 years	Kraig Andrews
Business Incubator Center	1 st Wednesday of each month @ 7:30 am, 2591 Legacy Way	Bennett Boeschstein	Phyllis Norris
Colorado Municipal League Legislative Liaison	CML Office	Duncan McArthur – 2 years	Anna Stout
Colorado Water Congress	Meets 3-4 times a year in Denver	Duncan McArthur - 4 years	Anna Stout
Downtown Development Authority/Downtown BID	2 nd and 4 th Thursdays @ 7:30 am @ DDA Offices, 437 Colorado, BID board meets monthly 2 nd Thursday	Phyllis Norris – 2 years	Anna Stout
5-2-1 Drainage Authority	Meets quarterly, generally the 4 th Wednesday of month at 3:00 p.m. in Old Courthouse in Training Rm B	Duncan McArthur – 6 years	Phyllis Norris Kraig Andrews
Grand Junction Economic Partnership	3rd Wednesday of every month @ 7:30 am @ GJEP offices, 122 N. 6 th Street	Chris Kennedy – 2 years	Duke Wortmann
Grand Junction Housing Authority	4 th Monday @ 5:00 pm @ GJHA Offices at 8 Foresight Circle	Phyllis Norris- 2 years	Rick Taggart
Grand Junction Regional Airport Authority	Usually 3 rd Tuesday @ 5:15 pm @ the Airport Terminal Building (workshops held the 1 st Tuesday)	Rick Taggart – 4 years	Chuck McDaniel
Grand Valley	4 th Monday every other	Bennett Boeschstein – 2	Phyllis Norris

Regional Transportation Committee (GVRTC)	month @ 3:00 pm @ GVT Offices, 525 S. 6 th St., 2 nd Floor	years	
Homeless Coalition	Meets on the 3 rd Thursday of the month at 10 a.m. at St. Mary's Hospital, 5 th Floor, Saccomanno Room 3	Duncan McArthur – 3 years Bennett Boeschstein – 3 years	Chuck McDaniel Phyllis Norris
Horizon Drive Association Bus. Improvement Dist*	3 rd Wednesday of each month at 10:30 a.m.	Bennett Boeschstein – 1 year	NA
Las Colonias Development Corporation	Meets as needed and scheduled	Phyllis Norris – 1+ years	Phyllis Norris
Mesa County Separator Project Board (PDR)	Quarterly @ Mesa Land Trust, 1006 Main Street	Barbara Traylor Smith – 2 years	Mayoral Assignment
One Riverfront	3 rd Tuesday of every other month @ 5:30 p.m. in Training Room A, Old Courthouse	Duke Wortmann – 2 years	Rick Taggart

Internal Boards

* = No Council representative required or assigned - City Council either makes or ratifies appointments - may or may not interview dependent on particular board

Board Name	Meeting Day/Time/Place	2018/2019 Assignments/Number of Years Served	2019/2020 Assignments
Commission on Arts and Culture*	4 th Wednesday of each month at 4:00 p.m.	Bennett Boeschstein – 3 years	Anna Stout
Forestry Board*	First Thursday of each month at 8:00 a.m.	NA	NA
Historic Preservation Board*	1 st Tuesday of each month at 4:00 p.m.	Bennett Boeschstein – 3 years	NA
Orchard Mesa Pool Board	Meets twice a year at 8:00 a.m. at a designated location.	Duke Wortmann – 2 years	Duke Wortmann
Parks Improvement Advisory Board (PIAB)	Quarterly, 1 st Tuesday @ noon @ various locations (usually Hospitality Suite)	Barbara Traylor Smith – 2 years as alternate, 4 years as primary Alternate – Duke Wortmann – 2 years	Phillip Pe'a Alternate: Duke Wortmann
Board Name	Meeting Day/Time/Place	2018/2019	2019/2020

		Assignments/Number of Years Served	Assignments
Parks & Recreation Advisory Committee	1 st Thursday @ noon @ various locations (usually at Parks Administration Offices)	Duke Wortmann – 2 years	Phillip Pe'a
Persigo Board (All City and County Elected)	Annually and as needed	All	All
Planning Commission*	2 nd and 4 th Tuesday at 6:00 p.m.	NA	NA
Property Committee	Meets as needed and scheduled	Barbara Traylor Smith - 5 years Phyllis Norris – 1 year	Chuck McDaniel Phyllis Norris
Riverview Technology Corporation	Annual meeting in January	Bennett Boeschenstein – 3 years	Need Ex-Officio Member Phyllis Norris
Urban Trails Committee*	2 nd Tuesday of each month at 5:30 p.m.	Bennett Boeschenstein – 3 years	NA
Visit Grand Junction*	2 nd Tuesday of each month at 3:00 p.m.	Phyllis Norris – 3 years	NA
Zoning Code Board of Appeals*	As needed	NA	NA



Grand Junction City Council

Regular Session

Item #5.a.i.

Meeting Date: October 2, 2019

Presented By: Kristen Ashbeck, Principal Planner/CDBG Admin

Department: Community Development

Submitted By: Kristen Ashbeck, Principal Planner

Information

SUBJECT:

An Ordinance to Vacate a Portion of the East-West Alley Right-of-Way on the South Side of the Property Located at 845 Orchard Avenue

RECOMMENDATION:

The Planning Commission heard this item at its September 24, 2019 meeting and recommended approval of the vacation request.

EXECUTIVE SUMMARY:

Consider a request by the Applicant, Colorado Mesa University (CMU) on behalf of the property owner, Johnny Jr. and Colleen Martin, to vacate a portion of the East-West Alley right-of-way (2,348 square feet) on the south side of the property located at 845 Orchard Avenue. CMU is currently under contract to purchase the property and the vacated area would become part of the campus.

BACKGROUND OR DETAILED INFORMATION:

Colorado Mesa University (CMU) is in the process of acquiring the property on the north side of the alley that is presently owned by Johnny Jr. and Colleen Martin located at 845 Orchard Avenue. The property currently has three dwelling units on it. The sales contract on the property is conditioned upon the current owner having an opportunity to move the existing structures to a different location. Thus, final purchase of the property by CMU is not scheduled to occur until November 2019.

In the meantime, CMU, is requesting the vacation of a portion of the public right-of-way (2,348 square feet) in the east-west alley on the south side of the property. CMU

already owns the two properties on the south side of the alley that abut this segment proposed to be vacated. The vacation will aid in the continued westward expansion efforts planned for the campus. Consistent with CMU's approved Civic and Institutional Master Plan, this area of the campus is proposed to be a new outdoor track and field facility.

This particular segment of alley lies outside of the CMU Master Plan area boundary subject to Ordinance 4754 which established an agreement between the City and CMU to enable rights-of-way to be vacated through an administrative process. Since it is outside that area, the vacation process for this segment of alley right-of-way is subject to the City's standards processes as defined by the Zoning and Development Code and may only be approved by recommendation of the Planning Commission to City Council for final action.

Presently, the alley contains a City sewer line and Xcel Energy electrical and gas infrastructure. The relocation and/or easement needs for the City utility are subject to the Colorado Mesa University and City of Grand Junction Utility Easement and Maintenance Agreement-CMU Main Campus executed in September 2016. The Agreement was executed with the common understanding that 1) CMU has relied, and will continue to rely, on the City's water, sanitary sewer and other services to other citizens and landowners within the City; and 2) the City desires to support the expansion of the CMU campus and agrees that the City should continue to own, operate and maintain the main or trunk lines providing service to and within the campus as it exists and as it plans to exist. The Agreement outlines the responsibilities of each agency in providing access to and maintenance of utilities within rights-of-way proposed to be vacated and stipulates that the City will agree to vacations of rights-of-way, so long as at least 10 feet of unobstructed access is provided, centered over each wet utility line (e.g. sewer and water). The Agreement does not state that the access need be provided via an easement.

The alley does contain Xcel Energy infrastructure (electric and natural gas), however these existing utilities will be moved and relocated by Xcel Energy as part of the construction of the new track and field facility and if necessary, appropriate easements to Xcel Energy will be dedicated at that time.

The Grand Junction Fire Department has no objections to the proposed right-of-way vacation provided remaining existing and all future access roads created with new construction on the CMU campus are compliant with the state and locally adopted International Fire Code. Given the requirement and CMU's intention to develop and construct fire access lanes, it is Staff's assessment that the proposed vacation would not impede traffic, pedestrian movement or access to private property or obstruct emergency access.

NOTIFICATION REQUIREMENTS

A Neighborhood Meeting was held on August 26, 2019. There were 20 people in attendance. The Applicant provided a presentation with an update on various activities going on across campus and information regarding the most recent vacation requests. The discussion concerned alley access to the east, trash service in the alley, how traffic will be addressed to prevent people from driving through driveways that connect to Orchard Avenue, and emergency access to go south from Orchard Avenue on what used to be the Cannell Avenue alignment.

Notice was completed consistent with the provisions in Section 21.02.080 (g) of the Zoning and Development Code. The subject property was posted with an application sign and mailed notice of the public hearings before Planning Commission and City Council in the form of notification cards was sent to surrounding property owners within 500 feet of the subject property on September 13, 2019. The notice of the public hearing for the Planning Commission meeting was published September 17, 2019 in the Grand Junction Daily Sentinel.

ANALYSIS

Pursuant to Section 21.02.100 of the Zoning and Development Code, the vacation of public right-of-way shall conform to the following:

(1) The Comprehensive Plan, Grand Valley Circulation Plan and other adopted plans and policies of the City,

Granting the request to vacate a portion of an existing alley right-of-way meets the following Goal and Policy of the Comprehensive Plan by supporting the University in their facilities and building expansion projects, enhances a healthy, diverse economy and improves the City as a regional center of commerce, culture and tourism.

Goal 12: Being a regional provider of goods and services the City and County will sustain, develop and enhance a healthy, diverse economy.

Policy A: Through the Comprehensive Plan's policies the City and County will improve as a regional center of commerce, culture and tourism.

In addition to the goal and policy above the Grand Junction Comprehensive Plan states: "Due to the inefficiencies of low density sprawl, a significant amount of projected future growth is focused inward on vacant and underutilized land throughout the community. This takes advantage of land that already has roads, utilities and public services. Infill and redevelopment is especially focused in the City Center. Reinvestment and revitalization of the center, and maintaining and expanding a 'strong downtown', is a high priority of the Comprehensive Plan and essential for the area's regional economy. (Guiding Principle 1: Centers - Downtown)"

The requested vacation also does not conflict with the Grand Valley Circulation Plan and other adopted plans and policies of the City.

Therefore, this criterion has been met.

(2) No parcel shall be landlocked as a result of the vacation.

No private parcels shall be landlocked as a result of the proposed vacations as all remaining private properties west of this requested vacation will continue to have access to street and alley rights-of-way.

Therefore, this criterion has been met.

(3) Access to any parcel shall not be restricted to the point where access is unreasonable, economically prohibitive, or reduces or devalues any property affected by the proposed vacation;

All properties abutting the proposed portion of alley requested for vacation are owned by or soon to be owned by CMU. Therefore, provided CMU follows through with the acquisition of 845 Orchard Avenue prior to recording the vacation ordinance, there are no other properties in the vicinity that will rely on this alley for access to their property.

Therefore, this criterion will be met.

(4) There shall be no adverse impacts on the health, safety, and/or welfare of the general community, and the quality of public facilities and services provided to any parcel of land shall not be reduced (e.g., police/fire protection and utility services);

There are both City and Xcel utilities located within the segment of alley right-of-way requested to be vacation. City utilities will be accommodated via the previously-mentioned agreement which preserves a minimum 10-foot wide access centered on all wet utility lines. Xcel has not requested an easement be retained at this time for the existing utilities. Xcel utilities will be relocated and/or easements provided at the time the future facilities are to be constructed. CMU has provided an emergency access plan for this area of the campus including with the construction of the new track and field facility and the Fire Department has approved the plan. In addition, for City Sanitation, CMU will provide a hammerhead turnaround at the east end of the vacated alley that can still accommodate trash pick-up in the alley. The requested vacation does not adversely impact police/fire protection to the remaining adjacent private properties.

Therefore, the requested vacation has no identified adverse impacts on the health,

safety, and/or welfare of the general community, and the quality of public facilities and services provided to any parcel of land shall not be reduced.

Thus, Staff has found this criterion has been met.

(5) The provision of adequate public facilities and services shall not be inhibited to any property as required in Chapter 21.06 of the Grand Junction Zoning and Development Code; and

No adverse comments concerning the proposed right-of-way vacations were received from the utility review agencies during the review process including Xcel Energy. Sanitary sewer is located in the alley but its future relocation and/or need for easement is addressed in the Colorado Mesa University and City of Grand Junction Utility Easement and Maintenance Agreement-CMU Main Campus. Xcel utilities will be relocated if needed and/or easements provided at the time the future facilities are to be constructed.

Therefore, this criterion has been met.

(6) The proposal shall provide benefits to the City such as reduced maintenance requirements, improved traffic circulation, etc.

Maintenance requirements for the City will be reduced as a result of the proposed portion of alley right-of-way to be vacated since the City will not have to maintain the right-of-way. The benefit to the City is the expansion of CMU and its mission to educate and by enhancing and preserving Grand Junction as a regional center. The proposed alley right-of-way vacation is needed by CMU as part of their continued campus expansion to the west.

Therefore, this criterion has been met.

STAFF AND PLANNING COMMISSION RECOMMENDATION AND FINDINGS OF FACT

After reviewing the Colorado Mesa University Vacation of Alleyway Right-of-Way, VAC-2019-444, located at 845 Orchard Avenue, the following findings of fact have been made with the recommended conditions of approval:

1. The request conforms with Section 21.02.100 (c) of the Zoning & Development Code.
2. The requested vacation does not conflict with the goals and policies of the Comprehensive Plan.

Condition 1. The applicant shall provide evidence of ownership of the property located at 845 Orchard Avenue (parcel number 2945-111-08-006) prior to the ordinance being recorded with the Mesa County Clerk and Recorder in order for the vacation to take effect.

Condition 2. The Applicant shall pay all recording/documentary fees for the Vacation Ordinance.

Condition 3. The Applicant shall meet all terms and conditions of the Colorado Mesa University and City of Grand Junction Utility Easement and Maintenance Agreement- CMU Main Campus and all requirements of the Grand Junction Fire Department for construction of proposed campus facilities.

FISCAL IMPACT:

Values of the real property associated with right-of-way differ depending on the current market and the area of the City. The alley right-of-way requested to be vacated is 2,348 square feet and will become part of the Colorado Mesa University campus and allow for development of additional facilities.

SUGGESTED MOTION:

I move to (adopt/deny) Ordinance No. 4877, an ordinance vacating a portion of alley right-of-way located between Orchard Avenue and Hall Avenue on the south side of the property located at 845 Orchard Avenue on final passage and order final publication in pamphlet form.

Attachments

1. 845 Orchard Avenue Vacation Location Maps
2. Proposed Track and Field Facility Showing Access
3. CCON 3946 Contract - 2016 - Utility Easement and Maintenance Agreement within Campus - Colorado Mesa University (CMU)
4. CMU Alley Vacation 845 Orchard Ave Ordinance

LOCATION MAP




AERIAL PHOTO LOCATION MAP



 2017 Master Plan Boundary

 Property Owned by CMU



ORCHARD AVENUE

AREA OF VACATION

FIRE AND SANITATION
TURNAROUND

Hammer head
turnaround

AREA TO REMAIN OPEN
FOR FIRE ACCESS

COLORADO MESA UNIVERSITY AND CITY OF GRAND JUNCTION UTILITY EASEMENT AND MAINTENANCE
AGREEMENT-CMU MAIN CAMPUS

This Agreement is made by and between the City of Grand Junction, a Colorado home rule city ("City"), and the Board of Trustees of Colorado Mesa University ("CMU"), and is effective as of the date that both parties have signed below.

Recitals.

- A. CMU continues to expand its campus to serve the needs of Western Colorado and of the entire State of Colorado. For this Agreement, "campus" means the area generally bounded by North Avenue, Orchard Avenue, 7th Street and 12th Street, in Grand Junction, Colorado, within which exists the main CMU campus and within which CMU is expected to expand.
- B. CMU has adopted a master plan, the current iteration of which shows that in the years to come the campus can be expected to encompass many existing properties west of the now developed main campus. A copy of the current master plan is attached as Exhibit A. When land use is changed from residential to campus buildings and facilities, the number of service lines will decrease substantially yet the size of the lines and the complexity of the maintenance of the lines may increase and/or some lines may need to be relocated. A 'service line' for purposes of this Agreement is the water and/or the sewer pipe(s) connecting the structures on the campus with the City water or sewer pipe(s) that carry water or sewage, respectively, to and/or away from the campus and other structures served by such service lines.
- C. CMU has relied, and will continue to rely, on the City's water, sanitary sewer and other services provided to other citizens and land owners within the City.
- D. To utility providers and engineers, there is a distinction between 'main' or 'trunk' water, sanitary sewer and storm sewer lines (typically 4" or larger for water, 8" or larger for sanitary sewer and 12" or larger for storm sewer) and 'service' lines that are typically smaller and are owned and maintained by the owner of the served parcel. For purposes of this Agreement, the larger 'main' or 'trunk' lines as described above are the primary concern of the City and CMU under this agreement, not 'service lines (Wet Utilities)

The City desires to support the expansion of the CMU campus, and agrees that the City should continue to own, operate and maintain the main or trunk lines providing service to and within the campus as it exists and is planned to exist.

- E. At the present time, CMU is requesting City approval of a plat and vacation of existing City rights-of-way as shown on said plat, attached as Exhibit B. This Agreement is agreed to in part to facilitate the City's approval of such plat.

NOW THEREFORE, in consideration of the many benefits received by CMU and the City, individually and collectively, as a result of this Agreement, the City of Grand Junction and Colorado Mesa University agree as follows:

1. CMU, as the owner of the property described on Exhibit B, hereby grants to the City as the owner and service provider of the Wet Utilities serving the property shown on Exhibit B, a perpetual and non-exclusive easement to be used by the City to access, operate, maintain, improve, repair and replace as necessary the Wet Utilities serving the property shown on Exhibit B in accordance with City standards.
2. The City agrees that it will continue to own, operate, maintain, improve, repair and replace as needed the main and trunk lines as described in recital C above, that serve the property shown on Exhibit B now and as it is planned to exist in the future except as the deviation procedure in paragraph 4 below applies.
3. While the City standards ordinarily require unobstructed ten-foot-wide access on either side of the centerline of Wet Utilities, the City recognizes that doing so within the campus may unduly limit the ability of CMU to make the most efficient use of its limited area and lands. Thus, the City agrees to accept existing accesses to existing Wet Utilities, so long as at least ten feet of unobstructed access is provided, centered over the Wet Utility in question.
4. CMU shall deliver its construction plans to the City with respect to Wet Utilities so that the City has an opportunity to improve the efficiency and effectiveness of Wet Utility service line that will serve the campus both now and in the future. When, CMU determines that one or more City standard(s) must be deviated from when constructing or locating Wet Utilities, CMU shall consult with the City's Engineers to obtain City approval of such deviation(s). If the City's Engineers do not approve such deviation(s), then CMU may request review of such denials by the City Director of Public Works and if said Director does not approve such deviation(s) then CMU may request the City Manager to review such denial and if said City Manager does not approve such deviation(s), and CMU elects to construct the deviations anyway CMU shall be responsible for maintenance, repair and replacement of such service, trunk or main line(s) for that segment or portion of the Wet Utilities that do not meet the City's specifications. Deviations that are approved shall be described in writing, typically including drawing(s) specifying the deviation(s).
5. For buildings and other improvements within the area described on Exhibit A, and for future easements for the campus as it will exist, CMU agrees to provide ready and safe access to the City for Wet Utilities.
6. In the event the City concludes that it cannot reasonably obtain access to Wet Utilities because the CMU design access is too narrow, short or small, City Engineers will inform the City Director of Public Works who shall consult with the CMU consultant/engineer to determine a practical solution, on a case-by-case basis.
7. In any instance where the wet utilities do not meet city standards and where the Campus surface has been improved (e.g., sidewalks and landscaping) , including within the area described in Exhibit A, if the City cannot reasonably obtain access to or perform its necessary maintenance,


improvement, repairs or replacement to Wet Utilities owned by the City, the City shall inform CMU which shall perform the needed maintenance, improvement, repair or replacement; however, in an emergency, the City may damage or remove such surface improvements without notice to CMU and in such event, the City shall not be obligated to replace the improved surface of the damaged area to its prior condition, but shall return the surface to a substantially equivalent of grade and elevation.

8. CMU shall pay for the costs to repair or replace any improvements damaged by the City as a result of the reasonable exercise of maintenance, repair or replacement of City Wet Utilities in locations where such Wet Utilities do not meet City standards.
9. Notwithstanding any provision of this Agreement to the contrary, CMU shall prohibit the construction of any structures on the Campus as it exists or will exist that are not at least ten feet at the centerline from any Wet Utilities existing as of the date of the Agreement.
10. The parties agree that the existing rights-of-way for Cannell and Elm and any existing multi-purpose easements ("MPE"s) shall be vacated, and title thereto shall vest in CMU, subject to reservation by the City of easements (the "Cannell and Elm Easements") for any such MPEs and for access for utilities. The legal description of the Cannell and Elm Easements that are being vacated shall be identical to the description of the vacated rights-of-way and any adjacent MPEs.
11. The City agrees that CMU shall have the right to install improvements such as fiber optic lines and related facilities within the Cannell and Elm Easements, subject to CMU's duty to abide by the law applicable to easements.
12. To facilitate the logical and efficient expansion of CMU on land presently owned or owned in the future either in the name of the CMU Real Estate Foundation or titled in the name of the State of Colorado for the benefit of CMU, or in the name of any entity controlled by the CMU Board of Trustees, this Agreement shall apply to all Wet Utilities serving the present and future CMU main campus.
13. The term of this Agreement shall be for a five year period and can be renewed for another five year term provided both parties are agree able. The term also provides for a two year review by both parties from the effective date of the agreement. This two year review will be an opportunity for the two parties to meet and assess how the agreement is working and make appropriate changes to the agreement as agreed upon by both parties.

Colorado Mesa University, President



By: Tim Foster

City of Grand Junction, City Manager


Greg Caton

Dated: 2-12-16

Dated: 9/12/2016



MESA STATE COLLEGE

PROGRAM PLAN

WEST EXPANSION PROPERTY ACQUISITION PROJECT

APRIL 8, 2011



C H A M B E R L I N
A R C H I T E C T S

CONTRIBUTORS

Mesa State College Board of Trustees:

Charlie Monfort, Chair
Kathleen Eck
Lena Elliott
Jerome Gonzales
Cecil Hernandez
Lorenzo Marquez
Doug Price
Dan Robinson
Joe Skinner
Monte Atkinson, Faculty Trustee
Ryan Hendershot, Student Trustee

Mesa State College Administration:

Tim Foster, President
Patrick Doyle, Vice President of Finance
Carol Futhey, Vice President of Academic Affairs
Kent Marsh, Director of Facilities Services
Derek Wagner, Director of Strategic Initiatives

Mesa State College Foundation Officers

Doug May, President
Keith Gilstrap, Vice-President
Travis Perry, Secretary/Treasurer

PREFACE

The project described herein continues the activities associated with the main campus land acquisition project begun in 1999. Since then, the Mesa State College Foundation has been acquiring property and, beginning in 2004 with the approval of the “House Demolition and Ground Recovery Project” program plan, began gifting the properties to the College. Originally the 2004 program plan was expected to take 15 years to complete; however, with only five remaining properties to be acquired, it is approaching its successful completion in half the time. This coupled with the unprecedented enrollment growth that has occurred during this time period places the College in a position where it needs to proceed with phase two its land expansion plan. Approval of this program plan will authorize the Foundation to acquire the additional properties described herein.

Coordinators for this project were Pat Doyle, Vice President, Finance and Administrative Services, Derek Wagner, Director, Strategic Initiatives, Kent Marsh, Director of Facilities Services; and Andy Rodriguez, Director of Purchasing. Program plan documentation was accomplished by Ed Chamberlin, Chamberlin Architects, Campus Architect. This document has been approved by Tim Foster, President of Mesa State College, as well as by the senior administration of the College.

This document responds to the outline requirements of CCHE policy Section III.E, *Guidelines for Facilities Program Planning* last revised April 5, 2001. Some outline sections have been omitted because the project does not deal with new capital construction or building renovation.

TABLE OF CONTENTS

Section	Page
Contributors	1
Preface.....	2
Table of Contents.....	3
Executive Summary	4
Program Information.....	5
Description of the Program	5
History, Role and Mission, Needs and Trends	5
Relation to Academic/Strategic Plans.....	6
Relation to Other Programs or Agencies	7
Program Alternatives	7
Facilities Needs.....	8
Total Space & Site Requirements	8
Acquisition of Real Property	10
Project Description.....	10
Improvements	10
Project Cost Estimate	12
Financial Analysis	12
Project Schedule	12
Relation to the Master Plan / Other Projects.....	13
Appendices.....	14
A. Student demographics	14
B. Property listing	15
C. Third Party Review	21
D. CCHE Form CC-C	22

EXECUTIVE SUMMARY

It is the purpose of this project to consolidate activities associated with the main campus land acquisition project begun in 1999. Since then, the Mesa State College Foundation has been acquiring property and giving it to the College through Foundation, Trustee, Colorado Commission on Higher Education, and Legislative actions. The College now needs to be able to accept the gift of additionally acquired properties and to consolidate those and prior associated properties into useful capital construction expansion sites.

This project is necessitated by the continued growth of Mesa State College. In the past ten years, unduplicated fiscal year FTE has increased from 4302 to 6555 or 52.4%. Likewise, unduplicated fiscal year headcount has grown from 5212 to 8131 or 56.0%. These figures indicate a growth rate of almost 4.5% per year.

The specific additional property being considered by the College by its Foundation consists of 214 residential lots, 2 churches, and 21 commercial properties comprising a total of 77.3 acres. Other property that is being given to the College consists of city streets and alleys that will become within the College boundaries.

The land gifts are part of the Land Acquisition Project begun in 1999 with donations from the City of Grand Junction, Mesa County, and numerous community organizations, institutions, leaders, and individuals. The original acquisition project was identified in the 1999 *Mesa State College Facilities Master Plan*. This project will allow for the acceptance of gifted properties within specified boundaries which have yet to be acquired by the College, the Mesa State College Foundation, or through subsequent capital construction projects. The boundaries for the main campus will be North Avenue on the south, Orchard Avenue on the north, Seventh Street on the west, and with the addition of one block east of 12th Street, 12th Street on the east. There are also two other large tracts that, if they become available, will be valuable additions to the campus. These are at the northwest and southeast corners of 12th and Orchard.

Consolidation of the properties into useful sites will consist of demolition of the existing structures and surveying and replatting of the individual lots, streets, and alleys into one parcel that belongs to the College. Existing structures include those being donated to the College under this project as well as those yet to be acquired by the Foundation. The consolidated parcel will then be available for construction of temporary parking lots and green spaces, provide ongoing revenue sources and sites for significant campus expansion projects.

The project will be self-financed over time by the College through the use of cash exempt funds and donations. As those funds become available, parts of the project will be finished. No endowment is included with the gifted properties. It is understood that the College will maintain them within its own budgeted resources.

PROGRAM INFORMATION

DESCRIPTION OF THE PROGRAM

For the past several years, Mesa State College has been increasing its enrollment. In 1996, it was recognized that this enrollment growth would require additional land and facilities, placing its main campus in need of a significant boundary expansion. Since approval of the *Mesa State College Facilities Master Plan* in 1999, the Mesa State College Foundation with the help of the City of Grand Junction, Mesa County, and numerous community organizations, institutions, leaders, and individuals, has acquired several properties to help meet expansion needs. The Foundation has already gifted many of these to the college. The project described herein continues this gifting process that began in 2004. The project gives additional properties to the college in accordance with current and future facilities master plan needs.

HISTORY, ROLE AND MISSION, NEEDS AND TRENDS

Mesa State College's current role and mission:

There is hereby established a college at Grand Junction, to be known as Mesa state college, which shall be a general baccalaureate and specialized graduate institution with moderately selective admission standards. Mesa state college shall offer liberal arts and sciences, professional and technical degree programs and a limited number of graduate programs. Mesa state college shall also maintain a community college role and mission, including career and technical education programs. Mesa state college shall receive resident credit for two-year course offerings in its commission-approved service area. Mesa state college shall also serve as a regional education provider.¹

As regional education provider, Mesa State College serves 14 counties in western Colorado. The region's population continues to grow, providing the College with additional students every year. According to the State's Demographic Office, all of the counties in Mesa State's region have grown and will continue to grow.² (The period in question is from 2000 to 2040 for 15 to 25 year olds. These dates are the period analyzed for the *Mesa State College Facilities Master Plan*.) Historically, well over half of the College's enrollment comes from this region.³ However, recent enrollment growth from outside Mesa County and outside Colorado has been dramatic. Non-resident student FTE has grown from 438 to 614 since 2007 – a 40% increase confirming the College's need for additional land to support its mission.

¹ Colorado Revised Statutes 23-53-101, College Established – Role and Mission.


² Rather than reprint the demographic information within this document, the reader is referred to <http://dola.colorado.gov/demog/demog.cfm> for backup information from the Colorado Demography Office on the population trends for each county.

³ See Appendix A of this document for student demographic information.

RELATION TO ACADEMIC/STRATEGIC PLANS

Mesa State College anticipates continued enrollment growth. The *Mesa State College Strategic Plan*⁴ recognizes the need to balance sustainable growth with maintaining the institution's role as a regional education provider for 14 counties in western Colorado. With a focus on enhancing quality in the institution's programs, faculty, students, technology and facilities, sustainable enrollment growth is likely over the life of the plan. As financial support from the State of Colorado continues to dwindle, the institution is focused on strategic growth initiatives that enhance our competitiveness and strengthen our financial position.

The following graph presents enrollment growth, actual and projected, for the thirty-five year period from 2000 to 2035.



Using 2000 as the base year, the graph shows that for fiscal year 2010, the actual FTE of 6555 and actual headcount of 8131 represent a growth rate of over 2.1% and 4.5% respectively. The trend for both FTE and headcount is continued growth especially among out of town students who will need on-campus housing. The projection anticipates a growth rate of 2.125% per year.

The College is reevaluating its strategic planning documents in the light of the current economic climate in its current role and mission. However, it is known that, because of its designation as regional education provider for 14 counties, the College will need to be able to respond to the increasing educational needs of a growing western Colorado

⁴ <http://www.mesastate.edu/president/documents/StrategicPlan01-27-11.PDF>

population. It is anticipated that College growth and the subsequent need for additional land will continue.⁵

RELATION TO OTHER PROGRAMS OR AGENCIES

This program is integral to the college being able to fulfill its role and mission. Without the ability to expand the campus boundaries, the college will be limited in its ability to provide access to students outside of its immediate geographic location i.e. Mesa county. Having the capacity to continue to grow enrollment throughout Colorado and surrounding Western Undergraduate Exchange (WUE) states is key to the long term financial stability of the institution.

PROGRAM ALTERNATIVES


The only alternative to this project is to cap enrollment. This is not acceptable and contrary to the College's role and mission.

⁵ It should be noted that this Program Plan discusses only the needs of the main campus. Enrollment growth with subsequent land and facility needs are also anticipated for the UTEC and Montrose campuses.

FACILITIES NEEDS

TOTAL SPACE AND SITE REQUIREMENTS

Prior to the 2004 acquisition project, the main campus contained approximately 45 acres of land. The 1999 Facilities Master Plan identified several areas of potential expansion in accordance with the map shown below.⁶





⁶ This map is a reprint of that in the 1999 *Mesa State College Facilities Master Plan*, page 113.

The background of this map shows concepts developed for the 1999 Facilities Master Plan. Several of the capital building projects indicated with diagonal lines on the map have already occurred.

The 2004 House Demolition & Ground Recovery project added most of the property between Cannell and Houston. All but 5 lots within this area have been acquired as shown on the inserted graphic titled Property Acquisitions 2004-2011.

The second inserted graphic titled Acquisition Priorities shows the new priority areas. Priority I areas are those the college is actively trying to purchase. Priority II areas are those the college will pursue if they become available.





- | | |
|---|--|
| Priority I (59 Acres) | Under contract April 12, 2011 |
| Priority II (27 Acres) | To be acquired w/in campus area |

ACQUISITION OF REAL PROPERTY

Appendix B includes a listing of properties under consideration by the College. The list indicates the street address and parcel number.

The property locations are shown by their street address number. Within the Priority I area there are 214 single family houses most of which were constructed in the 1950's and 1960's. Some are vacant while others are rentals. There are also 20 commercial and church properties.

Following discussion with the City of Grand Junction the streets and alleys will be vacated and deeded to the College in sections at different times where property ownership surrounding the various rights-of-way has been completed.

PROJECT DESCRIPTION

Improvements:

As stated, it is the intention of this phase of the land acquisition project to establish complete new boundaries for the main campus of Mesa State College. The western boundary from North Ave. to Orchard Ave. will move from Cannell Ave to Seventh Street. The southern boundary of North Ave. will not change. The eastern boundary of 12th Street will also not change except for the area bounded by Orchard Ave., 13th Street, and Glenwood Ave. The northern boundary may include the Community Hospital property if it becomes available.

Once acquired, it is the intention of the College to replat the land parcels into one parcel belonging to the College, remove structures, and to prepare the ground for construction of College related facilities, parking areas, and green space in accordance with the *Mesa State College Facilities Master Plan*.

The first part of this project will consolidate all properties between Cannell Street, North Avenue, Seventh Street and Orchard Avenue, and within the block shown east of 12th Street. The maps on the next several pages show the campus after completion of incremental consolidation work on a five year basis. Once all structures have been demolished, the lots, streets, and alleys will be surveyed and replatted to identify one parcel belonging to the College.

Initially, the area will become either green space or temporary parking. Green space work will consist of leveling the ground and providing dust and weed control. As more houses are removed and large areas become available, the area will be covered with grass and sprinklered. Lights and appropriate sidewalks will also be provided. Temporary parking work will consist of leveling the ground and providing a gravel surface with dust and weed control, parking bumpers, parking control equipment, and appropriate lighting. Mature trees in good condition will be flagged and protected during construction.

Mesa State College – Program Plan, West Expansion Property Acquisition Project

It will take a period of time to acquire all properties, remove all structures, and convert all areas to either parking or green space. All work under this program plan, whether designated as parking or green space, should be viewed as temporary, as all areas will serve as sites for future capital construction projects.⁷

The building areas, parking and land area requirements are based on projected enrollment by prorating approximate facilities in use today. A spreadsheet showing these projections follows.

Mesa State College Campus Expansion Projection

April 7, 2011

CHAMBERLIN ARCHITECTS

2010-11 Factor				Growth	2015-16	Growth	2020-21	Growth	2025-26	Growth	2030-31	Growth	2035-36	
Student Enrollment														
Main Campus only														
Headcount														
On Campus	1624	11%	5-year		180	1,804	200	2,004	222	2,226	247	2,473	274	2,747
Off Campus	6486	11%	5-year		719	7,205	799	8,004	887	8,891	986	9,877	1,095	10,972
Total	8,110				899	9,009	999	10,008	1,109	11,117	1,232	12,350	1,369	13,719
Buildings														
Main Campus only														
Academic	688,000	85 sf	per Student		76,272	764,272	84,727	848,999	94,120	943,119	104,554	1,047,673	116,145	1,163,818
Residence Halls	402,500	62 sf	per Student		44,821	447,121	49,568	496,689	55,063	551,752	61,167	612,919	67,948	680,867
Non-Academic	91,500	11 sf	per Student		10,144	101,644	11,268	112,912	12,517	125,429	13,905	139,334	15,447	154,781
Total	1,182,000	158	per Student		131,037	1,313,037	145,563	1,458,600	161,700	1,620,300	179,626	1,799,927	199,540	1,999,466
Parking														
Main Campus only														
Residential	1,056	65%	On Campus		117	1,173	130	1,303	144	1,447	160	1,607	178	1,786
Commuter	1,881	29%	Off Campus		209	2,089	232	2,321	257	2,578	286	2,864	318	3,182
Reserved														
Total					326	3,262	362	3,624	402	4,025	446	4,472	496	4,967
Land Area														
Main Campus only														
Total SF	3,189,330				353,569	3,542,899	389,719	3,932,618	432,588	4,365,206	480,173	4,845,379	532,992	5,378,370
Acres	73				8	81	9	90	10	100	11	111	12	123

⁷ Program Plans for future capital construction projects within the revised boundary areas will be submitted to CCHE for consideration and approval.

Project Cost Estimate:

Each property will be independently appraised to determine a fair acquisition price. Based on the results of the 2004 House Demolition and Ground Recovery project, the average purchase price over the past seven years was \$180,000. However, with the housing market somewhat depressed this may be higher than what the market currently reflects but can serve as a conservative estimate. In the end, each house will be based on its unique characteristics. Total estimated average recovery costs per parcel:

Property Acquisition (projected average):	\$180,000
Testing, Abatement, Demolition	\$ 36,000
Temporary Parking Improvements	\$ 16,500
Planning and Approvals	\$ 500

PER RESIDENTIAL LOT TOTAL	\$233,000
---------------------------	-----------

The initial consolidation work includes environmental assessments and removal of hazardous material in accordance with current laws and regulations. Acquisition will be accomplished by the College or the Mesa State College Foundation through donation, nonexempt funds, or through other capital construction projects.

Projected acquisition cost for the residential lots is based on the average of 17 recently purchased in the neighborhood. The projected acquisition cost for commercial property is an average of the values on a per acre basis considering comparable sales, lease rates and other factors. Projected testing, abatement, demolition, lighting, grading and gravel cost is based on the average of 67 lots recently completed.

Financial Analysis:

The project will be self-financed by the College through the use of cash exempt funds and donations. The Board of Trustees will be requested to authorize the transfer of funds to the Mesa State College Foundation for property acquisition identified in this program plan. This request will be part of the annual budget process. It should be noted that funds to accomplish the entire project are not currently available.

Project Schedule:


It is anticipated that the project will be completed incrementally over the next ten years. Parts of the project will be completed as money becomes available and as the final properties become available for acquisition. In addition, many of the properties will become rentals providing a revenue stream that can assist in the funding of the acquisition program.

RELATION TO THE MASTER PLAN / OTHER PROJECTS

This project is part of “Project A1 – Land Acquisition, Main Campus” as described in the 1999 *Mesa State College Facilities Master Plan*, Volume 1, pages 114 – 116. In coordination with CCHE and the State of Colorado, Mesa State College has already accepted other properties under this project and will quite probably be working to accept additional properties as they become available within the priority areas established in this plan.



- Building Future Consturction
- Sports Field Future construction
- Green Space
- Surface Parking



- Building Future Construction
- Sports Field Future construction
- Green Space
- Surface Parking





- Building Future Consturction
- Sports Field Future construction
- Green Space
- Surface Parking



APPENDIX A
STUDENT DEMOGRAPHICS

Actual Student and FTE Enrollment Data

Year	Count	Head FTEs
1997	4900	4135
1998	5042	4219
1999	4904	4096
2000	5212	4302
2001	5303	4405
2002	5572	4625
2003	5765	4751
2004	6235	5096
2005	6062	4992
2006	5994	4891
2007	6199	4961
2008	6261	4973
2009	7042	5661
2010	8131	6555

Student Origin	Number of Students	Percent
Mesa State's 14 County Region	5488	67.5%
All Other Colorado	1667	20.5%
Out of State	941	11.6%
International	35	0.4%
Total	8131	

**APPENDIX B
PROPERTY LISTING**

Number	PARCEL_NUM	LOCATION
1	2945-114-08-010	1825 CANNELL AVE
2	2945-114-11-008	850 TEXAS AVE
3	2945-114-08-023	1816 N 8TH ST
4	2945-114-10-009	1727 CANNELL AVE
5	2945-114-09-019	725 ORCHARD AVE
6	2945-114-10-012	1717 CANNELL AVE
7	2945-114-08-016	860 HALL AVE
8	2945-114-11-005	828 TEXAS AVE
9	2945-114-08-014	888 HALL AVE
10	2945-114-09-008	1720 N 7TH ST
11	2945-114-08-020	820 HALL AVE
12	2945-114-11-004	816 TEXAS AVE
13	2945-114-10-004	847 HALL AVE
14	2945-114-09-020	749 ORCHARD AVE
15	2945-114-09-006	1742 N 7TH ST
16	2945-114-09-018	1808 N 7TH ST
17	2945-114-09-014	1825 N 8TH ST
18	2945-114-09-007	1730 N 7TH ST
19	2945-114-08-021	810 HALL AVE
20	2945-114-10-011	1735 CANNELL AVE
21	2945-114-08-019	830 HALL AVE
22	2945-114-10-005	855 HALL AVE
23	2945-114-08-012	890 HALL AVE
24	2945-114-08-017	848 HALL AVE
25	2945-114-10-001	1750 N 8TH ST
26	2945-114-09-005	1752 N 7TH ST
27	2945-114-08-013	880 HALL AVE
28	2945-114-09-011	1801 N 8TH ST
29	2945-114-11-009	858 TEXAS AVE
30	2945-114-08-006	845 ORCHARD AVE
31	2945-114-09-010	1737 N 8TH ST
32	2945-114-10-007	875 HALL AVE
33	2945-114-11-010	866 TEXAS AVE
34	2945-114-09-002	1828 N 7TH ST
35	2945-114-09-951	730 MESA AVE
36	2945-114-08-015	868 HALL AVE
37	2945-114-08-018	840 HALL AVE
38	2945-114-09-001	1842 N 7TH ST

Mesa State College – Program Plan, West Expansion Property Acquisition Project

39	2945-114-08-025	905 ORCHARD AVE
40	2945-114-09-013	1815 N 8TH ST
41	2945-114-11-003	804 TEXAS AVE
42	2945-114-08-003	817 ORCHARD AVE
43	2945-114-10-010	895 HALL AVE
44	2945-114-10-002	829 HALL AVE
45	2945-114-08-002	809 ORCHARD AVE
46	2945-114-08-022	802 HALL AVE
47	2945-114-09-004	1806 N 7TH ST
48	2945-114-11-007	842 TEXAS AVE
49	2945-114-08-008	911 ORCHARD AVE
50	2945-114-11-002	1616 N 8TH ST
51	2945-114-08-001	759 ORCHARD AVE
52	2945-114-09-017	1816 N 7TH ST
53	2945-114-11-001	1622 N 8TH ST
54	2945-114-11-006	836 TEXAS AVE
55	2945-114-08-011	898 HALL AVE
56	2945-114-09-021	723 ORCHARD AVE #N
57	2945-114-09-009	1727 N 8TH ST
58	2945-114-10-006	865 HALL AVE
59	2945-114-10-013	1707 CANNELL AVE
60	2945-114-08-009	921 ORCHARD AVE
61	2945-114-10-003	835 HALL AVE
62	2945-114-08-005	841 ORCHARD AVE
63	2945-114-10-008	885 HALL AVE
64	2945-114-08-004	829 ORCHARD AVE
65	2945-114-10-014	825 HALL AVE
66	2945-114-09-012	1805 N 8TH ST
67	2945-114-08-024	901 ORCHARD AVE
68	2945-114-13-021	888 ELM AVE
69	2945-114-14-032	1416 N 7TH ST
70	2945-114-15-013	1343 CANNELL AVE
71	2945-114-13-017	873 TEXAS AVE
72	2945-114-14-006	843 ELM AVE
73	2945-114-12-011	727 MESA AVE
74	2945-114-14-026	830 KENNEDY AVE
75	2945-114-15-003	771 KENNEDY AVE
76	2945-114-13-001	1524 N 7TH ST
77	2945-114-13-024	860 ELM AVE
78	2945-114-12-009	1625 N 8TH ST
79	2945-114-12-003	1628 N 7TH ST
80	2945-114-15-004	775 KENNEDY AVE
81	2945-114-15-012	885 KENNEDY AVE

Mesa State College – Program Plan, West Expansion Property Acquisition Project

82	2945-114-14-010	803 ELM AVE
83	2945-114-13-011	827 TEXAS AVE
84	2945-114-13-028	820 ELM AVE
85	2945-114-14-013	749 ELM AVE
86	2945-114-12-001	1630 N 7TH ST
87	2945-114-14-024	810 KENNEDY AVE
88	2945-114-13-007	755 TEXAS AVE
89	2945-114-14-019	740 KENNEDY AVE
90	2945-114-13-003	1516 N 7TH ST
91	2945-114-13-032	760 ELM AVE
92	2945-114-13-034	740 ELM AVE
93	2945-114-14-027	840 KENNEDY AVE
94	2945-114-13-019	889 TEXAS AVE
95	2945-114-13-031	774 ELM AVE
96	2945-114-13-014	849 TEXAS AVE
97	2945-114-13-016	865 TEXAS AVE
98	2945-114-13-033	748 ELM AVE
99	2945-114-11-014	898 TEXAS AVE
100	2945-114-13-005	743 TEXAS AVE
101	2945-114-15-020	824 BUNTING AVE
102	2945-114-14-007	833 ELM AVE
103	2945-114-15-005	805 KENNEDY AVE
104	2945-114-11-013	890 TEXAS AVE
105	2945-114-13-026	834 ELM AVE
106	2945-114-15-002	755 KENNEDY AVE
107	2945-114-14-011	769 ELM AVE
108	2945-114-13-027	830 ELM AVE
109	2945-114-13-004	735 TEXAS AVE
110	2945-114-15-015	874 BUNTING AVE
111	2945-114-12-008	1613 N 8TH ST
112	2945-114-13-972	704 ELM AVE
113	2945-114-13-009	811 TEXAS AVE
114	2945-114-15-009	845 KENNEDY AVE
115	2945-114-14-030	890 KENNEDY AVE
116	2945-114-14-002	883 ELM AVE
117	2945-114-13-002	1520 N 7TH ST
118	2945-114-15-019	834 BUNTING AVE
119	2945-114-13-035	730 ELM AVE
120	2945-114-15-008	835 KENNEDY AVE
121	2945-114-11-011	874 TEXAS AVE
122	2945-114-11-012	882 TEXAS AVE
123	2945-114-14-031	701 ELM AVE
124	2945-114-13-013	841 TEXAS AVE

Mesa State College – Program Plan, West Expansion Property Acquisition Project

125	2945-114-14-004	863 ELM AVE
126	2945-114-14-012	761 ELM AVE
127	2945-114-13-012	835 TEXAS AVE
128	2945-114-12-012	1604 N 7TH ST
129	2945-114-14-018	1400 N 7TH ST
130	2945-114-13-030	780 ELM AVE
131	2945-114-15-006	815 KENNEDY AVE
132	2945-114-13-010	819 TEXAS AVE
133	2945-114-15-011	865 KENNEDY AVE
134	2945-114-13-029	818 ELM AVE
135	2945-114-15-017	854 BUNTING AVE
136	2945-114-14-005	855 ELM AVE
137	2945-114-14-001	889 ELM AVE
138	2945-114-13-008	803 TEXAS AVE
139	2945-114-14-021	760 KENNEDY AVE
140	2945-114-14-003	875 ELM AVE
141	2945-114-15-007	825 KENNEDY AVE
142	2945-114-12-007	1603 N 8TH ST
143	2945-114-12-010	1635 N 8TH ST
144	2945-114-12-004	1616 N 7TH ST
145	2945-114-13-022	886 ELM AVE
146	2945-114-13-023	880 ELM AVE
147	2945-114-13-025	850 ELM AVE
148	2945-114-14-023	800 KENNEDY AVE
149	2945-114-14-029	860 KENNEDY AVE
150	2945-114-14-028	850 KENNEDY AVE
151	2945-114-12-002	721 MESA AVE
152	2945-114-15-010	855 KENNEDY AVE
153	2945-114-13-036	1510 N 7TH ST
154	2945-114-13-015	859 TEXAS AVE
155	2945-114-13-018	881 TEXAS AVE
156	2945-114-14-017	1410 N 7TH ST
157	2945-114-14-008	817 ELM AVE
158	2945-114-14-025	820 KENNEDY AVE
159	2945-114-14-009	809 ELM AVE
160	2945-114-13-020	895 TEXAS AVE
161	2945-114-13-006	753 TEXAS AVE
162	2945-114-15-018	844 BUNTING AVE
163	2945-114-14-020	750 KENNEDY AVE
164	2945-114-15-016	864 BUNTING AVE
165	2945-114-14-014	745 ELM AVE
166	2945-114-14-022	780 KENNEDY AVE
167	2945-114-17-012	856 GLENWOOD AVE

Mesa State College – Program Plan, West Expansion Property Acquisition Project

168	2945-114-16-014	752 GLENWOOD AVE
169	2945-114-19-006	865 GLENWOOD AVE
170	2945-114-18-001	763 GLENWOOD AVE
171	2945-114-17-013	846 GLENWOOD AVE
172	2945-114-17-014	836 GLENWOOD AVE
173	2945-114-17-017	804 GLENWOOD AVE
174	2945-114-16-006	727 BUNTING AVE
175	2945-114-19-007	875 GLENWOOD AVE
176	2945-114-16-012	730 GLENWOOD AVE #B
177	2945-114-15-023	768 BUNTING AVE
178	2945-114-17-024	888 GLENWOOD AVE
179	2945-114-15-028	710 BUNTING AVE
180	2945-114-16-010	720 GLENWOOD AVE
181	2945-114-16-003	749 BUNTING AVE
182	2945-114-15-025	750 BUNTING AVE
183	2945-114-17-021	866 GLENWOOD AVE
184	2945-114-19-005	845 GLENWOOD AVE
185	2945-114-17-006	853 BUNTING AVE
186	2945-114-19-008	911 GLENWOOD AVE
187	2945-114-16-008	1226 N 7TH ST
188	2945-114-19-003	825 GLENWOOD AVE
189	2945-114-17-018	867 BUNTING AVE
190	2945-114-15-024	762 BUNTING AVE
191	2945-114-15-021	814 BUNTING AVE
192	2945-114-17-009	887 BUNTING AVE
193	2945-114-21-951	1350 N 7TH ST
194	2945-114-19-002	815 GLENWOOD AVE
195	2945-114-16-004	745 BUNTING AVE
196	2945-114-19-001	805 GLENWOOD AVE
197	2945-114-16-016	1204 N 7TH ST
198	2945-114-17-002	815 BUNTING AVE
199	2945-114-18-003	751 GLENWOOD AVE
200	2945-114-17-003	825 BUNTING AVE
201	2945-114-16-005	739 BUNTING AVE
202	2945-114-17-005	843 BUNTING AVE
203	2945-114-19-004	835 GLENWOOD AVE
204	2945-114-16-001	769 BUNTING AVE
205	2945-114-18-005	727 GLENWOOD AVE
206	2945-114-18-002	759 GLENWOOD AVE
207	2945-114-17-015	824 GLENWOOD AVE
208	2945-114-17-016	814 GLENWOOD AVE
209	2945-114-17-004	833 BUNTING AVE
210	2945-114-16-013	740 GLENWOOD AVE

Mesa State College – Program Plan, West Expansion Property Acquisition Project

211	2945-114-16-002	757 BUNTING AVE
212	2945-114-17-007	859 BUNTING AVE
213	2945-114-17-001	805 BUNTING AVE
214	2945-114-18-004	733 GLENWOOD AVE
215	2945-114-15-030	730 BUNTING AVE
216	2945-114-18-006	705 GLENWOOD AVE
217	2945-114-15-026	740 BUNTING AVE
218	2945-114-16-007	1236 N 7TH ST
219	2945-114-16-015	760 GLENWOOD AVE
220	2945-114-15-022	804 BUNTING AVE
221	2945-114-17-950	875 BUNTING AVE
222	2945-114-10-953	1704 N 8TH ST
223	2945-114-10-954	

APPENDIX C
THIRD PARTY REVIEW

APPENDIX D
CCHE FORM CC-C

B

A TRACT OF LAND ENCOMPASSING ALL THAT REAL PROPERTY PREVIOUSLY SUBDIVIDED AS LOT 1, BLOCK 1 OF ELAM SUBDIVISION, A SUBDIVISION RECORDED AS RECEPTION NUMBER 2261431 IN THE RECORDS OF THE OFFICE OF THE MESA COUNTY CLERK AND RECORDER, LOT 1 OF ELAM II SUBDIVISION, A SUBDIVISION RECORDED AS RECEPTION NUMBER 2455622, SAID MESA COUNTY RECORDS, BLOCKS 1, 2, 3, 4, 5 AND 6, MCMULLIN & GORMLEY SUBDIVISION, A SUBDIVISION RECORDED AS RECEPTION NUMBER 349926, SAID MESA COUNTY RECORDS, BLOCKS 1, 2, 3, 4, 5 AND 6, GARFIELD PARK SUBDIVISION, ACCORDING TO THE RE-FILED PLAT THEREOF, A SUBDIVISION RECORDED AS RECEPTION NUMBER 444756, SAID MESA COUNTY RECORDS, LOTS 1 THROUGH 38, INCLUSIVE AND LOT 40, SOUTH GARFIELD PARK SUBDIVISION, A SUBDIVISION RECORDED AS RECEPTION NUMBER 539508, SAID MESA COUNTY RECORDS, MESA COLLEGE CAMPUS SUBDIVISION, A SUBDIVISION RECORDED AT RECEPTION NUMBER 459010, SAID MESA COUNTY RECORDS, TOGETHER WITH THOSE RIGHTS-OF-WAY AND ALLEY WAYS DEDICATED BY THE ABOVE REFERENCED SUBDIVISION PLATS AND VACATED BY THOSE CITY OF GRAND JUNCTION ORDINANCES NUMBERED 1120, 1299, 1675, 2913, 3356, 3759, 4106, 4252, 4431, 4590 AND 4628, ALL IN THE SOUTHEAST QUARTER OF SECTION 11, TOWNSHIP 1 SOUTH, RANGE 1 WEST OF THE UTE MERIDIAN, CITY OF GRAND JUNCTION, COUNTY OF MESA, STATE OF COLORADO

AREA = 73.848 ACRES +/-
Sheet 1 of 3

KNOW ALL MEN BY THESE PRESENTS THAT COLORADO MESA UNIVERSITY IS THE OWNER OF THAT REAL PROPERTY DESCRIBED AS FOLLOWS;

A TRACT OF LAND ENCOMPASSING ALL THAT REAL PROPERTY PREVIOUSLY SUBDIVIDED AS LOT 1, BLOCK 1 OF CLAM SUBDIVISION, A SUBDIVISION RECORDED AS RECEPTION NUMBER 2281431 IN THE RECORDS OF THE OFFICE OF THE MESA COUNTY CLERK AND REORDER, LOT 1 OF CLAM II SUBDIVISION, A SUBDIVISION RECORDED AS RECEPTION NUMBER 2455622, SAID CLAM II SUBDIVISION, SAID BLOCK 1 OF CLAM II SUBDIVISION, SAID LOT 1 OF CLAM II SUBDIVISION, SAID RECEPTION NUMBER 349286, SAID MESA COUNTY RECORDS, BLOCKS 1, 2, 3, 4, 5 AND 6, GARFIELD PARK SUBDIVISION, ACCORDING TO THE RE-FLIP PLAT THEREOF, A SUBDIVISION RECORDED AS RECEPTION NUMBER 447456, SAID MESA COUNTY RECORDS, LOTS 1 THROUGH 38, INCLUSIVE AND LOT 40, SOUTH GARFIELD PARK SUBDIVISION, A SUBDIVISION RECORDED AS RECEPTION NUMBER 447456, SAID MESA COUNTY RECORDS, LOTS 1 THROUGH 38, INCLUSIVE AND LOT 40, SOUTH GARFIELD PARK SUBDIVISION, A SUBDIVISION RECORDED AS RECEPTION NUMBER 459010, SAID MESA COUNTY RECORDS, TOGETHER WITH THOSE RIGHTS-OF-WAY AND ALLEYS VACATED DEDICATED BY THE ABOVE REFERENCED SUBDIVISION PLATS AND VACATED BY THOSE CITY OF GRAND JUNCTION ORDINANCES NUMBERED 1120, 1289, 1675, 1701, 3396, 3759, 4106, 4252, 5311, 4590, AND 4626, ALL IN THE SOUTHEAST QUARTER OF SECTION 11, TOWNSHIP 14 NORTH, RANGE 11E, MERIDIAN, CITY OF GRAND JUNCTION, COUNTY OF MESA, STATE OF COLORADO, BEING THE FULL AND COMPLETE DESCRIPTION AS FOLLOWS:

7. THEREFORE, AT THE SOUTHEAST CORNER OF SAID SECTION AND CONSIDERING THE SOUTH LINE OF SAID SECTION 11 TO BEAR NORTH 89°31'39" WEST, WITH ALL BEARINGS CONTAINED HEREIN RELATIVE THERETO; THENCE NORTH 89°31'39" WEST, ALONG SAID SOUTH LINE, SAID LINE BEING ALSO THE CENTERLINE OF NORTH AVENUE, A DISTANCE OF 40.50 FEET; THENCE NORTH 00°03'55" EAST, A DISTANCE OF 40.00 FEET TO A POINT AT THE INTERSECTION OF THE NORTHERLY RIGHT-OF-WAY LINE OF SAID NORTH AVENUE AND THE WESTERLY RIGHT-OF-WAY LINE OF 12TH STREET AND THE SOUTHERLY RIGHT-OF-WAY LINE OF SAID NORTH 89°31'39" WEST, ALONG SAID NORTHERLY RIGHT-OF-WAY LINE, A DISTANCE OF 121.14 FEET TO A POINT AT THE INTERSECTION OF SAID NORTHERLY RIGHT-OF-WAY LINE OF SAID NORTH AVENUE AND THE WESTERLY RIGHT-OF-WAY LINE OF 12TH STREET AND THE SOUTHERLY RIGHT-OF-WAY LINE OF SAID NORTH 89°31'39" WEST, ALONG SAID WESTERLY RIGHT-OF-WAY LINE THE FOLLOWING FOUR (4) COURSES:

- (1) NORTH 00°06'37" WEST, A DISTANCE OF 137.85 FEET;
- (2) NORTH 14°07'49" WEST, A DISTANCE OF 51.60 FEET;
- (3) NORTH 26°38'21" WEST, A DISTANCE OF 27.99 FEET;
- (4) NORTH 00°06'37" WEST, A DISTANCE OF 100.11 FEET TO THE SOUTHWEST CORNER OF LOT 26, SAID BLOCK 3, MCWILLIAMS AND GORMLEY SUBDIVISION;

DISTANCE NORTH 89°37'31" EAST, ALONG THE SOUTH LINE OF SAID LOT 26 AND THE EASTERLY EXTENSION THEREOF, A DISTANCE OF 131.72 FEET TO THE CENTERLINE OF THAT ALLEY VACATED PER SAID ORDINANCE NUMBER 4431; THENCE NORTH 00°31'17" WEST, ALONG THE CENTERLINE OF SAID VACATED ALLEY, A DISTANCE OF 123.10 FEET TO A POINT AT THE INTERSECTION OF SAID CENTERLINE AND THE EASTERLY EXTENSION OF THE NORTH LINE OF LOT 30, SAID BLOCK 3, MCWILLIAMS AND CORMELEY SUBDIVISION; THENCE SOUTH 89°58'44" WEST, ALONG SAID NORTH LINE AND THE EASTERLY EXTENSION THEREOF, A DISTANCE OF 131.84 FEET TO THE NORTHWEST CORNER OF SAID LOT 30 AND SAID EASTERLY RIGHT-OF-WAY LINE OF SAID ELM AVENUE; THENCE SOUTH 89°58'42" WEST, ALONG SAID NORTH LINE AND THE EASTERLY EXTENSION THEREOF, A DISTANCE OF 190.22 FEET TO A POINT AT THE INTERSECTION OF SAID NORTHERLY EXTENSION OF THE WESTERLY LINE OF BLOCK 3 AND THE SOUTHERLY EXTENSION OF THE WESTERLY LINE OF BLOCK 2, SAID MCWILLIAMS AND CORMELEY SUBDIVISION; THENCE NORTH 00°04'38" WEST, ALONG THE WESTERLY LINE OF SAID BLOCK 2 AND THE SOUTHERLY AND NORTHERLY EXTENSIONS THEREOF AND CONTINUING ALONG SAID EASTERLY RIGHT-OF-WAY LINE OF SAID ELM AVENUE, A DISTANCE OF 277.37 FEET; THENCE NORTH, CONTINUING ALONG SAID EASTERLY LINE OF SAID ELM AVENUE SUBDIVISION AND ALONG THE EASTERLY LINE OF NELMS SUBDIVISION, A SUBDIVISION RECORDED AT RECEPTION NO. 367856, SAID MESA COUNTY RECORDS, NORTH 00°21'30" WEST, A DISTANCE OF 308.07 FEET TO THE SOUTH RIGHT-OF-WAY LINE OF TEXAS AVENUE; THENCE NORTH 89°58'24" EAST, ALONG THE NORTHERLY LINE OF SAID VACATED CANNELL AVENUE, A DISTANCE OF 80.00 FEET TO THE SOUTHWESTERLY CORNER OF THAT PORTION OF CANNELL AVENUE VACATED BY CITY OF MESA ORDINANCE NO. 4288, RECORDED AT RECEPTION NO. 2688887, SAID MESA COUNTY RECORDS, NORTH 00°04'38" WEST, A DISTANCE OF 277.37 FEET; THENCE NORTHERLY, CONTINUING ALONG SAID EASTERLY LINE OF SAID ELM AVENUE SUBDIVISION AND ALONG THE EASTERLY LINE OF NELMS SUBDIVISION, A SUBDIVISION RECORDED AT RECEPTION NO. 367856, SAID MESA COUNTY RECORDS, NORTH 00°21'30" WEST, A DISTANCE OF 308.07 FEET TO THE SOUTH RIGHT-OF-WAY LINE OF TEXAS AVENUE; THENCE NORTH 89°58'24" EAST, ALONG THE NORTHERLY LINE OF SAID VACATED CANNELL AVENUE, A DISTANCE OF 80.00 FEET TO THE SOUTHWESTERLY CORNER OF THAT PORTION OF CANNELL AVENUE VACATED BY CITY OF MESA ORDINANCE NO. 4288, RECORDED AT RECEPTION NO. 2688887, SAID MESA COUNTY RECORDS, NORTH 00°04'38" WEST, ALONG THE WESTERLY LINE OF SAID VACATED PORTION OF CANNELL AVENUE, A DISTANCE OF 2.82 FEET; THENCE CONTINUING ALONG SAID WESTERLY LINE, NORTH 30°48'28" EAST, A DISTANCE OF 58.28 FEET TO THE EASTERLY RIGHT-OF-WAY LINE OF CANNELL AVENUE; THENCE NORTH 00°12'21" WEST, ALONG THE WESTERLY LINE OF BLOCKS 2, 3 AND 6 OF SAID GARFIELD PARK SUBDIVISION AND ALONG SAID EASTERLY RIGHT-OF-WAY LINE OF CANNELL AVENUE, A DISTANCE OF 830.71 FEET TO THE SOUTHERLY RIGHT-OF-WAY LINE OF ORCHARD AVENUE; THENCE SOUTH 89°58'42" EAST, ALONG SAID SOUTHERLY RIGHT-OF-WAY LINE OF ORCHARD AVENUE, A DISTANCE OF 80.00 FEET TO THE SOUTHWESTERLY CORNER OF SAID BLOCK 2, SAID MCWILLIAMS AND CORMELEY SUBDIVISION, A DISTANCE OF 1248.02 FEET TO THE WESTERLY RIGHT-OF-WAY LINE OF 12TH STREET; THENCE SOUTH 00°02'58" WEST, ALONG SAID WESTERLY RIGHT-OF-WAY LINE, SAID LINE BEING ALSO THE EAST LINE OF BLOCKS 1, 4 AND 5 OF GARFIELD PARK SUBDIVISION AND THE EAST LINE OF SAID SOUTH GARBELD PARK SUBDIVISION AND THE SOUTHERLY EXTENSION THEREOF, A DISTANCE OF 1285.41 FEET; THENCE SOUTH 89°45'08" WEST, A DISTANCE OF 0.50 FEET TO A POINT ON THE NORTHERLY EXTENSION OF THE EAST LINE OF SAID GARFIELD PARK SUBDIVISION; THENCE SOUTH 00°03'55" EAST, ALONG SAID EAST LINE AND THE NORTHERLY EXTENSION THEREOF AND ALONG SAID WESTERLY RIGHT-OF-WAY LINE OF 12TH STREET, A DISTANCE OF 1276.38 FEET TO THE

CONTAINING 73,848 ACRES OR 3,218,833 SQUARE FEET, MORE OR LESS.

SAID OWNER HAS BY THESE PRESENTS LAID OUT, PLATTED AND SUBDIVIDED THE ABOVE-DESCRIBED REAL PROPERTY INTO A LOT, AND A BLOCK AS SHOWN HEREON, AND DESIGNATED THE SAME AS "COLORADO MESA UNIVERSITY SUBDIVISION", IN THE CITY OF GRAND JUNCTION, COUNTY OF MESA, STATE OF COLORADO.

ALL STREETS, ROADS AND RIGHTS-OF-WAY ARE DEDICATED TO THE CITY OF GRAND JUNCTION FOR THE USE OF THE PUBLIC FOREVER.

ALL UTILITY EASEMENTS ARE DEDICATED TO THE CITY OF GRAND JUNCTION AS PERPETUAL EASEMENTS FOR CITY APPROVED UTILITIES INCLUDING THE INSTALLATION, OPERATION, MAINTENANCE AND REPAIR OF SAID UTILITIES AND APPURTENANCES WHICH MAY INCLUDE BUT ARE NOT LIMITED TO ELECTRIC LINES, CABLE TV LINES, NATURAL GAS PIPELINES, SANITARY SEWER LINES, STORM SEWERS, WATER LINES, TELEPHONE LINES, EQUIVALENT OTHER PUBLIC UTILITY PROVIDERS AND APPURTENANT FACILITIES.


INGRESS-EGRESS EASEMENTS SHOWN HEREON ARE HEREBY DEDICATED TO THE CITY OF GRAND JUNCTION AS PERPETUAL NON-EXCLUSIVE EASEMENTS FOR PUBLIC INGRESS AND EGRESS.

ALL TRACTS/EASEMENTS INCLUDE THE RIGHT OF INGRESS AND EGRESS ON, ALONG, OVER, UNDER, THROUGH AND ACROSS BY THE BENEFICIARIES/HEIR SUCCESSORS, OR ASSIGNS, TOGETHER WITH THE RIGHT TO TRIM OR REMOVE INTERFERING TREES AND BUSHES, IN, DRAINAGE, DETENTION/RETENTION EASEMENTS OR TRACTS, THE RIGHT TO DREDGE, PROVIDED, HOWEVER, THAT THE BENEFICIARIES/OWNERS SHALL UTILIZE THE SAME IN A REASONABLE AND PRUDENT MANNER. FURTHERMORE, THE OWNERS OF SAID LOTS OR TRACTS HEREBY PLATTED SHALL NOT BURDEN OR OVERTURDEN SAID EASEMENTS BY DRECTING OR PLACING ANY IMPROVEMENTS THEREON WHICH MAY IMPED THE USE OF THE EASEMENT AND/OR PREVENT THE REASONABLE INGRESS AND EGRESS TO AND FROM THE EASEMENT. SURFACE USE WITHIN THE UTILITY EASEMENTS DEDICATED HEREOF SHALL LIMITED TO DOD, ASPHALT OR GRAVEL.

OWNER HEREBY DECLARES THERE ARE NO LIEN HOLDERS OF RECORD FOR THE HEREIN DESCRIBED PROPERTY.

IN WITNESS WHEREOF, SAID OWNER HAS CAUSED ITS NAME TO BE HEREUNTO DESCRIBED THIS _____ DAY
OF _____, A.D. 2016.

BY: TIM FOSTER
PRESIDENT, COLORADO MESA UNIVERSITY



Vicinity Map
No Scale

[illegible]

STATE OF COLORADO }
COUNTY OF MESA } SS

THE FOREGOING INSTRUMENT WAS ACKNOWLEDGED BEFORE ME BY TIM FOSTER AS PRESIDENT OF COLORADO MESA UNIVERSITY.

THIS _____ DAY OF _____, A.D. 2015

WITNESS MY HAND AND OFFICIAL SEAL: _____

NOTARY PUBLIC

NY COMMISSION EXPIRES:

1. *NOTICE: ACCORDING TO COLORADO LAW YOU MUST COMMENCE ANY LEGAL ACTION BASED UPON ANY DEFECT IN THIS SURVEY WITHIN THREE YEARS AFTER YOU FIRST DISCOVER SUCH DEFECT. IN NO EVENT, MAY ANY ACTION BASED UPON ANY DEFECT IN THIS SURVEY BE COMMENCED MORE THAN TEN YEARS FROM THE DATE OF THE CERTIFICATION SHOWN HEREON*.

2. THE BEARINGS AS SHOWN HEREON ARE BASED UPON THE CONSIDERATION THAT THE SOUTH LINE OF SECTION 11, TOWNSHIP 1 SOUTH, RANGE 1 WEST OF THE UTE MERIDIAN IS CONSIDERED TO BEAR NORTH 89°51'39" WEST. SAID LINE IS MONUMENTED AS SHOWN HEREON.

3. THE UNDERSIGNED HAS RELED, IN PART, UPON ABSTRACT & TITLE CO. OF MESA COUNTY, INC., COMMITMENT TO INSURE, COMMITMENT NUMBER ABA 107001232 HAVING AN EFFECTIVE DATE OF JUNE 2, 2008 AT 7:00 A.M., FOR OWNERSHIP INFORMATION USED IN DEVELOPING THE BOUNDARY OF THE HEREON DESCRIBED PARCEL. ADDITIONAL INFORMATION PERTAINING TO OWNERSHIP HAS BEEN PROVIDED BY THE CITY OF GRAND JUNCTION AND COLORADO MESA UNIVERSITY. THE SURVEY DOES NOT CONSTITUTE A TITLE SEARCH BY DREXEL, BARRELL & CO., TO DETERMINE OWNERSHIP AND EASEMENTS OF RECORD.

RECORDED EASEMENTS AND RIGHTS-OF-WAY WITHIN THE BOUNDARY OF THE HEREDIN DESCRIBED PARCEL HAVE NOT BEEN SHOWN PENDING COMPLETION OF A FORMAL AGREEMENT BETWEEN COLORADO MESA UNIVERSITY AND THE CITY OF GRAND JUNCTION VACATING ALL PRIOR EASEMENTS OF RECORD.

4. FOR THE PURPOSES OF THE SURVEY OF THIS SUBDIVISION THE CENTERLINE OF NORTH AVENUE IS CONSIDERED TO BE THE SOUTH LINE OF SECTION 11 RUNNING BETWEEN MESA COUNTY SURVEY MARKER No. P032 AT THE SOUTHEAST CORNER, WESTERLY TO MESA COUNTY SURVEY MARKER No. P033 AT THE SOUTHWEST CORNER.

3. DIMENSIONS SHOWN ON THE SURVEY AND DENOTED WITH AN "M" INDICATE RECORD DIMENSIONS BASED UPON INFORMATION CONTAINED IN THE CITY OF GRAND RAPIDS ELECTRICAL DEPARTMENT RECORDS PERTAINING TO CITY MONUMENT STUDY AND TO THE PLAT OF CARFIELD PARK SUBDIVISION, ACCORDING TO THE RETILING PLAT THEREOF, RECORDED IN BOOK 7 AT PAGE 9, THE PLAT OF SOUTH CARFIELD PARK SUBDIVISION, RECORDED IN BOOK 7 AT PAGE 84, THE PLAT OF MULLHILL & CORNLEY SUBDIVISION, RECORDED IN BOOK 8 AT PAGE 3 AND THE PLAT OF MESA COLLEGE CAMPUS, RECORDED IN BOOK 7 AT PAGE 28, ALL IN THE RECORDS OF THE OFFICE OF THE CLERK AND RECORDER OF MESA COUNTY. (refer to legend on sheet 2)

6. THE LINEAL DIMENSIONS AS SHOWN HEREON ARE IN U.S. SURVEY FEET.

I, PATRICK C. O'HEARN, A REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF COLORADO, DO HEREBY CERTIFY THAT THIS SUBDIVISION PLAT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION, AND THAT IT IS ACCURATE TO THE BEST OF MY KNOWLEDGE AND BELIEF AND IS IN COMPLIANCE WITH THE APPLICABLE LAWS AND REGULATIONS OF THE STATE OF COLORADO PERTAINING TO LAND SURVEYING. THIS CERTIFICATION IS NOT A GUARANTEE OR WARRANTY, EITHER EXPRESSED OR IMPLIED.

PATRICK C. O'HEARN, P.L.S. 23515
COLORADO LICENSED PROFESSIONAL LAND SURVEYOR
FOR AND ON BEHALF OF DREXEL, BARRELL & CO.

WE, ~~XXXXXXXXXXXXXXXXXXXXXXXXXXXX~~, A TITLE INSURANCE COMPANY, AS DULY LICENSED IN THE STATE OF COLORADO, HEREBY CERTIFY THAT WE HAVE EXAMINED THE TITLE TO THE HEREON DESCRIBED PROPERTY, THAT WE FIND THE TITLE TO THE PROPERTY IS VESTED TO COLORADO MESA UNIVERSITY, THAT THE CURRENT TAXES HAVE BEEN PAID; THAT ALL MORTGAGES NOT SATISFIED OR RELEASED OF RECORD NOR OTHERWISE TERMINATED BY LAW ARE SHOWN HEREON AND THAT THERE ARE NO OTHER ENCUMBRANCES OF RECORD, THAT ALL EASEMENTS, RESERVATIONS AND RIGHT-OF-WAYS OF RECORD ARE SHOWN HEREON.

DATE: _____ BY: _____

TITLE: _____

THIS PLAT OF COLORADO MESA UNIVERSITY SUBDIVISION, A SUBDIVISION IN THE CITY OF GRAND JUNCTION, COUNTY OF MESA,
STATE OF COLORADO IS APPROVED AND ACCEPTED ON THE _____ DAY OF _____, A.D. 2018.

CITY MANAGER _____ PRESIDENT, CITY COUNCIL _____

STATE OF COLORADO }
COUNTY OF MESA } SS

I HEREBY CERTIFY THAT THIS INSTRUMENT WAS FILED FOR RECORDING IN MY OFFICE
AT _____ O'CLOCK _____ THIS _____ DAY OF _____ A.D. 2018
AND IS DULY RECORDED IN BOOK NO. _____ AT PAGE _____
RECEPTION NO. _____ : DRAWER NO. _____ : FEE \$ _____

CLERK AND RECORDER BY: DEPUTY

Sheet 1 - Description, Dedication, Notes and Certificates
Sheet 2 - Plat Graphic / Subdivision Boundary
Sheet 3 - Plat Graphic / Easement Dedications



Drexel, Barrell & Co. Engineers/Surveyors
 1800 10TH STREET BOULDER, COLORADO 80501 (303) 442-4385


3 DUWY 7TH STREET CHANDLER SPRING CHANDLER 85006		(719) 505-0017	
SILVER BURDETT G AND GARDNER (SINGLES)			
Revisions - Date	Date	Drawn By	Job No.
3-8-15 / revised recorded addendum	11-08-14	IT/PCO	20219-02
	Scale	Checked By	Drawing No.
	1/4"	PCO	

COLORADO MESA UNIVERSITY SUBDIVISION
LOCATED IN THE SE 1/4 OF SECTION 11, TOWNSHIP
1 SOUTH, RANGE 1 WEST OF THE UTE MERIDIAN,
CITY OF GRAND JUNCTION, COUNTY OF MESA,
STATE OF COLORADO.

COLORADO MESA UNIVERSITY SUBDIVISION

A TRACT OF LAND ENCOMPASSING ALL THAT REAL PROPERTY PREVIOUSLY SUBDIVIDED AS LOT 1, BLOCK 1 OF ELAM SUBDIVISION, A SUBDIVISION RECORDED AS RECEPTION NUMBER 2261431 IN THE RECORDS OF THE OFFICE OF THE MESA COUNTY CLERK AND RECORDER, LOT 1 OF ELAM II SUBDIVISION, A SUBDIVISION RECORDED AS RECEPTION NUMBER 2455622, SAID MESA COUNTY RECORDS, BLOCKS 1, 2, 3, 4, 5 AND 6, MCMULLIN & GORMLEY SUBDIVISION, A SUBDIVISION RECORDED AS RECEPTION NUMBER 349926, SAID MESA COUNTY RECORDS, BLOCKS 1, 2, 3, 4, 5 AND 6, GARFIELD PARK SUBDIVISION, ACCORDING TO THE RE-FLING PLAT THEREOF, A SUBDIVISION RECORDED AS RECEPTION NUMBER 444756, SAID MESA COUNTY RECORDS, LOTS 1 THROUGH 38, INCLUSIVE AND LOT 40, SOUTH GARFIELD PARK SUBDIVISION, A SUBDIVISION RECORDED AS RECEPTION NUMBER 539508, SAID MESA COUNTY RECORDS, MESA COLLEGE CAMPUS SUBDIVISION, A SUBDIVISION RECORDED AT RECEPTION NUMBER 459010, SAID MESA COUNTY RECORDS, TOGETHER WITH THOSE RIGHTS-OF-WAY AND ALLEY WAYS DEDICATED BY THE ABOVE REFERENCED SUBDIVISION PLATS AND VACATED BY THOSE CITY OF GRAND JUNCTION ORDINANCES NUMBERED 1120, 1299, 1675, 2913, 3356, 3759, 4106, 4252, 4431, 4590 AND 4628, ALL IN THE SOUTHEAST QUARTER OF SECTION 11, TOWNSHIP 1 SOUTH, RANGE 1 WEST OF THE UTE MERIDIAN, CITY OF GRAND JUNCTION, COUNTY OF MESA, STATE OF COLORADO

AREA = 73.848 ACRES +/-
Sheet 2 of 3



COLORADO MESA UNIVERSITY SUBDIVISION
LOCATED IN THE SE 1/4 OF SECTION 11, TOWNSHIP
1 SOUTH, RANGE 1 WEST OF THE UTE MERIDIAN,
CITY OF GRAND JUNCTION, COUNTY OF MESA,
STATE OF COLORADO.



Sheet 2 of 3 - Subdivision Boundary

Drexel, Barrell & Co. Engineers/Surveyors	
1000 10TH STREET GRAND JUNCTION, COLORADO 81501 (970) 244-4300	11-08-14
Drawn By TJ/PCD	20219-02
Scale 1"=100'	Checked By PCD

COLORADO MESA UNIVERSITY SUBDIVISION

A TRACT OF LAND ENCOMPASSING ALL THAT REAL PROPERTY PREVIOUSLY SUBDIVIDED AS LOT 1, BLOCK 1 OF ELAM SUBDIVISION, A SUBDIVISION RECORDED AS RECEPTION NUMBER 2261431 IN THE RECORDS OF THE OFFICE OF THE MESA COUNTY CLERK AND RECORDER, LOT 1 OF ELAM II SUBDIVISION, A SUBDIVISION RECORDED AS RECEPTION NUMBER 2455622, SAID MESA COUNTY RECORDS, BLOCKS 1, 2, 3, 4, 5 AND 6, MCMULLIN & GORMELY SUBDIVISION, A SUBDIVISION RECORDED AS RECEPTION NUMBER 349926, SAID MESA COUNTY RECORDS, BLOCKS 1, 2, 3, 4, 5 AND 6, GARFIELD PARK SUBDIVISION, ACCORDING TO THE RE-FILING PLAT THEREOF, A SUBDIVISION RECORDED AS RECEPTION NUMBER 444756, SAID MESA COUNTY RECORDS, LOTS 1 THROUGH 38, INCLUSIVE AND LOT 40, SOUTH GARFIELD PARK SUBDIVISION, A SUBDIVISION RECORDED AS RECEPTION NUMBER 539508, SAID MESA COUNTY RECORDS, MESA COLLEGE CAMPUS SUBDIVISION, A SUBDIVISION RECORDED AT RECEPTION NUMBER 459010, SAID MESA COUNTY RECORDS, TOGETHER WITH THOSE RIGHTS-OF-WAY AND ALLEY WAYS DEDICATED BY THE ABOVE REFERENCED SUBDIVISION PLATS AND VACATED BY THOSE CITY OF GRAND JUNCTION ORDINANCES NUMBERED 1120, 1299, 1675, 2913, 3356, 3759, 4106, 4252, 4431, 4590 AND 4628, ALL IN THE SOUTHEAST QUARTER OF SECTION 11, TOWNSHIP 1 SOUTH, RANGE 1 WEST OF THE UTE MERIDIAN, CITY OF GRAND JUNCTION, COUNTY OF MESA, STATE OF COLORADO

AREA = 73.848 ACRES +/-
Sheet 3 of 3



Easement Dedications
1) Unless indicated otherwise, all easements shown are Utility Easements to the City of Grand Junction for City approved utilities.

COLORADO MESA UNIVERSITY SUBDIVISION
LOCATED IN THE SE 1/4 OF SECTION 11, TOWNSHIP 1 SOUTH, RANGE 1 WEST OF THE UTE MERIDIAN, CITY OF GRAND JUNCTION, COUNTY OF MESA, STATE OF COLORADO.

Sheet 3 of 3 - Easement Dedications			
Drexel, Barrell & Co. Engineers/Surveyors			
1004 SOUTH STREET GRAND JUNCTION, COLORADO 81501	1004 SOUTH STREET GRAND JUNCTION, COLORADO 81501	(303) 448-4338 (714) 368-8887	
Revised: - Date	Date	Drawn By	Job No.
11-08-14	11-08-14	TI/PCD	20219-02
Scale	Checked By	Drawing No.	
1"=100'	PCD		

CITY OF GRAND JUNCTION, COLORADO

ORDINANCE NO. _____

**AN ORDINANCE VACATING A PORTION OF ALLEY RIGHT-OF-WAY LOCATED
BETWEEN ORCHARD AVENUE AND HALL AVENUE ON THE SOUTH SIDE OF
THE PROPERTY LOCATED AT 845 ORCHARD AVENUE**

RECITALS:

Colorado Mesa University has requested to vacate a portion of alley right-of-way located between Orchard Avenue and Hall Avenue on the south side of the property located at 845 Orchard Avenue in order to enable the continued westward expansion efforts planned for the campus, specifically in the future to develop a new track and field sports venue.

Colorado Mesa University is under contract to acquire the 845 Orchard Avenue property. City staff does not expect that the proposed right-of-way vacations would impede traffic, pedestrian movement or access to private property. As conditions of approval, CMU will need to demonstrate ownership of the property at 845 Orchard Avenue prior to recording the vacation ordinance and meet all Grand Junction Fire Department requirements for construction of the proposed campus facilities.

Presently, the segment of alley right-of-way requested to be vacated contains a City public sewer line as well as Xcel electric and gas infrastructure. The existing electric utilities will be moved and relocated by Xcel Energy as part of the construction of the new track and field sports venue and an appropriate easement to Xcel Energy will be dedicated at that time, if necessary. Applicant is also required to meet all terms and conditions of the *Colorado Mesa University and City of Grand Junction Utility Easement and Maintenance Agreement-CMU Main Campus* and any requirements of the Grand Junction Fire Department.

The City Council finds that the request is consistent with the Comprehensive Plan, the Grand Valley Circulation Plan and Section 21.02.100 of the Grand Junction Zoning and Development Code.

The Planning Commission, having heard and considered the requests, found the criteria of the Code to have been met, and recommended that the portion of east-west alley right-of-way adjacent to the south side of the property located at 845 Orchard Avenue be approved.

**NOW, THEREFORE BE IT ORDAINED BY THE CITY COUNCIL OF THE CITY OF
GRAND JUNCTION THAT:**

The following described dedicated alley right-of-way is hereby vacated subject to the listed conditions:

A Portion of Alley Right-of-Way as dedicated on the plat Mesa Subdivision as recorded at Reception Number 449854 of the Mesa County Records, situated in the Southeast Quarter of Section 11, Township 1 South, Range 1 West of Ute Meridian, County of Mesa, State of Colorado; being more particularly described as follows:

All of the Alley Right-of-Way lying West of the Southerly projection of the East line of Lot 8, Block 2 of said Mesa Subdivision and East of the of the Southerly projection of the East line of Lot 6, Block 2 of said Mesa Subdivision.

Containing an area of 2,348 square feet (0.054 acres) more or less, as described herein and on Exhibit A.

Conditions of Approval:

1. Applicant shall provide evidence of ownership of the property located at 845 Orchard Avenue (parcel number 2945-114-08-006) prior to this Ordinance being recorded with the Mesa County Clerk and Recorder in order for the vacation to take effect.
2. Applicant shall pay all recording/documentary fees for the Vacation Ordinance.
3. Applicant shall meet all terms and conditions of the *Colorado Mesa University and City of Grand Junction Utility Easement and Maintenance Agreement-CMU Main Campus* and all requirements of the Grand Junction Fire Department for construction of proposed campus facilities.

Introduced for first reading on this _____ day of _____, 2019 and ordered published in pamphlet form.

PASSED and ADOPTED this _____ day of _____, 2019 and ordered published in pamphlet form.


ATTEST:

President of City Council

City Clerk

EXHIBIT A

SOUTHEAST 1/4 OF SECTION 11,
TOWNSHIP 1 SOUTH, RANGE 1 WEST, UTE MERIDIAN,
CITY OF GRAND JUNCTION, COUNTY OF MESA, STATE OF COLORADO



*This Exhibit is not intended to be used for establishing or
verifying property boundary lines.

*Linear units are in U.S. Survey Feet.